

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	64A-01-93M	1993	3	12

GENERAL NOTES:

1. The scope of work for this project consists of constructing a truck off-loading area which includes removing a concrete traffic barrier, a sidewalk, and fences; grading; constructing a wheelchair ramp; striping; installing new fences, gates, signs, and an impact attenuator.

2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.

3. The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 - Public Convenience and Safety, Subsection 107.21 - Contractor's Responsibility for Utility Property and Services, Subsection 108.02 - Notice to Proceed and Section 645 - Traffic Control.

4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.

5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.

6. The Contractor shall notify the State in writing, two (2) weeks prior to starting paving operations.

7. Smooth riding connections shall be constructed at all limits of resurfacing including the beginning and end of project, connecting approaches, side streets and driveways as shown on the plans and/or as directed by the Engineer.

8. Dressing of shoulder, sidewalk and bus turnout shall consist of clearing, grubbing, grading, reshaping and compacting the unpaved shoulders with suitable excavated material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.
9. Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to the various contract items.

10. Earth swale shall be graded to drain. This work shall be considered incidental to the various contract items.

11. Contact David Shimokawa of the State Airports Property Management Branch at 836-6577 to coordinate moving of existing vehicles on the project site.

12. Removal and disposal of existing concrete traffic barrier, sidewalk and fences shall be paid for under Item No. 202.01 - Removal of Structures and Obstructions.

13. The Contractor shall install and relocate all chain link fencing and gates (install new 8 ft. high and 25 ft. wide, gate only) prior to commencing any other work. Temporary gates shall also be installed at the entrance and exit of the truck off-loading area to provide security for the project site and adjacent properties. Temporary gates shall be considered incidental to 8 ft. chain link fence. Relocation of existing fence and gate shall be considered incidental to 6 ft. chain link fence.

14. The Contractor shall provide dust control measures to prevent excessive dust and flying debris from damaging vehicles in adjacent properties. Dust control measures shall be considered incidental to roadway excavation.

15. The Contractor shall be held liable for any damages incurred to the vehicles, in the adjacent properties, as a result of his operations.

LEGEND

- Resurfacing Limits
- °lp

Existing Light Pole
- °pp

Existing Power Pole
- fm 24"—

Existing Sewer Line
- d 24"—

Existing Drain Line
- w 12"—

Existing Water Line
- S 10"—

Proposed Sewer Line (By Others)
- °SMH

Proposed Sewer Manhole (By Others)
- °sdmh

Existing Storm Drain Manhole
- cb

Existing Catch Basin

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOT MARKED	DRAWN BY	
DESIGNED BY		
QUANTITIES BY		
CHECKED BY		

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION	
GENERAL NOTES AND LEGEND	
SAND ISLAND ACCESS ROAD Weigh Station Off-Loading Area Project No. 64A-01-93M	
Scale: As Noted	Date: May, 1993
SHEET No. 1 OF 1 SHEETS	