

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
203.0010	Roadway Excavation for Temporary Pavement	230	Cu. Yd.	\$ _____	\$ _____
203.0100	Roadway Excavation	4,100	Cu. Yd.	\$ _____	\$ _____
203.0110	Borrow Excavation	1,010	Cu. Yd.	\$ _____	\$ _____
206.2020	Structure Excavation for Drainage Systems	2,369	Cu.Yd.	\$ _____	\$ _____
206.7001	Structural Excavation for Retaining Walls	2,146	Cu.Yd.	\$ _____	\$ _____
206.7002	Structural Backfill for Retaining Walls	1,629	Cu. Yd.	\$ _____	\$ _____
206.7003	Filter Material for Retaining Walls	98	Cu. Yd.	\$ _____	\$ _____
209.1000	Water Pollution and Erosion Control	F.A.	F.A.	F.A.	\$50,000.00
305.1000	Aggregate Subbase for Temporary Pavement	115	Cu. Yd.	\$ _____	\$ _____
305.1110	Aggregate Subbase	1,640	Cu. Yd.	\$ _____	\$ _____
306.1000	Untreated Permeable Base Course	690	Cu. Yd.	\$ _____	\$ _____
312.0001	Plant Mix Glassphalt Concrete Base Course for Temporary Pavement	160	Tons	\$ _____	\$ _____
312.1000	Plant Mix Glassphalt Concrete Base Course	2,950	Tons	\$ _____	\$ _____

STP-065-1(9)

02/07/03

P-8

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
401.1000	Asphalt Concrete Pavement, Mix No. IV for Temporary Pavement	80	Tons	\$ _____	\$ _____
402.0001	Superpave Asphalt Concrete Pavement	1,840	Tons	\$ _____	\$ _____
402.0600	Pavement Smoothness Incentive	allowance	allowance	allowance	\$12,000.00
411.1212	13-Inch Reinforced Concrete Pavement for bus bay	58	Cu. Yd.	\$ _____	\$ _____
503.0001	Reinforced Concrete Jacket for 8 inch waterline	452	Lin. Ft.	\$ _____	\$ _____
503.1200	Driveway Culverts	156	Lin. Ft.	\$ _____	\$ _____
503.1210	Reinforced Concrete Jacket for culvert	173	Lin. Ft.	\$ _____	\$ _____
503.1310	Concrete in Footings in CMU Wall (38 Cu. Yd.)	L.S.	L.S.	L.S.	\$ _____
503.2010	Concrete in Retaining Walls (554 Cu. Yd.)	L.S.	L.S.	L.S.	\$ _____
513.4000	Type "L2" CMU Wall	150	Sq. Yd.	\$ _____	\$ _____
513.5000	Type "L1" CMU Wall	96	Sq. Yd.	\$ _____	\$ _____
602.1002	Reinforcing Steel in Retaining Walls (136,023 Lbs.)	L.S.	L.S.	L.S.	\$ _____
602.1003	Reinforcing Steel in CMU Wall Concrete Footings (12,573 Lbs.)	L.S.	L.S.	L.S.	\$ _____

STP-065-1(9)

02/07/03

P-9

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
603.0010	Bed Course Material for Culverts	468	Cu. Yd.	\$ _____	\$ _____
603.1008	18-Inch Reinforced Concrete Pipe, Class III or 18-Inch High Density Polyethylene Pipe (Type S), or 18-Inch Aluminum Spiral Rib Pipe, thickness = 0.105"	73	Lin. Ft.	\$ _____	\$ _____
603.1010	24-Inch Reinforced Concrete Pipe, Class III or 24-Inch High Density Polyethylene Pipe (Type S), or 24-Inch Aluminum Spiral Rib Pipe, thickness = 0.105"	2,048	Lin. Ft.	\$ _____	\$ _____
604.1000	Adjusting Water Valve Box Frame and Cover	1	Each	\$ _____	\$ _____
604.1010	Relocation of Water Meter, Water Meter Box Frame and Cover	3	Each	\$ _____	\$ _____
604.2000	Adjusting Water Valve Manhole Frame and Cover	13	Each	\$ _____	\$ _____
604.5104	Type "A" Storm Drain Manhole 4.00 to 4.99 Feet	5	Each	\$ _____	\$ _____
604.5105	Type "A" Storm Drain Manhole 5.00 to 5.99 Feet	3	Each	\$ _____	\$ _____
604.5125	Type "B-1" Catch Basin, 6.00 to 6.99 Feet	1	Each	\$ _____	\$ _____
604.5126	Type "C" Catch Basin, 4.00 to 4.99 Feet	1	Each	\$ _____	\$ _____
604.5254	Type "A-9P" Grated Drop Inlet, 4.00 to 4.99 Feet	8	Each	\$ _____	\$ _____

STP-065-1(9)

02/14/2003

P-10

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
604.5255	Type "A-9P" Grated Drop Inlet, 5.00 to 5.99 Feet	2	Each	\$ _____	\$ _____
604.5262	Type "61614P" Grated Drop Inlet, 2.00 to 2.99 Feet	2	Each	\$ _____	\$ _____
604.5274	Type "2A-9P" Grated Drop Inlet, 4.00 to 4.99 Feet	1	Each	\$ _____	\$ _____
604.5284	Special Type "A-9P" Grated Drop Inlet, 4.00 to 4.99 Feet	3	Each	\$ _____	\$ _____
605.1000	Perforated Underdrain Pipe	1,117	Lin. Ft.	\$ _____	\$ _____
605.2000	Non-Perforated Underdrain Pipe	60	Lin. Ft.	\$ _____	\$ _____
606.1000	Guardrail Type 3 Single w/Steel Post	327	Lin. Ft.	\$ _____	\$ _____
606.1001	Triton Barrier	150	Each	\$ _____	\$ _____
607.1001	4.0 Feet Chain Link Fence Without Top Rail	391	Lin. Ft.	\$ _____	\$ _____
608.1200	4-Inch Reinforced Concrete Sidewalk	1,620	Sq. Yd.	\$ _____	\$ _____
608.1300	4-Inch Reinforced Concrete Walkway	30	Sq. Yd.	\$ _____	\$ _____
608.1400	4-Inch Modified Reinforced Concrete Sidewalk	38	Sq. Yd.	\$ _____	\$ _____
609.2020	Curb, Type 2D	1,200	Lin. Ft.	\$ _____	\$ _____
609.2720	Curb and Gutter, Type 2DG	1,740	Lin. Ft.	\$ _____	\$ _____

STP-065-1(9)

02/07/03

P-11

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
609.2740	Thru Gutter	144	Lin. Ft.	\$ _____	\$ _____
610.0300	8-Inch Reinforced Concrete Driveway	110	Sq. Yd.	\$ _____	\$ _____
610.0400	6-Inch Reinforced Concrete Driveway	700	Sq. Yd.	\$ _____	\$ _____
611.1000	Hand Laid Riprap	12	Cu. Yd.	\$ _____	\$ _____
612.6410	Grouted Rubble Paving for Outlet Structures	27	Cu. Yd.	\$ _____	\$ _____
621.5000	Regulatory and Warning Signs (10 Sq. Ft. or Less)	5	Each	\$ _____	\$ _____
621.5100	Regulatory and Warning Signs (10 Sq. Ft. or Less) with Post	25	Each	\$ _____	\$ _____
621.5600	Relocation of Existing Regulatory and Warning Signs (10 Sq. Ft. or Less) with Posts	2	Each	\$ _____	\$ _____
621.7100	Construction Signs with Posts	5	Each	\$ _____	\$ _____
621.8100	Street Name Sign on Mast Arm with New Brackets	2	Each	\$ _____	\$ _____
622.1001	Street Lighting Luminaire	9	Each	\$ _____	\$ _____
622.2001	Street Lighting Luminaire with House Side Shield	7	Each	\$ _____	\$ _____
622.3001	2' x 4' Handhole	2	Each	\$ _____	\$ _____

STP-065-1(9)

02/20/2003

P-12

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
622.4001	2 - 3" C Ductline	100	Lin. Ft.	\$ _____	\$ _____
622.5001	4 - 5" C Ductline	125	Lin. Ft.	\$ _____	\$ _____
622.6001	8 - 5" C Ductline	125	Lin. Ft.	\$ _____	\$ _____
622.7001	HECO Service Charges	L.S.	L.S.	L.S.	\$ _____
622.8001	2-5" C Ductline	125	Lin. Ft.	\$ _____	\$ _____
623.2011	Type I Signal Standard	1	Each	\$ _____	\$ _____
623.2021	Type II Signal Standard with 40' - 0" Mast Arm	1	Each	\$ _____	\$ _____
623.2031	Foundation for Type I Signal Standard	1	Each	\$ _____	\$ _____
623.2041	Foundation For Type II Signal Standard with 40' - 0" Mast Arm	1	Each	\$ _____	\$ _____
623.2061	Relocate Existing Solar Power Flashing Beacon with Foundation	1	Each	\$ _____	\$ _____
623.3001	Traffic Signal Assembly (One-way, 12-Inch, 1-3 Section with Slip Fitter Mounting)	1	Each	\$ _____	\$ _____
623.3055	Traffic Signal Assembly (Two-way, 12-Inch, 2-3 Section Vertical with Bracket Mounting)	1	Each	\$ _____	\$ _____

STP-065-1(9)

02/07/03

P-13

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
623.3060	Traffic Signal Assembly (One-way, 12-Inch, 1-3 Section Vertical with Mast Arm Mounting)	2	Each	\$ _____	\$ _____
623.4040	Pedestrian Push Button with Sign	4	Each	\$ _____	\$ _____
623.5000	Traffic Signal Ductline, One 2-Inch Conduit, Schedule 80 (110 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
623.5010	Traffic Signal Ductline, Two 2-Inch Conduit, Schedule 80 (20 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
623.5050	Traffic Signal Ductline, Four 2-Inch Conduit, Schedule 40 (100 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
623.6000	Type A Pullbox	1	Each	\$ _____	\$ _____
623.6010	Type B Pullbox	3	Each	\$ _____	\$ _____
623.7040	Type 1 Traffic Control Cable (110 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
623.7042	Type 2 Loop Detector Lead-In Cable (505 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
623.7046	Type 6 Power Cable (110 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
623.7051	Loop Detector Sensing Unit (6' x 6') One Loop	12	Each	\$ _____	\$ _____
624.0020	12-Inch waterline relocation at sta 23+11	L.S.	L.S.	L.S.	\$ _____

STP-065-1(9)

02/07/03

P-14

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
624.0030	8-Inch waterline relocation at sta 23+23	L.S.	L.S.	L.S.	\$ _____
624.0040	12-Inch waterline relocation at sta 25+09	L.S.	L.S.	L.S.	\$ _____
624.0050	8-Inch waterline relocation at sta 30+20	L.S.	L.S.	L.S.	\$ _____
624.0060	8-Inch waterline relocation at sta 34+36	L.S.	L.S.	L.S.	\$ _____
624.0070	20-Inch waterline relocation at sta 34+36	L.S.	L.S.	L.S.	\$ _____
624.0090	Fire Hydrant Relocation Including All Appurtenances at Station 27+33	1	Each	\$ _____	\$ _____
629.0110	4-Inch Pavement Striping - Tape, Type I or Thermoplastic Extrusion (170 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.0120	8-Inch Pavement Striping - Tape, Type I or Thermoplastic Extrusion (320 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.0130	Double 4-Inch Pavement Striping - Tape, Type I or Thermoplastic Extrusion (420 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.0210	4-Inch Pavement Striping - Tape, Type II or Thermoplastic Extrusion (3080 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.0220	6-Inch Pavement Striping - Tape, Type II or Thermoplastic Extrusion (2400 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____

STP-065-1(9)

02/07/03

P-15

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
629.0230	8-Inch Pavement Striping - Tape, Type II or Thermoplastic Extrusion (80 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.0240	12-Inch Pavement Striping - Tape, Type II or Thermoplastic Extrusion (120 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.0250	Double 4-Inch Pavement Striping - Tape, Type II or Thermoplastic Extrusion (1500 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1010	4-Inch Pavement Striping - Tape, Type III or Thermoplastic Extrusion (680 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1017	12-Inch Pavement Striping - Tape, Type III or Thermoplastic Extrusion (90 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1021	Crosswalk Marking - Tape, Type III or Thermoplastic Extrusion	10	Lane	\$ _____	\$ _____
629.1031	Pavement Arrows - Tape, Type III or Thermoplastic Extrusion	12	Each	\$ _____	\$ _____
629.1041	Pavement Words - Tape, Type III or Thermoplastic Extrusion	6	Each	\$ _____	\$ _____
629.1051	Pavement Symbol - Paint	12	Each	\$ _____	\$ _____
629.1061	Detour 4-Inch Pavement Striping - Tape	10,100	Lin. Ft.	\$ _____	\$ _____

STP-065-1(9)

02/07/03

P-16

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
629.1062	Detour Double 4-Inch Pavement Striping - Tape	5,740	Lin. Ft.	\$ _____	\$ _____
629.2030	Type A Pavement Marker	108	Each	\$ _____	\$ _____
629.2040	Type C Pavement Marker	112	Each	\$ _____	\$ _____
629.2041	Detour Type C Pavement Marker	250	Each	\$ _____	\$ _____
629.2050	Type D Pavement Marker	21	Each	\$ _____	\$ _____
629.2051	Detour Type D Pavement Marker	200	Each	\$ _____	\$ _____
629.2060	Type H Pavement Marker	81	Each	\$ _____	\$ _____
629.2061	Detour Type H Pavement Marker	120	Each	\$ _____	\$ _____
629.2070	Type DB Pavement Marker	1	Each	\$ _____	\$ _____
636.1001	Maintenance of Field Office and Project Site Laboratory	F.A.	F.A.	F.A.	\$24,000.00
638.1000	Cellular phone (Not to exceed \$4,800 for 3 phones)	L.S.	L.S.	L.S.	\$ _____
640.1000	Grass Swale	710	Lin. Ft.	\$ _____	\$ _____
641.0100	Hydro-Mulch Seeding	28,600	Sq. Ft.	\$ _____	\$ _____

STP-065-1(9)

02/07/03

P-17

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
645.0200	Additional Police Officers and/or Additional Traffic Control Devices	F.A.	F.A.	F.A.	\$100,000.00
650.0001	Curb Ramp Type D	10	Each	\$ _____	\$ _____
650.0002	Curb Ramp Type D-1	1	Each	\$ _____	\$ _____
650.0004	Curb Ramp Type C	1	Each	\$ _____	\$ _____
650.0005	Curb Ramp Type B Modified	2	Each	\$ _____	\$ _____
652.0150	2 Inch Cold Planing	4,900	Sq. Yd.	\$ _____	\$ _____
656.1000	Mailbox	14	Each	\$ _____	\$ _____
693.1000	Terminal Impact Attenuator	2	Each	\$ _____	\$ _____
693.1100	Replacement Cartridge Cell (Unassembled)	12	Cell	\$ _____	\$ _____
693.1200	Replacement Nose Section Cover and Replacment Cartridge Cell (Unassembled)	4	Each	\$ _____	\$ _____
699.1000	Mobilization (Not to Exceed 10% of the Sum of All Items Excluding the Bid Price of this Item, cellular phones, allowances, and force account items)	L.S.	L.S.	L.S.	\$ _____

STP-065-1(9)

02/14/2003

P-18

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
A.	SUM OF ALL ITEMS				\$ _____
B.	EITHER FURNISH FOREIGN STEEL NOT TO EXCEED AMOUNT (INSERT "0") OR FURNISH FOREIGN STEEL IN EXCESS OF MINIMAL AMOUNT (INSERT 25% X A)				\$ _____
C.	AMOUNT FOR COMPARISON OF BIDS (A+B)				\$ _____
	ALL BIDDERS MUST FILL IN B AND COMPLETE C				
NOTE:	BIDDERS MUST COMPLETE ALL UNIT PRICES AND AMOUNTS. FAILURE TO DO SO MAY BE GROUNDS FOR REJECTION OF BID.				

STP-065-1(9)

02/14/2003

P-19

PROPOSAL SCHEDULE

The bidder is directed to Subsection 108.01 - Subletting of Contract.

The bidder's attention is directed to Sections 638 - Cellular Phone, and 699 - Mobilization for the limitation of the amount bidders are allowed to bid.

If the bid price for any proposal item having a maximum allowable bid indicated therefor in any of the contract documents is in excess of such a maximum amount, the bid price for such proposal item shall be adjusted to reflect the limitation thereon. The comparison of bids to determine the successful bidder and the amount of contract to be awarded shall be determined after such adjustments are made, and such adjustments shall be binding upon the bidder.

The bidder is directed to Subsections 106.12 - Recycling of Waste Glass and 106.13 - Ordering of Certain Material.

INSTRUCTIONS TO COMPUTE THE AMOUNT FOR COMPARISON OF BIDS FOR FOREIGN STEEL

Each bidder shall indicate its intention to furnish foreign steel on this project by initialing after the AMOUNT for each of the items the bidder intends to use such foreign steel including lump sum items. A bidder not indicating such usage certifies that the bidder will furnish and use only domestic steel on this project. Also, the bidder shall add an additional 25% to the SUM OF ALL ITEMS if the bid submitted is based on furnishing foreign steel in excess of the minimal use specified in Subsection 106.11 - Domestic Materials.