1 2 3	SEC	TION 209 - TEMPORARY WATER POLLUTION, DUST, AND EROSION CONTROL
4 5	209.01	Description. This section describes the following:
6 7		(A) Including detailed plans, diagrams, and written site-specific best
8		management practices (BMP); constructing, maintaining, and repairing
9		temporary water pollution, dust, and erosion control measures at the project
10		site, including local material sources, work areas and haul roads; removing
11 12		and disposing hazardous wastes; control of fugitive dust (defined as uncontrolled emission of solid airborne particulate matter from any source
13		other than combustion); and complying with applicable State and Federal
14		permit conditions.
15		permit certaineries
16		(B) Work associated with dewatering activities and complying with
17		conditions of the National Pollutant Discharge Elimination System (NPDES)
18		general permit coverage authorizing discharges associated with construction
19		activity dewatering.
20		
21		Requirements of this section also apply to borrow pit operations, haul
22		roads and Contractor's storage sites located outside State Right-of-Way.
23	000.00	
24	209.02	Materials. Materials shall conform to the following:
25		(A) Slope Drains. Slope drains may be constructed of pipe, fiber, mats,
26 27		erosion control fabric, geotextiles, rubble, portland cement concrete,
28		bituminous concrete, plastic sheets, or other materials acceptable to
29		Engineer.
30		
31		(B) Mulches. Mulches shall be recycled materials include bagasse, hay,
32		straw, wood cellulose, bark, wood chips, or other materials acceptable to
33		Engineer. Mulches shall be clean and free of noxious weeds and deleterious
34		materials.
35		
36		(C) Grass. Grass shall be a quick growing species such as rye grass,
37		Italian rye grass, or cereal grasses. Grass shall be suitable to the area and
38		provide a temporary cover that will not compete later with permanent cover.
39		Alternative grasses are allowable if acceptable to Engineer.
40		(D) Fortilizer and Soil Conditioners Fortilizer and soil conditioners shall
41 42		(D) Fertilizer and Soil Conditioners. Fertilizer and soil conditioners shall be a standard commercial grade acceptable to the Engineer. Fertilizer shall
42		conform to Subsection 619.02(H)(1) - Commercial Fertilizer.
44		
45		(E) Hydro-mulching. Hydro-mulching used as a BMP shall consist of
46		materials in Subsections 209.02(B) - Mulches, 209.02(C) - Grass, and
47		209.02(D) –Fertilizer and Soil conditioners, with potable water meeting the

94

48 49			Subsection 712.01 - Water. Installation and other in accordance with portions of Section 641- Hydro-Mulch
50		eding.	in accordance with portions of Section 641-11yaro-Malch
51 52	/E\	Silt Eancas	Silt fances shall be synthetic filter fabric mounted on
52 53	(F)		s. Silt fences shall be synthetic filter fabric mounted on ded in compacted ground in accordance with contract
54 55	doc		all be in compliance with ASTM D6462, Standard Practice
56	101 \	Silt i erice irista	mation.
57 58	(G) mat		erms shall be gravel or sand wrapped with geotextile materials are allowable if acceptable to Engineer.
59 50 51			als or methods to control, prevent, remove and dispose acceptable to Engineer.
52 53	209.03	Construction.	
54	209.03	Construction.	
55	(A)	Preconstru	ction Requirements.
56		(4) 10/-1-	n Balladan Bartana I Francisco Control Martino
57 58		` '	er Pollution, Dust, and Erosion Control Meeting. specific BMP to Engineer. Schedule a water pollution,
59			rosion control meeting with Engineer after site specific
70			epted in writing by Engineer. Meeting shall be scheduled
71			ore start of construction work. Discuss sequence of work,
72		•	roposals for water pollution, dust, and erosion control.
73			
74		` '	er Pollution, Dust, and Erosion Control Submittals.
75		Submit the f	following:
76			Maria de la companya
77		(a)	Written site-specific BMP describing activities to
78 79			nize water pollution and soil erosion into State waters, age or sewer systems. BMP shall include the following:
30		urairi	age of sewer systems. Divir shall include the following.
31			1. An identification of potential pollutants and their
32			sources.
33			
34			2. A list of all materials and heavy equipment to be
35			used during construction.
36			
37			3. Descriptions of the methods and devices used to
88			minimize the discharge of pollutants into State waters,
39			drainage or sewer systems.
90			A Dataila of the precedures used for the
91 92			4. Details of the procedures used for the maintenance and subsequent removal of any erosion or
92 93			siltation control devices

95 96	 Methods of removing and disposing hazardous wastes encountered or generated during construction
97	
98	6. Methods of removing and disposing concrete and
99	asphalt pavement cutting slurry, concrete curing water
100	and hydrodemolition water.
101	
102	7. Spill control.
103	
104	8. Fugitive dust control, including dust from
105	grinding, sweeping, or brooming off operations o
106	combination thereof.
107	
108	9. Methods of storing and handling of oils, paint
109	and other products used for the project.
110	
111	10. Material storage and handling areas, and other
112	staging areas.
113	
114	11. Concrete truck washouts.
115	40 Ornanata varata aputual
116	12. Concrete waste control.
117	40 Eveling and projeton and other
118	13. Fueling and maintenance of vehicles and othe
119	equipment.
120	4.4 The chief of a phine out official frame music at authin
121	14. Tracking of sediment offsite from project entries
122	and exits.
123	4E Litter management
124 125	15. Litter management.
	16. Toilet facilities.
126 127	16. Toilet facilities.
127	17. Other factors that may cause water pollution
128	dust and erosion control.
130	dust and erosion control.
131	(b) Provide plans indicating location of water pollution, dus
132	and erosion control devices; provide plans and details of BMPs
133	to be installed or utilized; show areas of soil disturbance in cu
134	and fill, indicate areas used for storage of aggregate (indicate
135	type of aggregate), asphalt cold mix, soil or waste, and show
136	areas where vegetative practices are to be implemented
137	Indicate intended drainage pattern on plans. Include separate
138	drawing for each phase of construction that alters drainage
139	patterns. Indicate approximate date when device will be
140	installed and removed.
141	

188

142	(c) Construction schedule.
143	
144	(d) Name(s) of specific individual(s) designated responsible
145	for water pollution, dust, and erosion controls on the project
146	site. Include home and business telephone numbers, fax
147	numbers, and e-mail addresses.
148	
149	(e) Description of fill material to be used.
150	
151	Date and sign BMP. Keep accepted copy on site
152	throughout duration of the project. Revisions to the BMP shall
153	be included with original BMP. Modify contract documents to
154	conform to revisions. Include actual date of installation and
155	removal of BMP. Obtain written acceptance by Engineer
156	before revising BMP.
157	g are to the trig arm to
158	Effective October 1, 2008, follow guidelines in the
159	"Construction Best Management Practices Field Manual" dated
160	January 2008, in developing, installing, and maintaining BMPs
161	for all projects. Follow Honolulu's City and County "Rules for
162	Soil Erosion Standards and Guidelines" for all projects on
163	Oahu. Use respective Soil Erosion Guidelines for Maui, Kauai
164	and Hawaii projects.
165	and Hawaii projector
166	(B) Construction Requirements. Do not begin work until submittals
167	detailed in Subsection 209.03(A)(2) - Water Pollution, Dust, and Erosion
168	Control Submittals are completed and accepted in writing by Engineer.
169	control custimate and completed and accepted in triming by Engineer
170	Install, maintain, monitor, repair and replace site-specific BMP
171	measures, such as for water pollution, dust and erosion control; installation,
172	monitoring, and operation of hydrotesting activities; removal and disposal of
173	hazardous waste indicated on plans, concrete cutting slurry, concrete curing
174	water; or hydrodemolition water.
175	
176	Furnish, install rain gage in a secure location for projects that require
177	NPDES permit from the Department of Health prior to field work including
178	installation of site-specific BMP. Provide rain gage with a tolerance of at
179	least 0.05 inches of rainfall, and an opening of at least 1-inch diameter.
180	Install rain gage on project site in an area that will not deter rainfall from
181	entering the gate opening. Maintain rain gage and replace rain gage that is
182	stolen, does not function properly or accurately, is worn out, or needs to be
183	relocated. Do not begin field work until rain gauge is installed and site
184	specific BMPs are in place. Do not begin field work until rain gauge is
185	installed and site specific BMPs are in place.
186	motaned and one opcome biring and in piace.
187	Address all comments received from Engineer.
107	Addition all comments received from Engineer.

209-4

Modify and resubmit plans and construction schedules to correct conditions that develop during construction which were unforeseen during the design and pre-construction stages.

Coordinate temporary control provisions with permanent control features throughout the construction and post-construction period.

Limit maximum surface area of earth material exposed at any time to 300,000 square feet. Do not expose or disturb surface area of earth material (including clearing and grubbing) until BMP measures are installed and accepted in writing by Engineer. Protect temporarily or permanently disturbed soil surface from rainfall impact, runoff and wind before end of workday.

Protect exposed or disturbed surface area with mulches, grass seeds or hydromulch. Spray mulches at a rate of 2,000 pounds per acre. Add tackifier to mix at a rate of 85 pounds per acre. Apply grass seeds at a rate of 125 pounds per acre. For hydromulch use the ingredients and rates required for mulches and grass seeds.

Apply fertilizer to mulches, grass seed or hydromulch at a rate of 450 pounds per acre. Apply an additional 250 pounds per acre every 90 calendar days.

Install velocity dissipation measures when exposing erodible surfaces greater than 15 feet in height.

BMP measures shall be in place and operational (such as shaping the earthwork to control and directing the runoff) at the end of workday. Shaping earthwork may include constructing earth berms along the top edges of embankments if acceptable to Engineer.

Install and maintain either or both stabilized construction entrances and wheel washes to minimize tracking of dirt and mud onto roadways. Restrict traffic to stabilized construction areas only. Clean dirt, mud, or other material tracked onto the road immediately. Modify stabilized construction entrances to prevent mud from being tracked onto road. Stabilize entire access roads if necessary.

Chemicals may be used as soil stabilizers for either or both erosion and dust control if acceptable to Engineer.

Provide temporary slope drains of rigid or flexible conduits to carry runoff from cuts and embankments. Provide portable flume at the entrance. Shorten or extend temporary slope drains to ensure proper function.

Protect ditches, channels, and other drainageways leading away from cuts and fills at all times by either:

237	
238	(1) Hydro-mulching the lower region of embankments in the
239	immediate area.
240	
241	(2) Placing an 8- to 15-inch layer of excavated rock, if available on-
242	site, without reducing the cross section of the drainageway. Rocks
243	shall be less than four inches in diameter.
244	
245	(3) Installing check dams and siltation control devices.
246	(c) motaling officer dame and children control devices.
247	(4) Other methods acceptable to Engineer.
248	(4) Other methods acceptable to Engineer.
249	Provide for controlled discharge of waters impounded, directed, or
250	controlled by project activities or erosion control measures.
251	controlled by project activities of crosion control measures.
252	Cover exposed surface of materials completely with tarpaulin or similar
252 253	device when transporting aggregate, soil, excavated material or material that
254	may be source of fugitive dust.
255	may be source of rughtive dust.
	Clashup and ramova any pollutant that can be attributed to Contractor
256	Cleanup and remove any pollutant that can be attributed to Contractor.
257	Install or modify PMD magazines due to change in Contractor's magazines
258	Install or modify BMP measures due to change in Contractor's means
259	and methods, or for omitted condition that should have been allowed for in
260	the accepted site specific BMP or a BMP that replaces an accepted site
261	specific BMP that is not satisfactorily performing.
262	Dranarly maintain all DMD factures, Inchest prepare a written report
263	Properly maintain all BMP features. Inspect, prepare a written report,
264	and make repairs to BMP measures at following intervals:
265	(4) Waalde de winn dre naviada
266	(1) Weekly during dry periods.
267	(O) Within OA have of any pointall of O.F. inch an execution which
268	(2) Within 24 hours of any rainfall of 0.5 inch or greater which
269	occurs in a 24-hour period.
270	
271	(3) Daily during periods of prolonged rainfall.
272	
273	(4) When existing erosion control measures are damaged or not
274	operating properly as required by site specific BMP.
275	
276	Remove, destroy, replace or relocate any BMP that must be removed,
277	destroyed, replaced or relocated due to potential or actual flooding, or
278	potential danger or damage to project or public.
279	

Maintain records of inspections of BMP work. Keep continuous records for duration of the project. Submit weekly copy of records to Engineer.

In addition to weekly reports, submit to Engineer all amounts spent initializing and maintaining BMP during previous week. Amount spent includes, but is not limited to: purchases of erosion control material, construction of storage areas, and installation of water pollution, erosion and dust control measures. Submit report weekly along with site inspection report.

Protect finished and previously seeded areas from damage and from spillover materials placed in upper lifts of embankment.

The Contractor's designated representative specified in Subsection 209.03(A)(2)(d) shall address any BMP concerns brought up by Engineer within 24 hours of notification, including weekends and holidays. Failure to satisfactorily address these concerns, Engineer reserves the right to employ outside assistance or use Engineer's own labor forces to provide necessary corrective measures. Engineer will charge Contractor such incurred costs plus any associated project engineering costs. Engineer will make appropriate deductions from Contractor's monthly progress estimate. Failure to apply BMP measures shall result in either or both the establishment and increase in the amount of retainage due to unsatisfactory progress or withholding of monthly progress payment. Continued failure to apply BMP measures may result in one or more of the following: assessment of liquidated damages, suspension, or cancellation of Contract with Contractor being fully responsible for all additional costs incurred by State.

(C) Hydrotesting Activities. If work includes removing, relocation or installing waterlines, and Contractor elects to flush waterline or discharge hydrotesting effluent into State waters or drainage systems, obtain an NPDES Hydrotesting Waters Permit from Department of Health, Clean Water Branch (DOH-CWB).

Do not begin hydrotesting activities until the DOH-CWB has issued a Notice of General Permit Coverage (NGPC). Hydrotesting operations shall be in accordance with conditions in NGPC. Submit a copy of the NPDES Hydrotesting Waters Application and Permit to Engineer.

(D) Dewatering Activities. If excavation of backfilling operations require dewatering, and Contractor elects to discharge dewatering effluent into State waters or existing drainage systems, obtain NPDES General Permit Coverage authorizing discharges associated with construction activity

dewatering from Department of Health, Clean Water Branch (DOH-CWB). If permit is required, prepare and submit permit application (CWB-NOI Form G) to DOH-CWB.

Do not begin dewatering activities until DOH-CWB has issued Notice of General Permit Coverage (NGPC). Conduct dewatering operations in accordance with conditions in NGPC. Submit copy of NPDES Hydrotesting Waters Application and Permit to Engineer.

209.04 Measurement.

(A) Installation, maintenance, monitoring, and removal of BMP will be paid on a lump sum basis. Measurement for payment will not apply.

(B) Engineer will only measure additional water pollution, dust and erosion control required and requested by Engineer on a force account basis in accordance with Subsection 109.06 – Force Account Provisions and Compensation.

209.05 Payment. Engineer will pay for accepted pay items listed below at contract price per pay unit, as shown in the proposal schedule. Payment will be full compensation for work prescribed in this section and contract documents.

Engineer will pay for each of the following pay items when included in proposal schedule:

Pay Item Pay Unit

Installation, Maintenance, Monitoring, and Removal of BMP Lump Sum

Additional Water Pollution, Dust, and Erosion Control Force Account

An estimated amount for force account is allocated in proposal schedule under 'Additional Water Pollution, Dust, and Erosion Control', but actual amount to be paid will be the sum shown on accepted force account records, whether this sum be more or less than estimated amount allocated in proposal schedule. Engineer will pay for BMP measures requested by Engineer that are beyond scope of accepted site specific BMP and for litter management due to rubbish created by the public on a force account basis.

No progress payment will be authorized until Engineer accepts in writing sitespecific BMP or when Contractor fails to maintain project site in accordance with accepted BMP.

For all citations or fines received by the Department for non-compliance with Notice of General Permit Coverage (NGPC), the Contractor shall reimburse State

370	within 30 days for full amount of outstanding cost State has incurred, or Engineer will
371	deduct cost from progress payment.
372	
373	Engineer will assess liquidated damages up to \$27,500 per day for non-
374	compliance of each BMP requirement and all other requirements in this section.
375	
376	
377	END OF SECTION 209