

CONTINGENCY PLAN

Take rain gauge readings daily.

Inspect all erosion control measures at least once each week and within 24 hours of any rainfall event of 0.5 inches or greater within a 24 hour period.

Maintain all erosion control measures in good working order. If repair is necessary, it shall be initiated within 24 hours after the inspection.

For projects with large storage/staging areas, extra BMP materials are expected to be on-site. If no materials are stockpiled on-site, materials are expected to be locally available.

Contractor representatives and/or State personnel will monitor weather forecasts and take necessary action when large rain events are anticipated.

HDOT contracts shall contain a Force Account Item to cover additional Water Pollution, Dust, and Erosion Control. If a rainfall event is greater than the design storm, this item will be used to cover replacement of construction BMPs damaged by the storm.

Notify DOH-CWB of any illicit discharge within 24 hours of the discharge. During business hours call (808)586-4309. During non-business hours call the State Hospital Operator at (808)566-5049 or the DOH Switch Board Operator at 247-2191.