

POST-CONSTRUCTION POLLUTION CONTROL MEASURES

Slope Stabilization

Grouted Rubble Paving or other suitable slope stabilization measures will be installed on embankments at Sta. 35+00 Rt. and Sta. 8+50 Lt to prevent eroded material from entering State waters.

Miscellaneous Measures

Post-construction pollutant control measures include periodic sweeping and other maintenance activities as required to minimize pollutants from entering receiving water. Post Construction Pollution Control Measures specifically for the Kawa Stream Watershed include Debris Control (including sweeping and drain cleaning), Erosion Control BMP Program (permanent stabilization of eroded areas), and Permanent BMP Installation.