

1 **SECTION 603 – CULVERTS AND STORM DRAINS**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **603.03(C)(1) - Culverts** by revising lines 106 to 108 to read as
6 follows:

7
8 “Spacing between multi-barrel culverts shall be a minimum of 18 inches or
9 0.5 the culvert width, whichever is greater. The minimum spacing shall be 1 foot
10 when placing controlled low strength material (CLSM) as backfill. Anchor the
11 culverts in such a manner that the horizontal and vertical alignment of the
12 culverts does not change.”

13
14 **(II)** Amend **603.04 – Measurement** by revising lines 282 to 292 to read as
15 follows:

16
17 **“603.04 Measurement.**

18
19 The Engineer will measure cleaning of existing culverts on a force account
20 basis in accordance with Subsection 109.06 - Force Account Provisions
21 and Compensation and as ordered by the Engineer.

22
23 The Engineer will measure the 24-Inch reinforced concrete pipe by linear
24 foot according to the dimensions shown in the contract or as ordered by
25 the Engineer.”

26
27 **(III)** Amend **603.05 – Payment** by revising lines 294 to 350 to read as follows:

28
29 **“603.05 Payment.** The Engineer will pay for the accepted pay items listed
30 below at the contract price per pay unit, as shown in the proposal schedule.
31 Payment will be full compensation for the work prescribed in this section and
32 contract documents.

33
34 The Engineer will pay for each of the following pay items when included in
35 the proposal schedule:

36

Pay Item	Pay Unit
Clean Existing Culverts	Force Account
24-Inch Reinforced Concrete Pipe	Linear Foot”

37
38
39

40
41
42
43
44 **(IV)** Amend **603.05 – Payment** by deleting lines 357 to 359.

45
46 **END OF SECTION 603**