

1 Make the following section a part of the Standard Specifications:

2  
3 **“SECTION 627 – BOLT DOWN CURBING**

4  
5  
6 **627.01 Description.** This section describes furnishing and installing bolt down  
7 curbing shown in the plans according to the requirements of the contract or as  
8 ordered by the Engineer.  
9

10 **627.02 Materials.** The bolt down curbing system shall consist of a prequalified  
11 product such as Tuff Curb or approved equal.  
12

13 System shall be of uniform composition, free from surface irregularities, and  
14 free from other physical damage or defects that affect appearance or performance,  
15 or both.  
16

17 **627.03 Construction.** Contractor shall furnish and install bolt down curbing  
18 system per manufacturer’s specifications at locations identified on plans.  
19

20 **(A) General.**

21  
22 **(1)** Remove surface moisture and other materials that may  
23 adversely affect system installation.  
24

25 **(2)** Establish control points and layout alignment for bolt down  
26 curbing system.  
27

28 **(3)** Curb sections spacing should be ½” but no more than 1” to  
29 allow for drainage.  
30

31 **(4)** Bolt down curbing should begin and end with corresponding  
32 end sections per manufacturer’s specifications.  
33

34 **627.04 Measurement.** The Engineer will measure bolt down curbing system per  
35 linear foot in accordance with the contract documents. Curb section spacings of ½”  
36 but no more than 1” shall be included in the total linear foot length.  
37

38 **627.05 Payment.**

39  
40 The Engineer will pay for the following pay items when included in the  
41 proposal schedule:  
42

43 <b>Pay Item</b>	44 <b>Pay Unit</b>
45 Bolt Down Curbing	46 Linear Foot”

47 **END OF SECTION 627**