

1 **SECTION 634 – PORTLAND CEMENT CONCRETE SIDEWALKS**

2
3 Make the following amendment to said Section:

4
5 **(I) Amend Section 634.04 - Measurement** by replacing lines 60 to 61 to read:

6
7 **“634.04 Measurement.** The Engineer will measure Portland cement
8 concrete sidewalks and pads by the square yard of finished surface.”

9
10 **(II) Amend Section 634.05 – Payment** by replacing lines 62 to 72 to read:

11
12 **“634.05 Payment.** The Engineer will pay for the accepted quantities of
13 Portland cement concrete sidewalk and pads at the contract unit price per square
14 yard complete in place as shown in the proposal.

15
16 Payment will be full compensation for work prescribed in this section and
17 contract documents.

18
19 The Engineer will pay for following pay item when included in proposal
20 schedule:

21

Pay Item	Pay Unit
Portland Cement Concrete Sidewalk	Square Yard
4-Inch Portland Cement Concrete Pad (Bus Shelter)	Square Yard

27

28 The Engineer will pay for excavation of unsuitable material and backfill
29 with material acceptable to the Engineer under Section 203 – Excavation and
30 Embankment. If no pay item exists, refer to Subsection 104.02 – Changes.”

31
32
33
34
35
36 **END OF SECTION 634**