

1                                   **SECTION 645 – WORK ZONE TRAFFIC CONTROL**

2  
3       Make the following amendments to said Section:

4  
5       **(I)**       Amend the second paragraph of **645.03 - Construction** from lines 64 to 66  
6       to read as follows:

7  
8               “Furnish two police officers for each location that requires work zone traffic  
9       control, unless otherwise requested by the State. If TCP is included in the contract  
10      documents, furnish number of police officers indicated in the TCP or minimum of  
11      two police officers, whichever is greater.”

12  
13      **(II)**       Amend **645.03(F) – Lane Closures** from lines 248 to 252 to read as follows:

14  
15              **“(F) Lane Closures.** Lane closures will be allowed only during the  
16      following hours. Exceptions to lane closure hours specified require written  
17      acceptance by the Engineer. No increase in contract price or contract time will be  
18      given for lane closure restrictions specified.

19  
20                      **(1) Work requiring lane closures.** Contractor may perform  
21      work requiring lane closures during daytime working hours of 8:30  
22      a.m. to 3:00 p.m., Monday through Friday. Closure of only one lane  
23      of traffic is allowed during this time.

24  
25                      **(2) Night-time work maintaining one (1) open lane.** Night-  
26      time lane closure that maintains one (1) open lane in a particular  
27      direction will be allowed during the following hours:

28  
29                      Sunday to Thursday                                   7:00 p.m. to Midnight  
30                      Monday to Friday                                       Midnight to 3:00 a.m.

31  
32              The Contractor may request to close both Kailua-Bound and Hawaii Kai-  
33      Bound lanes simultaneously for Item (2) above. Obtain the Engineer’s acceptance  
34      prior to implementing full roadway lane closures. Full roadway lane closures will  
35      be limited to weekdays only except for State Holidays and shall not be combined  
36      with other lane closures. The Contractor shall be responsible for obtaining all the  
37      required Noise Variance permits and approvals associated with this project prior  
38      to the start of the work.

39  
40              The Contractor shall submit detour and site-specific traffic control plan(s)  
41      intended for use during construction to the Engineer and/or designated  
42      representative, with the traffic notification, a minimum of one (1) week prior to the  
43      scheduled start of the associated construction activities for review and approval.  
44      Construction may not proceed until the Engineer and/or designated representative  
45      has approved the detour and/or site-specific traffic control plan(s).

47  
48 (III) Amend **645.03(F) – Lane Closures** Line 260 to read as follows:  
49

50 “(2) Holidays (Midnight to 7 p.m.).”  
51

52 (IV) Amend **645.03(F) – Lane Closures** from lines 277 to 279 to read as follows:  
53

54 “See Subsection 107.03 — Working Hours; Night Work for description of  
55 Noise Variance hours, noise control conditions, and restrictions during weekend  
56 and night work.  
57

58 At the Director’s discretion, with a one-week prior notification to the  
59 Contractor, work may be suspended to allow traffic to flow freely during major  
60 public events, such as concerts, parades, sporting events, etc. The Contractor will  
61 not be compensated but the Contractor’s Roadway Completion Time and/or  
62 Contract Time will be adjusted accordingly.  
63

64 The Director may also suspend work at any time due to unforeseen  
65 circumstances that occur within the immediate vicinity that may disrupt the traffic  
66 on the freeway and/or alternate routes or in times of emergencies. The Contractor  
67 will be compensated for work performed up to the time of the suspension and  
68 Contractor’s Roadway Completion Time and/or Contract Time will be adjusted  
69 accordingly.”  
70

71 (V) Add the following to Subsection **645.03 Construction** after line 393:  
72

73 “**645.03(I) – Portable Message Board.** Furnish, install, maintain and  
74 remove portable message boards at locations and durations as specified in the  
75 Traffic Control Plans.  
76

77 The Contractor shall provide and maintain up to five portable message  
78 boards with remote access features to be used for the duration of the project as  
79 directed by the Engineer. Remote access shall be granted to HDOT personnel.  
80 Payment for all work associated with the message boards shall be included in  
81 Traffic Control lump sum pay item.”  
82

83  
84 **END OF SECTION 645**