

1 <sup>2</sup>△ Make the following Section a part of the Standard Specifications:

2  
3 **"SECTION 652 – ARCHAEOLOGICAL MONITORING**

4  
5 **652.01 Description.** This work includes archaeological monitoring of  
6 construction activities to identify, and provide mitigation for, archaeological  
7 resources and/or human burials that may be located in the project area.

8  
9 **652.02 Materials.** None specified.

10  
11 **652.03 Construction.** An approved Final Archaeological Monitoring plan is  
12 on file with the Department of Land and Natural Resources, State Historic  
13 Preservation Division (SPHD). A copy of the plan is available for viewing at the  
14 State of Hawaii Department of Transportation, Highway Division, Oahu District  
15 Office. The Contractor shall adhere to the conditions of the monitoring plan as  
16 well as comply with the requirements of Section 107.13(B) – Archaeological,  
17 Historical, and Burial Sites.

18 The Contractor shall obtain the services of a qualified Archaeologist or  
19 firm to monitor all ground altering disturbance work such as clearing and  
20 grubbing, excavation, and trenching activities for historical remains such as  
21 artifacts, burials, concentration of shells, or charcoal, and to fulfill the other  
22 requirements of the monitoring plan.

23 If remains are found, work shall cease in the immediate vicinity of the find  
24 and the find shall be protected from further damage. The Archaeologist shall  
25 immediately contact the State Historical Preservation Division (692-8023), which  
26 will assess the significance of the find and recommend appropriate mitigation  
27 measures, if necessary.

28  
29 A list of Archaeologist or Archaeological firms meeting the requirements to  
30 perform such work can be obtained on the SHPD website at  
31 <http://dlnr.hawaii.gov/shpd/files/2013/05/2015-Permittee-List-5.pdf> or by  
32 contacting SHPD's main office at (808) 692-8015.

33  
34  
35 **652.04 Measurement.** The Engineer will measure archaeological monitoring,  
36 including remedial measures, on a force account basis according to Subsection  
37 109.06 – Force Account Provisions and Compensation and as ordered by the  
38 Engineer.

39  
40 **652.05 Payment.** The Engineer will pay for the accepted archaeological  
41 monitoring, including remedial measures, on a force account basis. Payment will  
42 be full compensation for the work prescribed in this section, by the Engineer, and  
43 the contract documents.

44  
45 The Engineer will pay for the following pay item:  
46

47	<b>Pay Item</b>	<b>Pay Unit</b>
48		
49	Archaeological Monitoring	Force Account

50

51       An estimated amount for the force account is allocated as shown in the

52 proposal schedule under 'Archaeological Monitoring', but the actual amount to

53 be paid will be the sum shown on the accepted force account records, whether

54 this sum be more or less than the estimated amount allocated in the proposal

55 schedule.

56

57       The Engineer will not pay for work required that is due to the Contractor's

58 convenience, negligence, carelessness or failure to properly monitor excavation

59 activity.

62

63

64

**END OF SECTION 652**