STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION DESIGN BRANCH MEMORANDUM

HWY-DH 2.3846

DATE: November 13, 2009

TO:

HWY- C, O, -T, -L, -DS, -DD, -DH, -DB, -DL

FROM:

HWY-D SUIT > MAR

SUBJECT:

CITY AND COUNTY OF HONOLULU, DEPARTMENT OF PLANNING AND

PERMITTING (DPP) - GRADING PERMIT SUBMITTAL REQUIREMENTS

This is a follow up to a HWY Memo dated September 8, 2008 (Attachment 2). The original self-certification form has been revised to include a paragraph stating that the Department of Transportation has reviewed the City and County of Honolulu Rules Relating to Soil Erosion Standards and Guidelines and has submitted the required documents to DPP. (See revised self-certification form in Attachment 1)

Documents required for submittal to DPP include the revised self certification form, Universal Soil Loss calculations, and Erosion Control Plans. The Design Engineer shall be responsible to complete the self certification form and prepare the soil loss calculations. The Oahu District office shall be responsible to ensure that these documents along with the Erosion Control Plans are submitted to DPP prior to the start of construction.

Again as a reminder, these submittals are only applicable to construction projects on Oahu that require a Grading Permit from DPP. In general, projects such as: pavement preservation, resurfacing, reconstruction, and rehabilitation; roadway, traffic, and drainage safety improvements; landscaping; utility work; rockfall; retaining and sound walls will not apply. The Table in Attachment 2 provides a detailed description of projects that do not require a Grading Permit.

Should you have any questions, please contact Scot Urada, Design Branch Head at 692-7559, or Curtis Matsuda at 692-7561 of our Hydraulic Design Section.

Attachments


CM: mjkn

c: HWY

ATTACHMENT 1

То:	Department of Planning and Permitting City & County of Honolulu 650 South King Street, 7 th Floor Honolulu, Hawaii 96813
	Attention: Permitting & Inspection Section
From	State of Hawaii Department of Transportation Highways Division 601 Kamokila Boulevard, Room 688A Kapolei, Hawaii 96707
Subje	ct: Non applicability for Detailed Plan review for projects requiring Grading Permits:
	Project No:
	Project Title:
	TMK No(s):
is not	ed plan review and approval for the above project by the City & County of Honolulu applicable for the reasons stated in the HWY-D letter no. 2.8186 dated June 25, and as agreed with in DPP Letter 2008/ELOG-1912 dated August 12, 2008.
	rtify that the work has been reviewed and is found to be in compliance with er 14, Articles 13, 14 & 15 as amended, Revised Ordinances of Honolulu.
of Hor the att	epartment of Transportation and/or its consultant have reviewed the City & County olulu Rules Relating to Soil Erosion Standards and Guidelines (Guidelines) and ached Erosion Control Plan and related documents have been prepared in ance with the referenced Guidelines.
	estions regarding this matter, please contact Scot Urada at 692-7559, ering Program Manager, Design Branch, Highways Division.
Projec	et Manager: Date:
Section	n Head: Date:
Branc	h Head: Date:
Original:	HWY-OC Project File





STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION DESIGN BRANCH MEMORANDUM

HWY-D 2.9279

DATE: September 15, 2008

TO:

HWY-C, -D, -L, -T, -O

FROM:

HWY Drum m James

SUBJECT:

WAIVER OF DETAILED PLAN REVIEW - LETTER OF AGREEMENT

(LOA) BETWEEN HAWAII STATE DEPARTMENT OF TRANSPORTATION AND CITY & COUNTY OF HONOLULU (C&C) DATED AUGUST 12, 2008

By letter of agreement (Attachment A), the C&C has agreed not to conduct a detailed plan review for DOT-Highways projects requiring grading permits provided that DOT submits a self certification form (page 2 of Attachment B) along with any required grading permit applications. This applies only to projects on Oahu that require grading permits.

Upon completion of design, the design Project Manager shall use Attachment C, <u>Typical Projects not Requiring Grading Permits</u> dated 8-20-08 and Attachment D, <u>Revised Ordinances of Honolulu</u> to determine whether if the project requires a grading permit or not.

If the project does not require a grading permit, no grading plan review by C&C is needed. The Project Manager checks the applicable block and signs on page 1 of Attachment B. The original is furnished to HWY-OC, and a copy is placed in the project file.

However if a project requires a grading permit, the following shall be done:

- 1. The Project Manager shall complete check the applicable block and sign page 1 of Attachment B, and complete page 2 of this form. The signatures of Section Head and Branch Head will be that of the office managing the PS&E.
- 2. The signed originals will be provided to HWY-OC prior to the preconstruction conference. A copy of this form will be kept in the design project file.
- 3. At the preconstruction meeting, page 2 of the original, signed form will be provided to the construction contractor, who in turn, will provide this to the C&C when a grading permit is processed.

Memo to HWY-C, -D, -L, -T, -O Page 2 September 15, 2008 HWY-D 2.9279

It should be noted that this specifically pertains to <u>grading plan review</u> for projects on Oahu. The possibility exists that a project may affect other C&C facilities such as sewer lines, waterlines, traffic signals, sidewalks, etc. While such work may not require a grading permit, these plans will still require review and approval by C&C.

If you have any questions regarding this matter, please contact Scot Urada, Design Branch Head at 692-7559.

Attachment

SU:su

DIR REI

DEPARTMENT OF PLANNING AND PERMITTING

CITY AND COUNTY OF HONOLULU

650 South King Street, 7th Floor • Honolulu, Hawaii 96813 PHONE: (808) 768-8000 PAX: (808) 527-6743

DEPT. WEB SITE: www.honoluludop.org CITY WEB SITE: www.honolulu.gov

MUFI HANNEMANN MAYOR



August 12, 2008

HENRY ENG, PAICP DIRECTOR

DAVID K. TANOUE

2008/ELOG-1912 (wyw)

The Honorable Brennon T. Morioka, Ph. D., P. E., Director State of Hawaii Department of Transportation 869 Punchbowl Street Honolulu, Hawaii 96813-5097

Dear Dr. Morioka:

Subject: Grading Plan Reviews for State DOT **Highways Division Projects**

This is in response to your letter of June 25, 2008 (HWY-D 2.816).

We agree that a detailed review of grading plans for Highways Division projects by our department is a duplication of government effort. Accordingly, as originally established by the former Department of Public Works on May 27, 1986 (14-0415), we will continue to process grading permits for those projects without our detailed plan reviews, subject to the DOT's compliance with all applicable codes, rules, regulations, and procedures.

With regard to the required DOT certifications that must be submitted with the grading permit applications, we have no objections to the use of the proposed certification form enclosed with your letter.

Should there be any questions, please contact our Civil Engineering Branch staff at 768-8215.

Very truly yours,

Henry Eng, FAIC

A, Director AMAYS DIVISION

HE:th:ifk

cc/incom: Project Review Section

JUN \$ 5 2008

HWY-D 2.8186

JUN 2 5 2008

Mr. Henry Eng, Director Department of Planning and Permitting City and County of Honolulu 650 South King Street, 7th Floor Honolulu, Hawaii 96813

Dear Mr. Eng:

Subject: Request for Non-Applicability of Detailed Plan Review for State Department of

Transportation Highways (HDOT) projects

We request for the City & County of Honolulu's (City) continued concurrence that a detailed plan review is not required for projects submitted for grading permits. In 1986, the City and HDOT agreed that a detailed plan review was not required provided that HDOT submits with the grading permit application, "a statement certifying that the work has been reviewed and found in substantial compliance with the City's Grading Ordinance."

The rationale for the previous agreement was that during project development by HDOT, our design process already covers the intent of the City's grading ordinance and is in compliance with current State and Federal requirements. Thus another level of review by a different government agency would be a duplication of effort.

HDOT will continue to submit grading permits as required by Chapter 14, Revised Ordinances of Honolulu. Approved plan sheets will be furnished with the permit application.

HDOT is responsible to correct any deficiencies in erosion and sediment control, both during construction and post construction, and our field construction personnel are required to monitor, control and enforce erosion control procedures and Best Management Practices.

If agreeable, this request supersedes the City's letter 14-0415 dated May 27, 1986 and DOT's letter HWY-DD 2.90019 dated May 13, 1986. We look forward for a favorable consideration to this request to enable a cost and time efficient means to deliver transportation projects to Oahu's motorists.

Very truly yours,

BRENNON T. MORIOKA, Ph.D., P.E.

Director of Transportation

Enclosures

SU: mjkn.

bc: HWY-D, -DD, -DS, -DH, -DB, -DL, -T --

FRANK F. FASI

MATOR

Post-it® Fax Note 76	Date -2/14/08 pages 14
TO SHAKK!	From Wel
Co./Dept.	Co.
Phono #	Phone # 11/8 \$ 1 044-
Fax# 52% 2368	Fax #

BLIC WORKS

HENR-YIK TREST

.11 96612

HAY 29 3 38 PH '86

SE HER TRANSFED "ATION AUSSILL L SHITH

뜅

14-0415

May 27, 1986

Mr. Wayne Y. Yamasaki, Director Department of Transportation State of Hawaii . 869 Punchhowl Street Honolulu, Hawaii 96813

Dear Mr. Yamasaki:

Your Letter HWY-DD 2.90019, of May 13, 1986, Subject: Regarding Detailed Review of Highways Plans for Conformance to the Grading Ordinance

We generally concur in your belief that a detailed review of Righways Division plans by our Division of Engineering, for conformance to the requirements of Chapter 23 of the Revised Ordinances of Honolulu (Grading Ordinance) constitutes a duplication of effort in carrying out the intent of the Ordinance.

Therefore, we are approving your request for an exemption from a detailed plan review providing that you meet the requirements stated in your subject letter and that you submit with the grading permit application a statement certifying that the work has been reviewed and found to be in substantial compliance with the City's Grading Ordinance.

Very truly yours,

Director and Chief Engineer

Stic/Re wt

M - 17

HAY 1 3 1986

HWY-DD 2.90019

Mr. Russell L. Smith, Jr. Director and Chief Engineer Department of Public Works City and County of Honolulu Honolulu, Hawaii 96813

Dear Mr. Smith:

plans, developed by the Highways Division, State Department of Transportation (SDOT) are required to be approved by the City and County of Honolulu in accordance with the provisions —of Chapter 23, Grading, Soil Erosion and Sediment Control of the Revised Ordinances of Honolulu 1983 25 amended (Ordinance No...81-13), hecause—the Statemis not exempt from the wprovisions — of the ordinance.

After discussing the plan review process with your staff, we believe that the detailed review and approval of the Highways Division's plans is a duplication of effort by the City and State personnel in trying to carry out the intent of the City's grading ordinance. The Highways Division, in their plan development, must meet similar requirements listed in the Grading Ordinance and additionally must meet the following applicable State and Federal requirements:

State:

Environmental Impact Statement Regulation (Chapter 343, HRS)

Conservation District Use, Application

Hawaii Coastal Zone Management Program (HCZMP)

Mr. Russell L. Smith, Jr. Page 2

HWY-DD 2.90019

MAY 13 1902.

مرجون المحاولون

Federal:

Water Pollution Control Act

Clean Water Act

Safe Drinking Water

Flood Control Act

Farmland Protection Act

As the Director of Transportation, I approve all plans, thereby, signifying that all applicable requirements have been complied with and in the case of federal aid projects, the Administrator of the Federal Righway Administration also signs the plans for compliance.

We, therefore, request that an exemption be granted for the Highways Division, SDOT, from the detailed plan review and approval process of the grading ordinance.

However, we will continue to submit applications for grading permits as required by the ordinance. We will also furnish signed copies of the plans and the accompanying special provisions with the application. The City can then issue the grading permit subject to appropriate conditions desired by the City.

Regarding highway projects, the SDOT is responsible to correct any deficiencies in erosion and sediment control and further, our field personnel are required to monitor, control and enforce our temporary erosion control procedures that are specified in Section 639 — "Temporary Project Water Pollution Control (Soil Brosion)" of the Hawaii Standard Specifications for Road and Bridge Construction.

Mr. Russell L., Smith, Jr. Page 3 MAY 13 1984

HMX-DD .. 2.90019

I sincerely hope that a favorable consideration is given to our request for an exemption from the detailed plan review and approval process so that we may expedite projects which benefit oahu's motorists.

Very truly yours,

Wayre Transaki Director of Transportation

RMM: Wb

cc: HWY-DS

BWY-DD

HWY-M

HWY-K

HWY-H

SELF- CERTIFICATION FORM

To: Department of Planning and Permitting City & County of Honolulu 650 South King Street, 7th Floor Honolulu, Hawaii 96813 Attention: Permitting & Inspection Section From: State of Hawaii Department of Transportation Highways Division 601 Kamokila Boulevard, Room 688A Kapolei, Hawaii 96707 Subject: Non applicability for Detailed Plan review for projects requiring Grading Permits: Project No: Project Title: TMK No(s): _____ Detailed plan review and approval for the above project by the City & County of Honolulu is not applicable for the reasons stated in the HWY-D letter no. 2.8186 dated June 25, 2008 and as agreed with in DPP Letter 2008/ELOG-1912 dated August 12, 2008. We certify that the work has been reviewed and is found to be in compliance with Chapter 14, Articles 13, 14 & 15 as amended, Revised Ordinances of Honolulu. For questions regarding this matter, please contact Scot Urada at 692-7559, Engineering Program Manager, Design Branch, Highways Division.

Section Head:

Branch Head:

SUPERSEDED

Date:

Date:

Pavement Preservation and Maintenance (PPM)		Project Type	Typical Scope of Work
Road Resurfacing Cut and replace asphalt, place more than 1-1/2 inche of asphalt, ultra thin white topping Demolition and replacement of PCC, removal and repair and replacement of PCC, removal and repair and replacement of entire pavement section including PCC or AC and underlying pavement structure materials. Trenching, removal and/or installation of conduits or pipes, trench backfill, and patching. Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of raf signal facilities and installation of electrical and communication conduits. Retaining Walls or Sound Walls Reckfall Protection Trenching installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete betters. Earth or lined ditches	1	Pavement Preservation and	Application of chip seal, slurry seal, cold plane and
of asphalt, ultra thin white topping Demolition and replacement of PCC, removal and repair and replacement of PCC, removal and repair and replacement of entire pavement section including PCC or AC and underlying pavement structure materials. 4 Electrical, water, sewer, drainage, communication or other utility installation or relocations 5 Traffic Signal Modernization and/or Installation Trenching, removal and/or installation of conduits or pipes, trench backfill, and patching. Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of small concrete pads for electrical transformers and equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traf signal facilities and installation of electrical and communication conduits. Paterior of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, Installation of AC or concrete berms or curbs, Installation of Concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			
Road Rehabilitation Demolition and replacement of PCC, removal and repair and replacement of entire pavement section including PCC or AC and underlying pavement structure materials. Trenching, removal and/or installation of conduits or pipes, trench backfill, and patching. Traffic Signal Modernization and/or Installation of Note Installation Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical conduits, backfill, patching, augering and placement of small concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of small concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of trafficilities and installation of electrical and communication conduits. Paternal Protection Installation of anothors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete betters. Earth or lined ditches	2	Road Resurfacing	Cut and replace asphalt, place more than 1-1/2 inches
repair and replacement of entire pavement section including PCC or AC and underlying pavement structure materials. Trenching, removal and/or installation of conduits or pipes, trench backfill, and patching. Traffic Signal Modernization and/or Installation of relocations Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardraits and end treatments, relocating street lights, grading transpers shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of trafficing and or shaping; sometimes installation of trafficing and/or shaping; sometimes installation of trafficing and or shaping; sometimes installation of trafficing and or shaping; sometimes installation of trafficing and removal of boulders. Trenching and removal of boulders. Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of concrete between curry.			
including PCC or AC and underlying pavement structure materials. Electrical, water, sewer, drainage, communication or other utility installation or relocations Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of trafisignal facilities and installation of electrical and communication conduits. Paterining Walls or Sound Walls Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, Installation of Cactchment, inlet or outlet structures, installation of Concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	3	Road Rehabilitation	
Structure materials. Structure materials. Trenching, removal and/or installation of conduits or other utility installation or relocations Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of trafficiant or signal facilities and installation of electrical and communication conduits. Installation of trees, shrubs, irrigation facilities and other architectural features. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of Concrete berms or curbs, installation of Concrete berms or curbs, installation of Concrete berms or curbs, installation of Concrete berms or curbs.			
Electrical, water, sewer, drainage, communication or other utility installation or relocations Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traffic sign and formulation conduits. Retaining Walls or Sound Walls Rockfall Protection Trenching, installation of electrical and communication conduits, backfill, patching, replacement of concrete light foundations, placement of small concrete light foundations, placement of small concrete getters. Earth or lined ditches		**	
drainage, communication or other utility installation or relocations Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical equipment. Trenching, installation of electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Improvements Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of trafficial and communication conduits. Installation of trees, shrubs, irrigation facilities and other architectural features. Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, Installation of Concrete berms or ourbs, Installation of Concrete berms or curbs, Installation of Concrete gutters.			
other utility installation or relocations Traffic Signal Modernization and/or Installation Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of trafficial equipments. Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, installation of concrete gutters. Earth or lined ditches	4		
relocations Traffic Signal Modernization and/or Installation Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, installation of concrete gutters. Earth or lined ditches			pipes, trench backfill, and patching.
Trenching, installation of electrical and communication conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Improvements Intersection Improvements Intersection Improvements Intersection Improvements Installation of pavernent structures & sidewalks; mino grading and/or shaping; sometimes installation of trafficial for footings and walls. Installation of provements installation facilities and other architectural features. Retaining Walls or Sound Walls Rockfall Protection Trenching, installation of electrical equipment. Trenching, installation of pavernent of electrical equipment. Trenching, installation of electrical equipment. Excavation for shoulder pavernent structures, installation of catchment, inlet or outlet structures, installation of concrete berms or curbs, Installation of concrete patch in and part of pavernent s			
and/or Installation conduits, backfill, patching, replacement of traffic sign hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Improvements Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Landscape Improvements Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, Installation of Corconcrete gutters. Earth or lined ditches			
hardware, installation of poles & mast arms, augering and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Retaining Walls or Sound Walls Rockfall Protection Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	Ö		
and placement of concrete foundations, placement of small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of actchment, inlet or outlet structures, installation of concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches		and/or installation	
Small concrete pads for electrical equipment. Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			
Trenching, installation of electrical conduits, backfill, patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Improvements Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			
patching, augering and placement of concrete light foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Intersection Improvements Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication condults. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	6	Lighting Improvements	
foundations, placement of small concrete pads for electrical transformers and equipment. Guardrail and Shoulder Improvements Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of Concrete berms or curbs, linstallation of concrete berms or curbs, linstallation of concrete gutters. Earth or lined ditches	•	Lighting improvements	
Guardrail and Shoulder Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Intersection Improvements Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication condults. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			
Guardrail and Shoulder Improvements Excavation for shoulder pavement section, install concrete sidewalks and wheel chair ramps, guardrails and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of actchment, inlet or outlet structures, installation of concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			electrical transformers and equipment
Improvements concrete sidewalks and wheel chair ramps, guardraits and end treatments, relocating street lights, grading to "shape" shoulder areas. Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Rockfall Protection Rockfall Protection Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of concrete gutters. Earth or lined ditches	7	Guardrail and Shoulder	
and end treatments, relocating street lights, grading to "shape" shoulder areas. Intersection Improvements Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			concrete sidewalks and wheel chair ramps quardrails
#shape" shoulder areas. Intersection Improvements Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication condults. Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. Excavation and backfill for footings and walls. Rockfall Protection Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			and end treatments, relocating street lights, grading to
Intersection Improvements Installation of pavement structures & sidewalks; mino grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication condults. Installation of trees, shrubs, irrigation facilities and other architectural features. Installation of trees, shrubs, irrigation facilities and other architectural features. Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			"shape" shoulder areas.
grading and/or shaping; sometimes installation of traff signal facilities and installation of electrical and communication conduits. 10 Retaining Walls or Sound Walls Excavation and backfill for footings and walls. 11 Rockfall Protection Excavation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. 12 Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of Concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	8	Intersection Improvements	
signal facilities and installation of electrical and communication conduits. 1 Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. 1 Retaining Walls or Sound Walls Excavation and backfill for footings and walls. 1 Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. 1 Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			
communication conduits. 1 Landscape Improvements Installation of trees, shrubs, irrigation facilities and other architectural features. 10 Retaining Walls or Sound Walls Excavation and backfill for footings and walls. Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. Trenching and replacement of drainage pipes, Installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			signal facilities and installation of electrical and
other architectural features. 10 Retaining Walls or Sound Walls Excavation and backfill for footings and walls. 11 Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. 12 Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			communication conduits.
10 Retaining Walls or Sound Walls Excavation and backfill for footings and walls. 11 Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. 12 Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	9	Landscape Improvements	Installation of trees, shrubs, irrigation facilities and
11 Rockfall Protection Installation of anchors, restraining or containment mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. 12 Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			
mesh, restraining or containing of containing of containing of containing or mesh, restraining or energy absorbing fencing. Slope scaling and removal of boulders. 12 Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches		Retaining Walls or Sound Walls	Excavation and backfill for footings and walls.
scaling and removal of boulders. 12 Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	11	Rockfall Protection	Installation of anchors, restraining or containment
Drainage Improvements Trenching and replacement of drainage pipes, installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches			mesh, restraining or energy absorbing fencing. Slope
installation of catchment, inlet or outlet structures, installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	40		scaling and removal of boulders.
installation of AC or concrete berms or curbs, Installation of concrete gutters. Earth or lined ditches	12	Drainage Improvements	Trenching and replacement of drainage pipes,
Installation of concrete gutters. Earth or lined ditches			installation of catchment, inlet or outlet structures,
Installation of concrete gutters. Earth or lined ditches and/or swales.			installation of AC or concrete berms or curbs,
and/or swales.			Installation of concrete gutters. Earth or lined ditches
		1	and/or swales.

Exclusions (Section 14, ArtIcle 13.5, ROH)

- 1. Excavation which does not alter the general drainage pattern with respect to abutting properties, which does not exceed 50 cubic yards of materials on any one site, and does not exceed three feet in vertical height at its deepest point; provided that the cut meets the cut slopes and distance from property lines requirement in Section 14-15.1, ROH (attachment D).
- 2. Fill which does not alter the general drainage pattern with respect to abutting properties, which does not exceed 50 cubic yards of materials on any one site, and does not exceed three feet in vertical height at its deepest point; provided that the cut meets the cut slopes and distance from property lines requirement in Section 14-15.1, ROH.
- Grubbing that does not alter the general drainage pattern with respect to abutting properties and does not exceed a total of 15,000 square feet.

the corrective measures to be taken. Grading operations shall cease until corrective measures satisfactory to the chief engineer have been taken. In addition, whenever the work is not being done in conformance with a NPDES permit, the state department of health will be notified.

(Sec. 23-2.9, R.O. 1978 (1983 Ed.); Am. Ord. 92-122)

Article 15. Grading, Grubbing and Stockpiling

Sections:

14-15.1 Conditions of permit.

14-15.2 Special requirements.

Sec. 14-15.1 Conditions of permit.

The requirements of subsections (a), (b) and (c) may be modified by the director of planning and permitting based on the engineer's soils report and engineering slope hazard report.

- (a) Height. Where a cut or fill is greater than 15 feet in height, terraces or benches shall be constructed at vertical intervals of 15 feet except that where only one bench is required, it shall be at the midpoint. The minimum width of such terraces or benches shall be at least eight feet and provided with drainage provisions to control erosion on the slope face and bench surface.
- (b) Cut Slopes. Under the following soil conditions, no cut may be steeper in slope than the ratio of its horizontal to its vertical distance as shown below:
 - (1) One-half horizontal to one vertical in unweathered rock or mudrock;
 - (2) One horizontal to one vertical in decomposed rock;
- (3) One and one-half horizontal to one vertical in soils of low plasticity, cuts of any height in highly plastic soils shall be as recommended in the applicable report.
- (c) Fill Slopes. Fills shall not be steeper than a ratio of two horizontal to one vertical except that fill using highly plastic clays shall have slopes as recommended in the applicable report.
- (d) Distance from property line. The horizontal distance from the top of a cut slope or the bottom of a fill slope to the adjoining property line shall not be less than as follows:

Distance from Property Height of Cut or Fill Line (in feet)

Zero feet to 4 feet 2
More than 4 feet to 8 feet 4
More than 8 feet to 15 feet
More than 15 feet 8

These requirements may be modified by the director of planning and permitting when cuts or fills are supported by retaining walls or when the permittee submits an engineer's soils report or engineering slope hazard report stating that the soil conditions will permit a lesser horizontal distance without causing damage or danger to the adjoining property.

(e) Area Opened. The maximum-sized parcel of land that may be opened for grading or grubbing is 15 acres. Noncontiguous increments may be worked concurrently provided no single parcel exceeds 15 acres, provided the work is in conformance with the NPDES permit. The area of land that may be opened may be reduced by the director of planning and

Tall domen P

permitting to control pollution and minimize storm damage. However, if soils, hydrologic, climatic and construction conditions warrant, and adequate erosion prevention measures have been taken, the director of planning and permitting may authorize additional area to be opened. Additional area may not be opened for grading or grubbing until measures to prevent dust or erosion problems in the area already graded or grubbed have been undertaken to the satisfaction of the director.

- (f) Fills. The requirements of subdivisions (1), (2) and (3) may be modified by the director of planning and permitting if the permittee submits an engineer's soils report recommending criteria for the proposed fill for its intended use.
- (1) Fill material shall be selected to meet the requirements and conditions of the particular fill for which it is to be used. The fill material shall not contain vegetation or organic matter. Where rocks, concrete, or similar materials of greater than eight inches in diameter are incorporated into the fill, they shall be placed in accordance with the recommendation of a soils engineer.
- (2) Preparation of Ground Surface. Before placing or stockpiling, the natural ground surface shall be prepared by removing the vegetation and, if required by the director of planning and permitting, shall be notched by a series of benches and/or subsurface drains installed. No fill shall be placed over any water spring, marsh, refuse dump, nor upon a soft, soggy or springy foundation; provided, that this requirement may be waived by the director of planning and permitting if the permittee submits an engineer's soils report recommending criteria for the fill.
- (3) Placement and Compaction. Fill materials shall be spread and compacted in a series of eight-inch to 10-inch layers when compacted, unless otherwise recommended by the soils engineer. Except for slopes, the fill shall be compacted to 90 percent of maximum density as determined by the most recent ASTM soil compaction test D1557 unless the engineer's soils report justifies a lesser degree of compaction, or unless otherwise recommended by the soils engineer.
- (g) Vegetation. Whenever feasible, natural vegetation should be retained by becoming part of the erosion control plan during construction or part of the permanent landscaping plan if applicable. If it is necessary that vegetation be removed, trees, timber, plants, shrubbery and other woody vegetation, after being uprooted, displaced or dislodged from the ground by excavation, clearing or grubbing, shall not be stored or deposited along the banks of any stream, river or natural watercourse. After being uprooted, displaced or dislodged, such vegetation shall be disposed of by means approved in writing by the director of planning and permitting or removed from the site within a reasonable time, but not to exceed three months.
- (h) Drainage Provisions. Adequate provisions shall be made to prevent surface waters from damaging the cut face of an excavation or the sloped surfaces of a fill. Positive drainage shall be provided to prevent the accumulation or retention of surface water in pits, gullies, holes or similar depressions. All drainage facilities shall be designed to carry surface waters to a street, storm drain inlet or natural watercourse and shall include an erosion and sedimentation control plan to prevent sediment-laden runoff from leaving the site, either during or following construction. The director of planning and permitting may require such detention or retention drainage structures and pipes to be constructed or installed, which in the director's opinion, are necessary to prevent erosion damage, prevent sediment-laden runoff from leaving the site, and to satisfactorily carry off surface waters. The flow of any existing and known natural underground drainage shall not be impeded or changed so as to cause damage to adjoining property.
- (i) Debris Prohibited. No person shall perform any grading operation so as to cause falling rocks, soil or debris in any form to fall, slide or flow onto adjoining properties, streets or natural watercourses.

- (j) Work Days. No grading work shall be done on Saturdays, Sundays and holidays at any time without prior notice to the director of planning and permitting, provided such grading work is also in conformance with Hawaii Administrative Rules, Chapter 11-43, "Community Noise Control for Oahu."
- (k) Dust Control. All work areas within and without the actual grading area shall be maintained free from dust which will cause a nuisance or hazard to others and in conformance with the air pollution control standards contained in Hawaii Administrative Rules, Chapter 11-60, "Air Pollution Control."
- (l) Water Quality Standards. All grading operations authorized under Articles 13 through 16 of this chapter shall be performed in conformance with the applicable provisions of the water pollution control and water quality standards contained in Hawaii Administrative Rules, Chapter 11-55, "Water Pollution Control" and Chapter 11-54, "Water Quality Standards" and if applicable, the NPDES permit for the project. Any dewatering discharge into state waters will require an NPDES permit from the department of health under Chapter 11-55, "Water Pollution Control." Any dewatering discharge into the city-owned storm sewer system will require a construction dewatering permit from the director of planning and permitting and an NPDES permit for the discharge of any pollutant into state waters through the city-owned storm sewer system from the department of health, State of Hawaii. (m) Notification of Completion. The permittee or the permittee's agent shall notify the director of planning and permitting or the director's representative when the grading operation is ready for final inspection. Final approval shall not be given until completion of all work including installation of all drainage structures and their protective devices, completion of all planting showing a healthy growth in conformance with the approved plans and specifications, and the required reports have been submitted.
- (1) When grading involves cuts or fills for which an engineer's soils report was required, the permittee shall submit a

final report, prepared by an engineer, upon the completion of such work. This report shall contain:

(A) A description of materials used in the fill and its moisture content at the time of compaction, the

procedure used in depositing and compacting the fill, the preparation of original ground surface before

making the fill, but not limited to benching and subsurface drainage, and a plan or tabulation showing the

general location and elevation of compaction tests made in the fill together with a tabulation of relative

compaction densities obtained at each location, the location of subdrains and other pertinent features of

the fill necessary for its stability.

(n) Report After Grading.

(B) A certification that the work was done in conformity to this chapter, the approved plans and

specifications and the engineer's soils report.

(2) Where a slope hazard evaluation and mitigation plan was required to be submitted with a grading permit

application, the permittee shall submit a final assessment report, prepared by an engineer, upon the completion of

site work, prior to building construction. The assessment report shall contain a verification that the prevention

measures and any stabilization measures called for in the engineering slope hazard report or construction plans

were done in conformity with this chapter, and the approved plans and specifications.

(o) As-Graded Plan. Upon completion of grading areas over one acre or areas graded under subdivision rules, an as-graded plan prepared by an engineer or land surveyor shall be submitted if required by the director of planning and permitting.

(Sec. 23-3.1, R.O. 1978 (1983 Ed.); Am. Ord 92-122, 04-27)

Sec. 14-15.2 Special requirements.

- (a) Any person performing or causing to be performed any excavation or fill shall, at such person's own expense, provide the necessary means to prevent the movement of earth of the adjoining properties, to protect the improvements thereon, and to maintain the existing natural grade of adjoining properties.
- (b) Any person performing or causing to be performed, any excavation or fill shall be responsible for the maintenance or restoration of street pavements, sidewalks and curbs, and improvements of public utilities which may be affected. The maintenance or restoration of street pavements, sidewalks and curbs shall be performed in accordance with the requirements of the City and County of Honolulu and the maintenance and restoration of improvements of public utilities shall be in conformity with the standards of the public utility companies affected. At cuts fronting any street, a suitable and adequate barrier shall be installed to provide protection to the public.
- (c) Any person depositing or causing to be deposited, any silt or other debris in ditches, watercourses, drainage facilities and public roadways, shall remove such silt or other debris. In case such person shall fail, neglect or refuse to comply with the provisions of this section within 48 hours after written notice, served upon such person, either by mail or by personal service, the chief engineer may proceed to remove the silt and other debris or to take any other action the chief engineer deems appropriate. The costs incurred for any action taken by the chief engineer shall be payable by such person.
- (d) At any stage of the grading, grubbing or stockpiling work, if the chief engineer finds that further work as authorized by an existing permit is likely to create soil erosion problems or to endanger any life, limb or property, the chief engineer may require safety precautions, which may include but shall not be limited to the construction of flatter exposed slopes, the construction of additional silting or sediment basins, drainage facilities or benches; the removal of rocks, boulders, debris and other dangerous objects which, if dislodged, are likely to cause injury or damage; the construction of fences or other suitable protective barriers; or may refer to the local soil and water conservation district for advice from the soil conservation service or other appropriate agencies on the planting or sodding of slopes and bare areas. All planted or sodded areas shall be maintained. An irrigation system or watering facilities may be required by the chief engineer.
- (e) At any stage of the grading, grubbing or stockpiling operations, if the chief engineer finds that further work as authorized by an existing permit is likely to create dust problems which may jeopardize health, property or the public welfare, the chief engineer may require additional dust control precautions and, if these additional precautions are not effective in controlling dust, may stop all operations. These additional dust control measures may include such items as sprinkling water, applying mulch treated with bituminous material, or applying hydro mulch.
- (f) Hillside lots shall be graded in such a manner that any parcels which may be created therefrom, including all separate building sites which may be contained within said parcels, can be satisfactorily graded and developed as individual building sites. (Sec. 23-3.2, R.O. 1978 (1983 Ed.))

Article 16. Violations, Penalties and Liabilities for Grading, Grubbing and

Stockpiling

Sections:

- 14-16.1 General.
- 14-16.2 Notice of violation-Stop work.
- 14-16.3 Criminal prosecution.
- 14-16.4 Administrative enforcement.
- 14-16.5 Liability.
- 14-16.6 Rule-making powers.
- 14-16.7 Decisions of the chief engineer.

Sec. 14-16.1 General.

It is unlawful for any person to do any act forbidden, or to fail to perform any act required, by the provisions of Articles 13 through 16 of this chapter. Whenever a corporation violates any of the provisions of Articles 13 through 16 of this chapter, the violation shall be deemed to be also that of the individual directors, officers or agents of the corporation who in their capacity as directors, officers or agents of such corporation have authorized, ordered or done any of the acts constituting in whole or in part such violation. (Sec. 23-4.1, R.O. 1978 (1983 Ed.); Am. Ord. 90-71)

Sec. 14-16.2 Notice of violation-Stop work.

- (a) Whenever any person, firm or corporation violates any provision of Articles 13 throught 16 of this chapter, the chief engineer shall serve the person, firm or corporation with a notice of violation which shall require the person, firm or corporation responsible to correct the violation.
- (b) The notice of violation shall include but not be limited to the following information:
 - (1) The date of issuance of the notice:
- (2) The name and address of the person or entity notified and the location of the violation;
 - (3) The section number of the ordinance, code or rule which has been violated;
 - (4) The nature of the violation; and
 - (5) An order to stop work if deemed necessary by the chief engineer; and
 - (6) The deadline for correction of the violation.
- (c) If the chief engineer deems it necessary for work to stop, the work shall cease upon receipt of the notice and shall not resume until corrective measures satisfactory to the chief engineer have been taken. If the notice includes a stop work order, the chief engineer shall notify and transmit a copy to the chief of police concurrently with the issuance of the notice. The chief of police shall have the power to enforce the stop work order pursuant to Section 6-1604, Revised Charter of Honolulu, 1973, as amended. (Added by Ord. 90-71; Am. Ord. 91-07)

Sec. 14-16.3 Criminal prosecution.

Any person, firm or corporation violating any of the provisions of Articles 13 through 16 of this chapter shall be deemed guilty of a misdemeanor for each and every day or portion thereof during which any violation of any provisions of this chapter is committed and, upon conviction of any such violation, such person shall be punishable by a fine of not more than \$1,000.00 or by imprisonment for not more than one year, or by both fine and imprisonment. (Added by Ord. 90-71)

Sec. 14-16.4 Administrative enforcement.