

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	72C-01-00	2000	ADD. 11	16

1	CONDUIT	CABLE
2" Exist.	1-26c#14 New	
2" Exist.	1-26c #14 New	
2" Exist.	1-2c #14 New	

2	CONDUIT	CABLE
2" Exist.	1-26c#14 New	
2" Exist.	1-26c #14 New	
2" Exist.	1-2c #14 New	
2" Exist.	1-3c #20 New	

3	CONDUIT	CABLE
2" Exist.	1-26c #14 New	
2" Exist.	1-26c #14 New	
2" Exist.	3-2c #14 New	
2" Exist.	1-3c #20 New	

4	CONDUIT	CABLE
2" Exist.	1-3c #6 New	
2" Exist.	1-12PR #19 New	

5	CONDUIT	CABLE
2" Exist.	1-3c #6 New	
2" Exist.	1-12PR #19 New	

6	CONDUIT	CABLE
2" Exist.	1-26c#14 New	
2" Exist.	1-26c#14 New	
2" Exist.	1-3c#6 New	
2" Exist.	1-12PR #19 New	
	1-Video Coaxial	
	4-#22 Control	
	3-#14 SVT Power	
2" Exist.	4-2c #14 New	
2" Exist.	2-3c #20 New	

7	CONDUIT	CABLE
2" New	1-26c#14 New	
2" New	1-26c#14 New	
2" New	1-26c #14 New	
2" New	1-26c #14 New	
2" New	1-3c #14 New	
2" New	2-12PR #19 New	
	1-24 Strand Fiberoptic	
2" New	5-2c #14 New	
2" New	5-2c #14 New	
2" New	4-3c #20 New	

8	CONDUIT	CABLE
2" Exist.	1-26c#14 New	
2" Exist.	1-26c #14 New	
2" Exist.	5-2c #14 New	
2" Exist.	2-3c #20 New	
	1-12PR #19 New	
	1-24 Strand Fiberoptic	

9	CONDUIT	CABLE
2" Exist.	1-26c#14 New	
2" Exist.	1-26c #14 New	
2" Exist.	4-2c #14 New	
2" Exist.	1-3c #20 New	

10	CONDUIT	CABLE
2" Exist.	2-2c #14 New	

11	CONDUIT	CABLE
2" Exist.	2-2c #14 New	

12	CONDUIT	CABLE
2" Exist.	1-26c#14 New	
2" Exist.	1-26c#14 New	
2" Exist.	2-2c #14 New	
2" Exist.	1-3c #20 New	

13	CONDUIT	CABLE
2" Exist.	2-2c #14 New	

14	CONDUIT	CABLE
2" Exist.	2-2c #14 New	
2" Exist.	1-4c #14 New	

15	CONDUIT	CABLE
2" Exist.	1-2c #14 New	
2" Exist.	1-4c #14 New	

16	CONDUIT	CABLE
2" Exist.	1-4c #14 New	

17	CONDUIT	CABLE
2" New	1-3c #6 New	
2" New	1-3c #6 New	

18	CONDUIT	CABLE
2" New	1-12PR #19 Exist.*	
	1-24 Strand Fiberoptic	

19	CONDUIT	CABLE
2" New	1-24 Strand Fiberoptic	
2" New	1-Video Coaxial	
	4-#22 Control	
	2-3-#14 SVT Power	

20	CONDUIT	CABLE
	1-24 Strand Fiberoptic**	

21	CONDUIT	CABLE
2" Exist.	1-24 Strand Fiberoptic	

*Note: Exist. 1-12PR #19 Interconnect Cable shall be dropped from the overhead system via installed risers at junction poles located at Sta. 41+70± o/s 55± Rt. and 42+95± o/s 57± Rt., respectively. This work shall be coordinated with the C&C DTS.

**Note: New 24 Strand Fiberoptic Cable shall be attached to the existing overhead Fiberoptic Cable per C&C DTS requirements.

5/6/00 Add 26c #14 New to runs 1, 2, 3, 6, 7, 8, 9 & 12 and Add 12PR #19 to run 7 & 8 and Add Conduit/Cable Runs #18, 19, 20 & 21 and Notes. Add 24 Strand Fiberoptic to Runs 7 & 8.

DATE	REVISION
STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION TRAFFIC SIGNAL CONDUIT & CABLE SCHEDULE KALANIANA'OLE HIGHWAY Installation of Traffic Signals at Anali Street Project No. 72C-01-00 Scale: 20 Date: Jan., 2000 SHEET No. 1 OF 1 SHEETS	

SURVEY PLOTTED BY	DATE
DRAWN BY	
CHECKED BY	
QUANTITIES BY	
CHECKED BY	
ORIGINAL PLAN	
NOTE BOOK	
10/20/00	
10/20/00	