

| FED. ROAD DIST. NO. | STATE | FED. AID PROJ. NO. | FISCAL YEAR | SHEET NO. | TOTAL SHEETS |
|---------------------|-------|--------------------|-------------|-----------|--------------|
| HAWAII | HAW. | F-076-1(2) | 1990 | 3 | |
| S-RS-0760(2)R/W | | | | | |

LEGEND

| | |
|--|--|
| | Existing Street Survey Monument |
| | New Centerline or Street Survey Monument |
| | Existing Meter Box or Handhole |
| | Existing Manhole or Valve Box |
| | Existing Fire Hydrant |
| | New and/or Relocated Meter Box |
| | Relocated Valve Box |
| | Relocated Fire Hydrant |
| | Existing Electric Ductline |
| | New Electric Ductline |
| | Existing Telephone Ductline |
| | New Telephone Ductline |
| | Existing Electric Pole |
| | Existing Telephone Pole |
| | Existing Joint Pole |
| | Existing Electric, Telephone or Joint Pole to be Removed |
| | New Joint Pole |
| | Existing Anchor |
| | Existing Anchor to be Removed |
| | New Anchor |
| | Existing Sewer Force Main |
| | Existing Sewer Line |
| | Proposed Sewer Line |
| | Existing Water Line |
| | Existing Gas Line |

Denotes Hawaiian Electric Co., Inc.
E
2-4"
Denotes Duct Size
Denotes Number of Ducts

DUCTLINE IDENTIFICATION

GENERAL NOTES :

- Improvements consist of grading, paving, constructing drainage systems, installing traffic signal systems, sidewalk, highway lighting, traffic signs, pavement markers and striping, adjusting water, sewer, electric and telephone facilities and renovating the Ilima Intermediate School band storage room.
- The existence and locations of underground utilities and structures as shown on the plans are based upon records of varying degrees of accuracy and completeness and, as such, the encountering of other obstructions is not guaranteed against. The Contractor shall be liable for any damage to underground utilities or structures whether or not they are shown on the plans. Wherever connections of new utilities to existing utilities are shown, the Contractor shall expose the existing lines at the proposed connections to verify their locations and depths prior to excavation for the new lines.
- The Contractor shall make every effort to perform his work without closing any private driveways. Should such closure become unavoidable, the Contractor shall notify the affected parties at least three days in advance of the closure.
- Full compensation for all materials and labor not specifically shown or called for, which are necessary to complete the construction of the project, shall be considered incidental to the various contract items in the proposal and no additional compensation will be allowed therefor.
- Contractors bidding on this project shall verify the existing features at his own discretion prior to submitting a bid.
- Excavation, relocation of mailboxes and fences and any other work which is required to complete the driveway adjustments, but which is not paid for separately, will be considered incidental to Asphalt Concrete Mix No. V or Class A Concrete, whichever applies.

| | |
|-------------------|------|
| SURVEY PLATTED BY | DATE |
| DRAWN BY | |
| TRACED BY | |
| NOTED BY | |
| CHECKED BY | |
| ORIGINAL PLAN | |
| NOTE BOOK | |
| N. | |

| | |
|---------|--------------------------|
| 6/27/90 | Added General Note No. 6 |
| DATE | REVISION |

| |
|---|
| STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION GENERAL NOTES FORT WEAVER ROAD Hanakahi St. To Ewa Beach Rd. Proj. Nos. F-076-1(2) & S-RS-0760(2)R/W Date: Sept., 1989 |
| SHEET No. 1 OF 1 SHEETS |