



FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	CMAQ-076-(18)	2004	20	127

Planting Notes:

- Landscape Contractor Shall Field Verify All Plant Quantities And Dimensions Prior To Installation. Quantities Shown On Plant List Are For Reference Only. Verify Actual Quantities As Shown On Plan. If There Is A Discrepancy, The Planting Plan Shall Take Precedence. Plants Shall Govern.
- Landscape Contractor Shall Be Responsible For Locating And Protecting Existing Utilities.
- Prior To Tree And Shrub Hole Excavation, All Planting Locations Shall Be Staked Out By Contractor For Approval By Engineer. Do Not Plant Until Ground Has Been Prepared And Free Of Stones Greater Than 1/2" Dia. , Site Is Neat, Orderly, And The Engineer Accepts Site For Planting.
- Notify Engineer Of Any Discrepancies In Plant Locations Or Insufficient Plant Quantities Due To Difference In Plans And Actual Field Conditions.
- Notify Engineer 7 Days Prior To Planting Operations For Approval Of All Plant Material At Place Of Growth. All Plant Material Not Approved By The Engineer Will Be Subject To Rejection.
- The Engineer Will Inspect Plants At The Place Of Growth And After The Delivery To The Project. Each Tree Shall Be Tagged By The Engineer With A Consecutively Numbered Plastic Tamper-resistant And Self-locking Seal. Seals Shall Remain On Trees And Only Be Removed By The Engineer At The Completion Of The Plant Establishment Period. Trees Delivered To The Project Without The Engineers Seal Will Be Rejected.
- Plans Shall Meet Size Indicated By Minimum Height And Spread. Plants Shall Be Straight And Uniformly Shaped, Unless Unique Or Special Characteristics Are Specified, And Shall Be Undamaged, Sound, Healthy, Vigorous And Free Of Disease And Inspect Infestation. Plants Not Conforming To These Requirements On Delivery To The Project And At The End Of The Plant Establishment Period Will Be Rejected.

- Contractor Shall Be Solely Responsible For The Complete Removal And Damages Resulting From Planting Any Plant Species Listed On The Hawaii Department Of Agriculture "noxious Weed Rules" As Defined In The Statute, Hawaii Administrative Rules 4-88.1 Or The "Federal Noxious Weed List" As Defined In Title 7 Of The Code Of Federal Regulations (cfr), Parts 360 And 361.
- All Tree Work Must Adhere To American National Standard Institute (or Ansi) - A300 Tree Care Standards And Ansi-2133 Safety Standards For Tree Work. Work Shall Be Contracted To Arborists That Has Been Certified In Good Standings As An Isa Certified Arborist Or At Least 5 Years To Assure That Tree Work Is Performed Properly And Trees Are Not Damaged By Practices Such As Topping, Flush Cuts, Over-thinning Or Climbing With Spikes. Contractor Shall Submit A Copy Of The Isa Arborist Certification Of Good Standing Of 5 Years To The Engineer Minimum 7 Days Prior To Tree Pruning.

- If Trees Other Than Those Specifically Designated For Removal Are Damaged Beyond Survival Conditions Are Determined By Engineer, The Contractor Shall Remove Such Trees And Replace The Tree With A Same Specie And Size And Maintain For The Duration Of Construction Or 12 Months Whichever Is Greater At No Cost To The State.
- Guy Wires, Flagging, Stakes, Windbreakers, Etc. Shall Be Maintained And Replaced If Necessary By The Contractor Until The Tree Or Shrub Is Able To Stand By Itself. The Contractor Shall Remove And Dispose At The End Of Plant Establishment Period.
- Any Planting That Obstructs Sight Distance, Signs, Or Traffic Lights Shall Be Relocated As Determined By The Engineer.

LEGEND FOR AS-BUILT POSTINGS

	Squiggly line for as-built deletion
	Double line for as-built deletion
	Text for as-built posting



SIGNATURE
APRIL 30, 2004
EXPIRATION DATE OF LICENSE
THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION.

Revision	06/17/04	Revised Ramp C BL & LT EP Alignment Data
	Date	Description
STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION PLANTING PLAN FORT WEAVER ROAD WIDENING NEAR LAULANNU STREET FEDERAL AND PROJECT NO. CMAQ-076-(18) SCALE: 1"=20' DATE: October 2003 SHEET NO. 1 OF 1 SHEETS		

"AS-BUILT"

128 S-1