

NOTES ON BASE COURSE AND PAVEMENT.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	HSBT NO.	TOTAL SHEETS
HAWAII	HAW.	1-D	1932	2	57

BASE COURSE : The 6" Base Course shall be either a "Crusher Run Base Course" or a "Coral Base Course"; these being as noted below.

CRUSHER RUN BASE COURSE : 6" (compacted thickness) of Crusher Run Material (20% wear).
CORAL BASE COURSE : 6" (measured loose) of No 0 Coral (6" to 2") completely filled with sufficient No 2 Coral (2" to 1") to make 6" of material when the course is fully compacted.

PAVEMENT : The 3" pavement shall be either the "Asphaltic Macadam Surface Course" and "Seal Coat" or a "Cold Emulsified Asphalt Pavement"; these being as noted below.

ASPHALTIC MACADAM SURFACE COURSE : 3" (compacted thickness) No 1 Crushed rock (3 1/2" to 1"); 14 lbs. per sq. yd. asphalt (85-100); and sufficient No 3 Crushed Rock (1" to 3/8"); to cover.

SEAL COAT : 3 to 4 lbs. per sq. yd. asphalt (85-100); and sufficient No 6 Crushed Rock (1/4" to 1/8"); to cover.

COLD EMULSIFIED ASPHALT PAVEMENT : 3" (Compacted thickness) No 1 Crushed Rock (3 1/2" to 1"); filled to within one inch of top with No 5 Crushed Rock (3/8" to #10); 1 gal. per sq. yd. of emulsion; sufficient No 4 Crushed Rock (3/8" to #10); to key surface; 1 1/8 to 1 1/4 gals. per sq. yd. of emulsion; sufficient No 5 Crushed Rock (3/8" to #10); to complete surface keying; 3/8 gal. per sq. yd. of emulsion and sufficient No 6 Crushed Rock (1/4" to #20); to cover.

GENERAL NOTES : Particular reference is made to the specifications covering these items of work.

Note: Side roads are to be treated the same as driveways with 8 ft. radius on turnout except where other treatment is indicated on the plans.

NOTE :
Side ditches from gutter where required are to have the same sections as standard outlet ditches from 18" culverts.

