

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	83B-01-78	1980	2	8

BASELINE CURVE DATA					
NO.	N. COORDINATE	E. COORDINATE	DATA		
23	P.C.	-1148.89	204.77	Δ	28°46'51.3"
	P.T.	-975.08	406.04	R	535.00'
	C.C.	-669.77	-33.29	T	137.27'
	P.I.	-1087.81	327.70	L	268.74'
24	P.C.	-966.87	411.75	Δ	11°16'38.08"
	P.T.	-922.00	449.98	R	300.00'
	C.C.	-1138.07	658.10	T	29.62'
	P.I.	-942.55	428.65	L	59.05'
25	P.C.	-922.00	449.98	Δ	33°51'37.1"
	P.T.	-845.70	492.53	R	150.00'
	C.C.	-813.97	345.92	T	45.66'
	P.I.	-890.33	482.87	L	88.65'

W/W @ Sta. 20+56.14 to W/W @ Sta. 20+61.64 and
W/W @ Sta. 23+30.38 to W/W @ Sta. 23+35.88
New Concrete Approach Slab. For Details
See Sht. Nos. 6, 7 & 8.

W/W @ Sta. 23+35.88
Match Bituminous Sidewalk
to Top and Grade of New
Conc. Approach Slab.

W/W @ Sta. 20+55±
Removal of Existing Wooden
Barricade shall not be paid
for separately but shall be
made incidental to the various
contract items.

GENERAL NOTES

- The Contractor shall limit his construction operations and/or temporary storage of material and equipment within Easements E-1, E-2, E-3, E-4, E-5; Construction Parcels C-1, C-2, C-3, C-4; and the State's Highway Right of Way. The Contractor may obtain additional Construction Parcels at his own expense.
- The Contractor's attention is directed to Section 639 - Temporary Project Water Pollution Control (Soil Erosion) of the Standard Specifications.
- Excavation, Imported Borrow and Embankment for Walkway shall not be paid for separately but shall be made incidental to Bituminous Sidewalk.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
LAND TRANSPORTATION FACILITIES DIVISION

PLAN
WAIMEA RIVER FOOTBRIDGE
Proj. No. 83B-01-78

Scale: 1" = 20' Date: April, 1979
SHEET NO. 1 OF 1 SHEETS