HAZARDOUS MATERIALS SURVEY REPORT

KAIPAPAU STREAM BRIDGE REPLACEMENT HAU'ULA, OAHU, HAWAII

Prepared for: **R.M. TOWILL CORPORATION** 2024 North King Street, Suite 200 Honolulu, HI 96819

Prepared by: ENVIROSERVICES & TRAINING CENTER, LLC 505 Ward Avenue, Suite 202 Honolulu, Hawaii96814 tel: (808) 839-7222

ETC Project No. 19-4007

April 26, 2019

TABLE OF CONTENTS

1.0	CERTIFICATIONS AND LIMITATIONS	2
EXECU	TIVE SUMMARY	3
1.1 1.2 1.3	SUMMARY OF ASBESTOS CONTAINING MATERIALS SURVEY Summary of Lead Paint Survey Summary of Arsenic Survey	
2.0	INTRODUCTION/PURPOSE	4
3.0	METHODOLOGY	5
3.1 3.2 3.3	Asbestos Lead Paint Arsenic	5
4.0	RESULTS	6
4.1 4.2 4.3	Asbestos Lead Paint Arsenic	6
5.0	DISCUSSION AND RECOMMENDATIONS	7

APPENDICES

APPENDIX I:	
APPENDIX II:	LABORATORY ANALYTICAL REPORTS AND CHAIN-OF-CUSTODY FORMS
APPENDIX III:	PHOTOGRAPHIC DOCUMENTATION

1.0 CERTIFICATIONS AND LIMITATIONS

EnviroServices & Training Center, LLC (ETC) has completed a Limited Hazardous Materials Survey (Survey) for R.M. Towill Corporation at Kaipapau Buildings located at buildings identified by Tax Map Key (TMK) 5-4-18: Parcel 003, Kamehameha Highway, Oahu, Hawaii (Subject Site). ETC's findings and recommendations contained herein are based on site observations, government regulations and laboratory data, which were gathered at the time and location of the study. Opinions stated in this report do not apply to changes that may have occurred after the services were performed.

ETC has performed specified services for this project with the degree of care, skill and diligence ordinarily exercised by professional consultants performing the same or similar services. No other warranty, guarantee, or representation, expressed or implied, is included or intended; unless otherwise specifically agreed to in writing by both ETC and ETC's Client.

This report is intended for the sole use of R.M. Towill Corporation. exclusively for the Subject Site. R.M Towill Corporation may use and release this report, including making and retaining copies, provided such use is limited to the particular site and project for which this report is provided. However, the services performed may not be appropriate for satisfying the needs of other users. Release of this report to third-parties will be at the sole risk of ETC's Client and/or said user, and ETC shall not be liable for any claims or damages resulting from or connected with such release or any third party's use or reuse of this report.

Surveyed By:	Velverdee Roberts State of Hawaii Asbestos Building Inspector # HIASB-0315 State of Hawaii Lead Building Inspector # PB-0041
Surveyed/ Prepared By:	Daniel Woo State of Hawaii Asbestos Building Inspector # HIASB-4697 State of Hawaii Lead Building Inspector # PB-1075
Surveyed/ Prepared By:	Jacob Valencia State of Hawaii Asbestos Building Inspector # HIASB-4696 State of Hawaii Lead Building Inspector # PB-1074

EXECUTIVE SUMMARY

EnviroServices & Training Center, LLC (ETC) conducted a Limited Hazardous Materials Survey (Survey) and compiled this report for R.M. Towill Corporation at Kaipapau Buildings located at buildings identified by Tax Map Key (TMK) 5-4-18: Parcel 003, Kamehameha Highway, Oahu, Hawaii (Subject Site). The following hazardous materials were identified during ETC's survey of buildings A (main house) and B (studio):

1.1 Summary of Asbestos Containing Materials Survey

Laboratory analysis determined that the following material contains asbestos above the regulatory limit of 1%:

- Black mastic on pipe penetration on roof B
- Black Mastic under white caulking on pipe penetration on roof B
- Rolled on roofing on roof B

1.2 Summary of Lead Paint Survey

Laboratory analysis determined that the sampled paints do not contain detectable levels of lead above the laboratory detection limit and are considered to be non-lead-containing.

1.3 Summary of Arsenic Survey

None of the materials sampled were found to contain detectable levels of arsenic.

2.0 INTRODUCTION/PURPOSE

The purpose of this Survey was to inspect the Subject Site for the presence of suspected hazardous materials that may be affected by the project. The Survey was conducted on April 15, 2019and limited to the areas specified by R.M. Towill Corporation. Specifically, ETC completed the following tasks:

- Performed site reconnaissance at the Subject Site;
- Collected sixty (60) samples of suspected Asbestos-Containing Material (ACM) from the Subject Site;
- Submitted the 60 samples of suspected ACM to EMC Labs, Inc. (EMC) for analysis of asbestos via Polarized Light Microscopy (PLM) in accordance with the Environmental Protection Agency (EPA) Method 600/R-93/116;
- Collected four(4) paint chip samples from the Subject Site;
- Submitted the 4paint chip samples to EMC for analysis by flame atomic absorption spectroscopy (FAAS) via EPA Method 7000 for total lead content;
- Conducted a visual inspection for suspect arsenic-containing materials, and
- Collected one (1) arsenic sample from the Subject Site;
- Prepared this report documenting the field activities and the results of the investigation including analytical results, conclusions, and recommendations.

3.0 METHODOLOGY

3.1 Asbestos

ETC personnel collected 60 samples of suspected ACM for asbestos analysis. Samples were collected from various areas of the Subject Site in accordance with EPA guidelines and recommendations.

The suspected ACM were wetted with amended water before sample collection. A small piece was then carefully cut out and placed into a labeled, re-sealable plastic bag. The sampling equipment was cleaned between each sample collection to avoid cross-contamination between samples. The approximate quantity of each suspected ACM was noted. Sample locations were randomly selected in accordance with EPA protocols and recommendations.

Samples were properly logged and recorded following strict chain-of-custody procedures, and sent to EMC located in Phoenix, Arizona, for analysis by PLM in accordance with EPA Method 600/R-93/116. EMC is accredited for bulk asbestos analysis through successful participation in the National Voluntary Lab Accreditation Program (NVLAP).

3.2 Lead Paint

ETC personnel collected and had 4paint chip samples analyzed in accordance with the EPA guidelines and recommendations.

The suspected lead-containing paints were wetted with amended water before sample collection. Paint was carefully scraped and placed into a labeled re-sealable plastic bag. The sampling equipment was cleaned between each sample collection to avoid cross-contamination between samples. Samples were properly logged and recorded following strict chain of custody procedure and submitted to EMC for analysis by FAAS, in accordance with EPA Method 7420.EMC is an Environmental Lead Laboratory Accreditation Program (ELLAP)-accredited laboratory.

3.3 Arsenic

ETC personnel collected 1 sample of fiberboard material, suspected of being treated with arsenic, from the Subject Site. The suspected arsenic treated samples were collected in accordance with EPA guidelines and recommendations.

The suspected arsenic treated materials were wetted with amended water before sample collection. Small pieces were then carefully cut out and placed into a labeled, re-sealable plastic bag. The samples were logged and recorded following strict chain of custody procedure and submitted to NVL Laboratories, Inc. for analysis by EPA Method 6010.

4.0 **RESULTS**

4.1 Asbestos

Laboratory analysis determined that the following material contains asbestos above the regulatory limit of 1%:

- Black mastic on pipe penetration on roof B
- White Caulking on pipe penetration with black mastic on roof B
- Rolled on roofing on roof B

In accordance with federal and state regulations and industry standard practice, ETC determined homogenous areas of each suspect material and collected multiple representative samples of the material from each homogenous area. Typically, all samples for a suspect material will have similar laboratory results. When the results differ, a single result above the regulatory limit is sufficient to determine that the material within the homogenous area is ACM and the entirety of the homogenous area should be treated as ACM. Thus, ETC may request that the laboratory stops analyzing when the first sample in the set is determines to have asbestos content above one percent.

In addition, six (6) materials were found to contain glass fibers. Although materials containing such fibers are not specifically regulated, it is ETC's recommendation to handle materials containing glass fibers with appropriate protective equipment.

The asbestos analytical laboratory report is included in Appendix II.

4.2 Lead Paint

The sampled paints did not contain detectable levels of lead and are considered to be non-lead-containing.

The lead analytical laboratory reportis included in Appendix II.

4.3 Arsenic

The sampled suspect arsenic containing material did not contain detectable levels of arsenic.


The arsenic analytical laboratory report is included in Appendix II.

5.0 DISCUSSION AND RECOMMENDATIONS

The findings and recommendations of ETC's limited hazardous material survey extended only to those areas that were accessible at the time of the site reconnaissance. Any areas that were inaccessible either due to physical restraints (i.e. areas within walls, excessive heights, hidden materials, etc.) are not covered under the scope of this survey and should be evaluated for hazardous materials separately prior to any disturbance.

Based on ETC's visual inspection of the facility and laboratory data, ETC recommends the following:

- Manage and/or remove and dispose of hazardous and regulated materials in accordance with applicable federal, state, and local regulations, prior to renovation and/or demolition activities that may disturb these materials.
- Any material that is suspected to contain a hazardous contaminant but was not tested as part of this survey should be tested prior to disturbance.
- All ACM must be removed and disposed of by a qualified asbestos abatement contractor.
- Handle materials containing glass fibers with appropriate protective equipment to prevent inhalation or ingestion of fibers and contact with skin and mucous membranes.
- Any abatement and demolition contractor(s) must take appropriate measures to comply with applicable EPA, Occupational Safety and Health Administration (OSHA), and Hawaii Occupational Safety and Health (HIOSH) regulations pertaining to the handling of asbestos containing materials and worker protection. Note that OSHA and HIOSH regulate activities that disturb materials containing any detectable concentrations of these contaminants.
- Retain the services of a qualified consultant to monitor and inspect the removal activities to ensure compliance with applicable EPA, OSHA and HIOSH regulations pertaining to the handling of hazardous materials.
- Conduct air monitoring for asbestos fibers by qualified personnel during abatement and general renovation/demolition activities in areas that were determined to contain asbestos.



RESULTS TABLES

Table 1Asbestos Survey ResultsKaipapau Stream Bridge Replacement

Homogeneous Area	Material	Condition	Category	Friability	Analysis Layer	Asbestos Content	Estimated Quantity
Building A (Main	16"x16" White Ceramic		Not	Not		Not	Not
0	Tile with Grout	Good	Applicable		All	Applicable	Applicable
Kitchen, Kesuooni	White Drawall Walls and						
Building A (Main	2	Good	Not	Not	Δ11	Not	Not
Building) Throughout	e	Good	Applicable	Applicable	All	Applicable	Applicable
	*			NT /			
U	e	Good			All		Not Applicable
Building) Throughout	Fallels		Applicable	Applicable		Аррисанс	Applicable
Building A (Main	Carnet Material with		Not	Not		Not	Not
U (Adhesive	Good			All	Applicable	Applicable
			II	II		II ·····	rr ·····
Building A (Main	China las an Das 6 A	Carl	Not	Not	A 11	Not	Not
Building) Roof	Shingles on Roof A	0000	Applicable	Applicable	All	Applicable	Applicable
Building A (Main	Grev Sink Insulation	Good	Not	Not	All	Not	Not
Building) Kitchen			Applicable	Applicable		Applicable	Applicable
Duilding A (Main	Beige Caulking around		Not	Not		Not	Not
U (Bathroom Tub with	Good			All		Applicable
Dunung) Dunioom	Adhesive		Applicable	rippliedole		ripplicable	ripplicable
Building A (Main	Off-White Caulking		Not	Not		Not	Not
Building) Kitchen	around Kitchen Counter	Good	Applicable	Applicable	All	Applicable	Applicable
U,			11			* *	**
Building A (Main	White Caulking around	Good	Not	Not	A 11	Not	Not
Building) Bathroom	Bathroom Sink	0000	Applicable	Applicable	All	Applicable	Applicable
	Building A (Main Building) Living Room, Kitchen, Restroom Building A (Main Building) Throughout Building A (Main Building) Throughout Building A (Main Building) Roof Building A (Main Building) Kitchen Building A (Main Building) Bathroom Building A (Main Building) Kitchen Building A (Main Building) Kitchen	Building A (Main Building) Living Room, Kitchen, Restroom16"x16" White Ceramic Tile with GroutBuilding A (Main Building) ThroughoutWhite Drywall Walls and Ceilings with Joint CompoundBuilding A (Main Building) ThroughoutWhite Fiberboard Ceiling PanelsBuilding A (Main Building) ThroughoutCarpet Material with AdhesiveBuilding A (Main Building) ThroughoutCarpet Material with AdhesiveBuilding A (Main Building) RoofShingles on Roof ABuilding A (Main Building) KitchenGrey Sink InsulationBuilding A (Main Building) BathroomBeige Caulking around Bathroom Tub with AdhesiveBuilding A (Main Building) KitchenOff-White Caulking around Kitchen CounterBuilding A (Main Building) KitchenOff-White Caulking around Bathroom	Building A (Main Building) Living Room, Kitchen, Restroom16"x16" White Ceramic Tile with GroutGoodBuilding A (Main Building) ThroughoutWhite Drywall Walls and Ceilings with Joint CompoundGoodBuilding A (Main Building) ThroughoutWhite Fiberboard Ceiling PanelsGoodBuilding A (Main Building) ThroughoutCarpet Material with AdhesiveGoodBuilding A (Main Building) ThroughoutCarpet Material with AdhesiveGoodBuilding A (Main Building) ThroughoutShingles on Roof AGoodBuilding A (Main Building) RoofGrey Sink InsulationGoodBuilding A (Main Building) KitchenBeige Caulking around Bathroom Tub with AdhesiveGoodBuilding A (Main Building) BathroomOff-White Caulking around Kitchen CounterGood	Building A (Main Building A (Main Building) Living Room, Kitchen, Restroom16"x16" White Ceramic Tile with GroutGoodNot ApplicableBuilding A (Main Building ThroughoutWhite Drywall Walls and Ceilings with Joint CompoundGoodNot ApplicableBuilding A (Main Building A (Main Building ThroughoutWhite Fiberboard Ceiling PanelsGoodNot ApplicableBuilding A (Main Building ThroughoutCarpet Material with AdhesiveGoodNot ApplicableBuilding A (Main Building A (Main Building A (Main Building A (Main Building A (Main Building A (Main Building) RoofShingles on Roof AGoodNot ApplicableBuilding A (Main Building A (Main Building A (Main Building) RoofGrey Sink Insulation Beige Caulking around Bathroom Tub with AdhesiveGoodNot ApplicableBuilding A (Main Building) KitchenOff-White Caulking around Kitchen CounterGoodNot ApplicableBuilding A (Main Building) KitchenOff-White Caulking around Bathroom Tub with AdhesiveGoodNot Applicable	Building A (Main Building A (Ma	Homogeneous AreaMaterialConditionCategoryFriabilityLayerBuilding A (Main Building) Living Room, Kitchen, Restroom16"x16" White Ceramic Tile with GroutGoodNot ApplicableNot ApplicableAllBuilding A (Main Building) ThroughoutWhite Drywall Walls and CompoundGoodNot ApplicableNot ApplicableAllBuilding A (Main Building A (Main Building M (Main Building A (Main Buil	Homogeneous AreaMaterialConditionCategoryFriabilityLayerContentBuilding A (Main Building M (Main Building A (Main Build

Table 2Asbestos Survey ResultsKaipapau Stream Bridge Replacement

Sample ID	Homogeneous Area	Material	Condition	Category	Friability	Analysis Layer	Asbestos Content	Estimated Quantity											
1907-003B-A01		12" 12" Ceramic			Not														
1907-003B-A02	Building B Studio	Floor Tile with	Good	Not Applicable	Not Applicable	All Layers	None Detect	Not Applicable											
1907-003B-A03		Grout			Applicable														
1907-003B-A04		Black Mastic on Pipe			Category II	Black Mastic	Chyrsotile 5%												
1907-003B-A05	Building B Studio	Penetration on	Fair Misc	Fair	Fair	Fair	Fair	Misc	MISC	MISC	wiisc	IVIISC	MISC	MISC	MISC	Non-Friable	Not Analyzed	Not Applicable	2 square ft.
1907-003B-A06		Roof				Not Analyzed	Not Applicable												
1907-003B-A07		White Coulling			Net														
1907-003B-A08	Building B Studio	Building B Studio White Caulking Around Toilet	Good	Not Applicable	Not Applicable	All Layers	None Detect	Not Applicable											
1907-003B-A09		Alound Tonet			Applicable														
1907-003B-A10		Crox Sint			Not														
1907-003B-A11	Building B Studio	Grey Sink Insulation	Good	Not Applicable	Not Applicable	All Layers	None Detect	Not Applicable											
1907-003B-A12		insulation			Applicable														
1907-003B-A13	Building B Studio	Grey Felt on			Not														
1907-003B-A14		Perimeter of	Good	Not Applicable	Not Applicable	All Layers	None Detect	Not Applicable											
1907-003B-A15		Roof			Аррисанс														

Table 2Asbestos Survey ResultsKaipapau Stream Bridge Replacement

Sample ID	Homogeneous Area	Material	Condition	Category	Friability	Analysis Layer	Asbestos Content	Estimated Quantity
1907-003B-A16		Black Felt on			Not			
1907-003B-A17	Building B Studio	Perimeter of	Good	Not Applicable	Applicable	All Layers	None Detect	Not Applicable
1907-003B-A18		Roof			Applicable			
1907-003B-A19	Building B Studio	White Caulking				White Caulking	None Detect	
1907-0051-1119		Building B Studio		Good	Misc	Category II Non-Friable	Black Mastic	4% Chyrsotile
1907-003B-A20		Black Mastic on Roof			Not Analyzed	Not Applicable		
1907-003B-A21		Root				Not Analyzed	Not Applicable	
1907-003B-A22		White Door		Not Applicable	Not Applicable			
1907-003B-A23	Building B Studio	ng B Studio White Door Caulking	Good			All Layers	None Detect	Not Applicable
1907-003B-A24		Caulking						
1907-003B-A25		Drywall Wall			Not			
1907-003B-A26	Building B Studio	and Ceiling w/	Good	Not Applicable	Applicable	All Layers	None Detect	Not Applicable
1907-003B-A27		Joint Compound			Applicable			
1907-003B-A28		Beige Mastic on			Not			
1907-003B-A29	Building B Studio		Good	Not Applicable	Applicable	All Layers	None Detect	Not Applicable
1907-003B-A30		Pole on Roof			ripplicable			

Table 2Asbestos Survey ResultsKaipapau Stream Bridge Replacement

Sample ID	Homogeneous Area	Material	Condition	Category	Friability	Analysis Layer	Asbestos Content	Estimated Quantity
1007 0020 421						Black Roofing	8% Chrysotile	
1907-003B-A31	Building B Studio	0	Good	Misc	Category II Non-Friable	Black/Off- White Roofing	None Detect	150 square ft.
1907-003B-A32		Material				Not Analyzed	Not Applicable	
1907-003B-A33						Not Analyzed	Not Applicable	

Table 3Lead Survey ResultsKaipapau Stream Bridge Replacement

Sample ID	Location	Interior/ Exterior	Color	Substrate	Description	Condition	Reporting Limit (% Pb by weight)	Results (% Pb by weight)
				Drywall	Walls, Ceilings			
1907-L01 Throughout	Throughout	Interior	White	Wood	Door, Door Frame,	Intact	0.010	BRL
				wood	Window, Baseboard			
1907-L02	Garage Port, Exterior of	Exterior	White	Concrete	Walls, Building	Intact	0.010	BRL
1907-L02	Main Building and Studio	Exterior	w mite	Concrete	Foundation	intact	0.010	DKL
	Exterior of Main Building			Wood	Fence, Railings, Steps,			
1907-L03	and Studio	Exterior	Brown	wood	Porch, Window Frame	Intact	0.010	BRL
	and Studio			Metal	Flashing			
	Caraga Port Exterior of			Wood	Walls, Beams, Eeves,			
1907-L04	Garage Port, Exterior of Main Building and Studio	Exterior	Beige	wood	Overhang	Intact	0.013	BRL
	Main Dunung and Studio			Concrete	Support Poles			

Table 4 Arsenic Survey Results Kaipapau Stream Bridge Replacement

Sample ID	Location	Material Description	Condition	Color	Reporting Limit (mg/kg)	Results (mg/kg)
1907-003A-Ars01	Building A Main Building	Fiber Board Ceiling Panel	Good	White	20.0	<20.0

Appendix **II**

LABORATORY ANALYTICAL REPORTS AND CHAIN-OF-CUSTODY FORMS

Laboratory Report 0218703

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

		NVLAP	#101926-0)			
Client:	ENVIROSE	RVICES & TRAINING CENTER	l Job#	ŧ / P.O. #:	19-40	007	
Address:	505 WARD /	AVE, STE 202	Date	Received:	04/17	7/2019	
	HONOLULU	HI 96814	Date	Analyzed:	04/24	4/2019	
Collected:	04/15/2019		Date	Reported:	04/24	4/2019	
Project Name	e: KAIPAPAU	TMK 5-4-18:03 BLDG A	EPA	Method:	EPA	600/R-93/116	
Address:				mitted By: ected By:	JACO	OB VALENCIA	
Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto Detecte	os Asbestos d (%)	Туре	Non-Asbest Constituent	
0218703-001 1907-003A-A01		16x16 Ceramic Tile/ Grout, Beige/ Gray Note: No Ceramic Tile Present	No	None Detected		Cellulose Fiber Quartz Gypsum	<1%
						Mica Carbonates Binder/Filler	99%
0218703-002 1907-003A-A02		16x16 Ceramic Tile/ Grout, Beige/ Gray Note: No Ceramic Tile Present	No	None Detected		Quartz Gypsum Mica Carbonates Binder/Filler	100%
0218703-003 1907-003A-A03		16x16 Ceramic Tile/ Grout, Beige/ Gray Note: No Ceramic Tile Present	No	None Detected		Quartz Gypsum Mica Carbonates Binder/Filler	100%
0218703-004 1907-003A-A04		LAYER 1 Drywall, Off White/ Brown	No	None Detected		Cellulose Fiber Fibrous Glass Gypsum Mica Quartz Carbonatos	10% 2% 88%
		LAYER 2 Texture, White/ Off White	No	None Detected		Carbonates Carbonates Mica Quartz Perlite Binder/Filler	88%

Laboratory Report 0218703

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/24/2019
Collected:	04/15/2019	Date Reported:	04/24/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG A	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	•	Asbesto Detecte	os Asbestos Type d (%)	Non-Asbestos Constituents	
0218703-005 1907-003A-A05		LAYER 1 Drywall, Off White/ Brown	No	None Detected	Cellulose Fiber Fibrous Glass Gypsum Mica Quartz Carbonates	10% 2% 88%
		LAYER 2 Texture, White/ Off White	No	None Detected	Carbonates Quartz Gypsum Perlite Binder/Filler	100%
0218703-006 1907-003A-A06		Drywall/ Texture, Off White/ Brow Note: No Texture Present	n No	None Detected	Cellulose Fiber Fibrous Glass Gypsum Mica Quartz Carbonates	10% 2% 88%
0218703-007 1907-003A-A07		LAYER 1 Fiberboard, White/ Brown	No	None Detected	Cellulose Fiber Carbonates Gypsum Binder/Filler	90% 10%
		LAYER 2 Texture/ Paint, White/ Tan	No	None Detected	Cellulose Fiber Carbonates Mica Quartz Perlite Binder/Filler	1% 99%

Laboratory Report 0218703

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/24/2019
Collected:	04/15/2019	Date Reported:	04/24/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG A	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto Detected	s Asbestos Type I (%)	Non-Asbestos Constituents	
0218703-008		LAYER 1 Fiberboard, White/ Brown	No	None Detected	Cellulose Fiber	90%
1907-003A-A08		hiberboard, white/ brown			Carbonates Gypsum Binder/Filler	10%
		LAYER 2	No	None Detected	Cellulose Fiber	<1%
		Texture/ Paint, White/ Tan			Carbonates Mica Quartz Perlite Binder/Filler	99%
0218703-009 LAYER 1			No	None Detected	Cellulose Fiber	90%
1907-003A-A09	Fiberboard, White/ Brown			Carbonates Gypsum Binder/Filler	10%	
		LAYER 2	No	None Detected	Cellulose Fiber	<1%
		Texture/ Paint, White/ Tan			Carbonates Mica Quartz Perlite Binder/Filler	99%
0218703-010		LAYER 1	No	None Detected	Synthetic Fiber	85%
1907-003A-A10		Carpet, White			Carbonates Binder/Filler	15%
		LAYER 2	No	None Detected	Synthetic Fiber	<1%
		Adhesive, White/ Yellow			Carbonates Quartz Binder/Filler	99%

Laboratory Report 0218703

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/24/2019
Collected:	04/15/2019	Date Reported:	04/24/2019
Project Name	KAIPAPAU TMK 5-4-18:03 BLDG A	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto Detecte	os Asbestos Type d (%)	Non-Asbest Constituent	
0218703-011		LAYER 1	No	None Detected	Synthetic Fiber	85%
1907-003A-A11		Carpet, White			Carbonates Binder/Filler	15%
		LAYER 2 Adhesive, White/ Yellow	No	None Detected	Carbonates Quartz	
					Binder/Filler	100%
0218703-012		LAYER 1	No	None Detected	Synthetic Fiber	85%
1907-003A-A12		Carpet, White			Carbonates Binder/Filler	15%
		LAYER 2 Adhesive, White/ Yellow	No	None Detected		
		Adhesive, while/ tellow			Carbonates Quartz Binder/Filler	100%
0218703-013		LAYER 1	No	None Detected	Fibrous Glass	20%
1907-003A-A13		Shingle, Black			Carbonates Quartz Binder/Filler	80%
		LAYER 2 Shingle, Black/ Red	No	None Detected	Fibrous Glass Cellulose Fiber Carbonates	20% <1%
					Quartz Binder/Filler	79%
		LAYER 3	No	None Detected	Cellulose Fiber	40%
		Felt, Black			Carbonates Gypsum Binder/Filler	60%

Laboratory Report 0218703

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/24/2019
Collected:	04/15/2019	Date Reported:	04/24/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG A	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto: Detected	s Asbestos Type I (%)	Non-Asbesto Constituents	-
0218703-014		LAYER 1 Shingle, Black	No	None Detected	Fibrous Glass	20%
1907-003A-A14		Shingle, Diack			Carbonates Quartz Binder/Filler	80%
		LAYER 2	No	None Detected	Fibrous Glass	20%
		Shingle, Black/ Red			Carbonates Quartz Binder/Filler	80%
		LAYER 3	No	None Detected	Cellulose Fiber	40%
		Felt, Black			Carbonates Gypsum Binder/Filler	60%
0218703-015		LAYER 1	No	None Detected	Fibrous Glass	20%
1907-003A-A15	Shingle, Black			Carbonates Quartz Binder/Filler	80%	
		LAYER 2 Shingle, Black/ Red	No N	None Detected	Fibrous Glass	20%
					Carbonates Quartz Binder/Filler	80%
		LAYER 3	No	None Detected	Cellulose Fiber	40%
		Felt, Black			Carbonates Gypsum Binder/Filler	60%
0218703-016		Sink Insulation, Gray	No	None Detected		
1907-003A-A16			-		Carbonates Mica Quartz Binder/Filler	100%

Laboratory Report 0218703

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/24/2019
Collected:	04/15/2019	Date Reported:	04/24/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG A	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbestos Detected	s Asbestos Type I (%)	Non-Asbestos Constituents	
0218703-017 1907-003A-A17		Sink Insulation, Gray	No	None Detected	Carbonates Mica Quartz Binder/Filler	100%
0218703-018 1907-003A-A18		Sink Insulation, Gray	No	None Detected	Cellulose Fiber Carbonates Mica Quartz Binder/Filler	<1% 99%
0218703-019 1907-003A-A19		Caulking, Beige/ Off White	No	None Detected	Carbonates Quartz Binder/Filler	100%
0218703-020 1907-003A-A20		Caulking, Beige/ Off White	No	None Detected	Carbonates Quartz Binder/Filler	100%
0218703-021 1907-003A-A21		Caulking, Beige/ Off White	No	None Detected	Carbonates Quartz Binder/Filler	100%
0218703-022 1907-003A-A22		Caulking, Off White	No	None Detected	Cellulose Fiber Carbonates Quartz Binder/Filler	<1% 99%

Laboratory Report 0218703

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

NVLAP#101926-0

Client: Address:	ENVIROSERVICES & TRAINING CENTER 505 WARD AVE, STE 202 HONOLULU HI 96814	Job# / P.O. #: Date Received: Date Analyzed:	19-4007 04/17/2019 04/24/2019
Collected:	04/15/2019	Date Reported:	04/24/2019
Project Name:	KAIPAPAU TMK 5-4-18:03 BLDG A	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbeste Detecte	os Asbestos Type ed (%)	Non-Asbeste Constituent	
0218703-023		Caulking, Off White	No	None Detected	Cellulose Fiber	<1%
1907-003A-A23					Carbonates Quartz Binder/Filler	99%
0218703-024		Caulking, Off White	No	None Detected		
1907-003A-A24					Carbonates Quartz Binder/Filler	100%
0218703-025		Caulking, White	No	None Detected		
1907-003A-A25					Carbonates Quartz Binder/Filler	100%
0218703-026		Caulking, White	No	None Detected		
1907-003A-A26					Carbonates Quartz Binder/Filler	100%
0218703-027		Caulking, White	No	None Detected		
1907-003A-A27					Carbonates Quartz Binder/Filler	100%

Analyst - Kurt Kettler

Signatory - Lab Manager - Ken Scheske

Distinctly stratified, easily separable layers of samples are analyzed as subsamples of the whole and are reported separately for each discernible layer. All analyses are derived from calibrated visual estimate and measured in area percent unless otherwise noted. The report applies to the standards or procedures identified and to the sample(s) tested. The test results are not necessarily indicated or representative of the qualities of the lot from which the sample was taken or of apparently identical or similar products, nor do they represent an ongoing quality assurance program unless so noted. These reports are for the exclusive use of the addressed client and that they will not be reproduced wholly or in part for adversing or other purposes over our signature or in connection with our name without special written perports shall not be reproduced except in full, without written approval by our laboratory. The samples not destroyed in testing are retained a maximum of thirty days. The laboratory measurement of uncertainty for the test method is approximately less than 1 by area percent. Accredited by the National Institute of Standards and Technology, Voluntary Laboratory Accreditation Program for sabetced test method for asbestos. The accreditation ray reports generated by the National Institute of Standards and Technology. In endorsement by the National Institute of Standards and Technology. No unlary Laboratory Accreditation Program for selected test method for used by use used by the outsel to testint to reproduce extension, approval, or endorsement by the National Institute of Standards and Technology. The reports man to estimate and the sample of the standards and Technology. No unlary Laboratory Accreditation Program for selected test method to used by the used by the Distonated trainton, approval, or endorsement by the National Institute of Standards and Technology. The report must not be used by the used by the outsel to leint to claim product certification, approval, or endorsement by the National In

Page	of)	CHAIN OF CUSTODY LAB#: 218703 EMC Labs, Inc. 9830 S. 51st St., Ste B-109 Phoenix, AZ 85044 TAT: 35 Jay (800) 362-3373 Fax (480) 893-1726						
COMPANY NA		5 & TRAINI	NG CENTER, LLC BILL TO: (If Different Location)					
	505 Ward Ave. Suit	te #202	Trina Oshiro					
·	Honolulu, HI 96814	Ionolulu, HI 96814						
CONTACT:		Daniel Woo, Jawb Valuncia, Vel Roberts						
Phone/Fax:		808) 839-7222 ext 225 / (619) 495-6559						
Email:		dwoo@gotoetc.com, jvalencia @gotoetc.com						
Now Acce			Price Quoted: \$ / Sample \$ / Layers any items may cause a delay in processing or analyzing your san					
**** <u>Prior</u> cor ****Addition ****Laborate 2. TYPE (nfirmation of turnaround time is <u>re</u> al charges for rush analysis (please ory analysis may be subject to dela OF ANALYSIS: SAL INSTRUCTIONS:	e call marketin y if credit tern PLM [Air [Dispose of	g department for pricing details)	ape]				
4. Project	Name: Kaipapaw TM	K 5-4-1	8:103 6/dg. A Project Number: 19-4007					
EMC SAMPLE #	CLIENT SAMPLE #	DATE & TIME SAMPLED	LOCATION/MATERIAL TYPE	Samples Accepted Yes / No				
1,2,3	1907-003A-A01-A03	4/15/19	16"x16" coramic tile w/growt; LIV/KIt/Restricon	Ø N				
4.56	1907-003A-A04-A06	1	Drugwall walls and ceiling w/ joint compound	y N				
7,8,9	1907 - 003A - A67 - A09		Fiberboard ceiling panels	Y N				
10,11,12	1907-003A. Ald-A12		(arpet materia) w/ adhesive	Y N				
	1907-003/7-A13-HIS			Y N				
	1907-003A-A16-A18		Gray sink insulation in Kitchen	Y N				
,	1907-013A - A19-A21		Beige caulting around bothroom the w/adhesitie	Y N				
	1907-003A-A22-224		Off-while caulking around kitchen counter	Y N				
	1907-003A - A25-A27	<u> </u>	white caulcing around bathroom sink	Ø N				
<u>, , , , , , , , , , , , , , , , , , , </u>				Y N				
				Y N				
				Y N				
Sample Co Relinquish	NSTRUCTIONS: Stop at Allector: (Print) Jacob Value ed by D.Woo Date/Time44	115/19 F	Received by: Drana Federico Date/Time:	119 950				
			et //17/19 315 Received by: //// Date/Time: 2	1 nf 19 55				
Relinquish	-	_ Date/Time						
			es for these services or otherwise, parties agree that jurisdiction and ven I to attorney's fees and court costs.	ue will be				

.

.

.

Rev.	09/27/08
------	----------

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

NVLAP#101926-0					
Client:	ENVIROSER	VICES & TRAINING CENTER	R Job# / P.O. #:	19-4007	
Address:	505 WARD A	VE, STE 202	Date Received:	04/17/2019	
	HONOLULU	HI 96814	Date Analyzed:	04/22/2019	
Collected:	04/15/2019		Date Reported:	04/22/2019	
Project Nam	e: KAIPAPAU T	MK 5-4-18:03 BLDG B	EPA Method:	EPA 600/R-93/116	
Address:			Submitted By:	JACOB VALENCIA	
			Collected By:		
Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbestos Asbestos Detected (%)	<i></i>	

0218704-001 1907-003B-A01	LAYER 1 Ceramic Floor Tile, White/ Red	No	None Detected	Quartz Gypsum Binder/Filler	100%
	LAYER 2 Grout, Beige/ Gray	No	None Detected	Quartz Gypsum Mica Carbonates Binder/Filler	100%
0218704-002 1907-003B-A02	LAYER 1 Ceramic Floor Tile, White/ Red	No	None Detected	Quartz Gypsum Binder/Filler	100%
	LAYER 2 Grout, Beige/ Gray	No	None Detected	Cellulose Fiber Quartz Gypsum Mica Carbonates Binder/Filler	<1% 99%
0218704-003 1907-003B-A03	LAYER 1 Ceramic Floor Tile, White/ Red	No	None Detected	Quartz Gypsum Binder/Filler	100%
	LAYER 2 Grout, Beige/ Gray	No	None Detected	Cellulose Fiber Quartz Gypsum Binder/Filler	<1% 99%
0218704-004 1907-003B-A04	Mastic, Black	Yes	Chrysotile 5%	Fibrous Glass Gypsum Carbonates Quartz Binder/Filler	3% 92%

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/22/2019
Collected:	04/15/2019	Date Reported:	04/22/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG B	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

	Conected by.							
Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto Detecte	s Asbestos Type d (%)	Non-Asbestos Constituents			
0218704-005 1907-003B-A05	i	Mastic, Black Note: *Not analyzed per client request						
0218704-006 1907-003B-A06	1	Mastic, Black Note: *Not analyzed per client request						
0218704-007 1907-003B-A07		Caulking, White/ Off White	No	None Detected	Silicone	100%		
0218704-008 1907-003B-A08	1	Caulking, White/ Off White	No	None Detected	Silicone	100%		
0218704-009 1907-003B-A09	•	Caulking, White/ Off White	No	None Detected	Silicone	100%		
0218704-010 1907-003B-A10		Sink Insulation, Gray	No	None Detected	Cellulose Fiber Carbonates Mica Quartz Binder/Filler	<1% 99%		
0218704-011 1907-003B-A11		Sink Insulation, Gray	No	None Detected	Cellulose Fiber Carbonates Mica Quartz Binder/Filler	<1% 99%		
0218704-012 1907-003B-A12		Sink Insulation, Gray	No	None Detected	Carbonates Mica Quartz Binder/Filler	100%		

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

NVLAP#101926-0

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/22/2019
Collected:	04/15/2019	Date Reported:	04/22/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG B	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto Detecte	os Asbestos Type d (%)	Non-Asbestos Constituents	
0218704-013		Felt, Gray	No	None Detected	Fibrous Glass	1%
1907-003B-A13					Carbonates Quartz Gypsum Binder/Filler	99%
0218704-014 1907-003B-A14		Felt, Gray	No	None Detected	Fibrous Glass Cellulose Fiber Carbonates Quartz	1% <1%
					Gypsum Binder/Filler	98%
0218704-015 1907-003B-A15		Felt, Gray	No	None Detected	Fibrous Glass Cellulose Fiber Carbonates Quartz	1% <1%
					Gypsum Binder/Filler	98%
0218704-016 1907-003B-A16		LAYER 1 Felt, Black	No	None Detected	Fibrous Glass Carbonates	20%
					Quartz Binder/Filler	80%
		LAYER 2 Coating, White/ Black	No	None Detected	Cellulose Fiber	<1%
		,			Carbonates Quartz Binder/Filler	99%

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/22/2019
Collected:	04/15/2019	Date Reported:	04/22/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG B	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto Detecte	s Asbestos d (%)	Туре	Non-Asbest Constituent	
0218704-017		LAYER 1	No	None Detected		Fibrous Glass	20%
1907-003B-A17		Felt, Black				Carbonates Quartz Binder/Filler	80%
		LAYER 2	No	None Detected		Fibrous Glass	20%
		Felt, Black				Carbonates Quartz Binder/Filler	80%
		LAYER 3	No	None Detected		Cellulose Fiber	<1%
		Coating, White/ Black				Quartz Carbonates Gypsum Mica Binder/Filler	99%
0218704-018		LAYER 1	No	None Detected		Fibrous Glass	20%
1907-003B-A18		Felt, Black				Carbonates Quartz Binder/Filler	80%
		LAYER 2	No	None Detected		Fibrous Glass	20%
		Felt, Black				Carbonates Quartz Binder/Filler	80%
		LAYER 3 Coating, White/ Black	No	None Detected		Carbonates Quartz Binder/Filler	100%
0218704-019		LAYER 1	No	None Detected		Cellulose Fiber	<1%
1907-003B-A19		Caulking, White/ Off White				Carbonates Quartz Binder/Filler	99%
		LAYER 2	Yes	Chrysotile	4%	Cellulose Fiber	1%
		Mastic, Black				Carbonates Quartz	
						Binder/Filler	95%

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

NVLAP#101926-0 Client: **ENVIROSERVICES & TRAINING CENTER** Job# / P.O. #: 19-4007 Address: 505 WARD AVE, STE 202 Date Received: 04/17/2019 HONOLULU HI 96814 Date Analyzed: 04/22/2019 Collected: 04/15/2019 Date Reported: 04/22/2019 Project Name: KAIPAPAU TMK 5-4-18:03 BLDG B **EPA Method:** EPA 600/R-93/116 Submitted By: JACOB VALENCIA Address: Collected By: Lab ID Sample Layer Name / Asbestos Asbestos Type Non-Asbestos Location Sample Description Constituents Detected Client ID (%) LAYER 1 0218704-020 Caulking, White/ Off White 1907-003B-A20 Note: *Not analyzed per client request LAYER 2 Mastic, Black Note: *Not analyzed per client request 0218704-021 LAYER 1 Caulking, White/ Off White 1907-003B-A21 Note: *Not analyzed per client request LAYER 2 Mastic, Black Note: *Not analyzed per client request 0218704-022 Door Caulking, White/ Off White None Detected Cellulose Fiber <1% No 1907-003B-A22 Carbonates Quartz Binder/Filler 99% 0218704-023 Door Caulking, White/ Off White No None Detected Cellulose Fiber <1% 1907-003B-A23 Carbonates Quartz Binder/Filler 99% 0218704-024 Door Caulking, White/ Off White None Detected No 1907-003B-A24 Carbonates Quartz **Binder/Filler** 100%

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/22/2019
Collected:	04/15/2019	Date Reported:	04/22/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG B	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbesto Detecte	s Asbestos Type d (%)	Non-Asbest Constituent	
0218704-025		LAYER 1	No	None Detected	Cellulose Fiber	12%
1907-003B-A25		Drywall, Off White/ Brown			Gypsum Mica Quartz Carbonates	88%
		LAYER 2	No	None Detected	Cellulose Fiber	1%
		Texture, White/ Off White			Carbonates Quartz Perlite Binder/Filler	99%
0218704-026		LAYER 1	No	None Detected	Cellulose Fiber	12%
0218704-026 1907-003B-A26		Drywall, Off White/ Brown			Gypsum Mica Quartz	
		LAYER 2 Texture, White/ Off White	No	None Detected	Carbonates Mica Quartz Perlite Binder/Filler	88%
0218704-027 1907-003B-A27		LAYER 1 Drywall, Off White/ Brown	No	None Detected	Cellulose Fiber Gypsum Mica Quartz Carbonates	12% 88%
		LAYER 2	No	None Detected	Cellulose Fiber	1%
		Texture, White/ Off White			Carbonates Quartz Perlite Binder/Filler	99%

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

NVLAP#101926-0

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/22/2019
Collected:	04/15/2019	Date Reported:	04/22/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG B	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

	Conceica Dy.						
Lab ID Client ID	Sample Location	•	Asbesto Detecte	s Asbestos Type d (%)	Non-Asbesto Constituent		
0218704-028 1907-003B-A28		Mastic/ Caulking, Beige/ Off White	e No	None Detected	Quartz Gypsum Binder/Filler	100%	
0218704-029 1907-003B-A29		Mastic/ Caulking, Beige/ Off White	e No	None Detected	Quartz Gypsum Binder/Filler	100%	
0218704-030 1907-003B-A30		Mastic/ Caulking, Beige/ Off White	e No	None Detected	Cellulose Fiber Quartz Gypsum Binder/Filler	<1% 99%	
0218704-031 1907-003B-A31		LAYER 1 Coating, White/ Gray	No	None Detected	Carbonates Quartz Binder/Filler	100%	
		LAYER 2 Roofing, Black/ Off White	No	None Detected	Synthetic Fiber Fibrous Glass Carbonates Quartz Binder/Filler	15% 5% 80%	
		LAYER 3 Roofing, Black	No	None Detected	Cellulose Fiber Carbonates Gypsum Quartz	20%	

No

None Detected

LAYER 4

Roofing, Black

80%

20%

80%

Binder/Filler

Carbonates Quartz Binder/Filler

Fibrous Glass

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

		NVLAP	#101926-0				
Client: Address:	HONOLULU HI 96814			P.O. #: Received: analyzed:	19-400 04/17/2 04/22/2	2019	
Collected:	04/15/2019		Date F	Reported:	04/22/2	2019	
Project Name	e: KAIPAPAU T	MK 5-4-18:03 BLDG B	EPA N	lethod:	EPA 60)0/R-93/116	
Address:				tted By: ted By:	JACOE	3 VALENCIA	
Lab ID Client ID	Sample Location	Layer Name / Sample Description	Asbestos Detected	Asbestos T (%)	уре	Non-Asbestos Constituents	
0218704-032 1907-003B-A32	ADDITIONAL LAYERS	LAYER 1 Coating, White/ Gray Note: *Not analyzed per client request					
		LAYER 2 Roofing, Black/ Off White Note: *Not analyzed per client request					
		LAYER 3 Roofing, Black Note: *Not analyzed per client request					
		LAYER 4 Roofing, Black Note: *Not analyzed per client request					
0218704-033 1907-003B-A33		LAYER 1 Coating, White/ Gray Note: *Not analyzed per client request					
		LAYER 2 Roofing, Black/ Off White Note: *Not analyzed per client request					
		LAYER 3 Roofing, Black Note: *Not analyzed per client request					
		LAYER 4 Roofing, Black Note: *Not analyzed per client request					

Laboratory Report 0218704

9830 S. 51st Street, Suite B109, Phoenix, AZ 85044 Phone: 800-362-3373 or 480-940-5294 - Fax: (480) 893-1726

Bulk Asbestos Analysis by Polarized Light Microscopy

NVLAP#101926-0

Client:	ENVIROSERVICES & TRAINING CENTER	Job# / P.O. #:	19-4007
Address:	505 WARD AVE, STE 202	Date Received:	04/17/2019
	HONOLULU HI 96814	Date Analyzed:	04/22/2019
Collected:	04/15/2019	Date Reported:	04/22/2019
Project Name	: KAIPAPAU TMK 5-4-18:03 BLDG B	EPA Method:	EPA 600/R-93/116
Address:		Submitted By:	JACOB VALENCIA
		Collected By:	

Lab ID	Sample	Layer Name /	Asbestos	Asbestos Type	Non-Asbestos
Client ID	Location	Sample Description	Detected	(%)	Constituents

Yes

0218704-034 1907-003B-A31 LAYER 1 Roofing, Black

LAYER 2 Roofing, Black/ Off White

		Quartz Binde
No	None Detected	Fibrou
		Carbo Quartz

Chrysotile

8%

Gypsum Carbonates tz er/Filler 92% us Glass 20% onates tz **Binder/Filler** 80%

lam O. the

Analyst - James A. Storm

fint feart

Signatory - Lab Director - Kurt Kettler

Distinctly stratified, easily separable layers of samples are analyzed as subsamples of the whole and are reported separately for each discernible layer. All analyses are derived from calibrated visual estimate and measured in area percent unless othewise noted. The report applies to the standards or procedures identified and to the sample(s) tested. The test results are not necessarily indicated or representative of the qualities of the lot from which the sample was taken or of apparently identical or similar products, nor do they represent an ongoing quality assurance program unless so noted. These reports are for the exclusive use of the addressed client and that they will not be reproduced wholly or in part for advertising or other purposes over our signature or in connection with our name without special written permission. The report shall not be reproduced werely or in part for advertising or other advertes are more of a signature or in connection with our name without special written permission. The report shall not be reproduced werely or in test developed in testing are retained a maximum of thirty days. The laboratory measurement of uncertainty for the test method is approximately less than 1 by area percent. Accredited by the National Institute of Standards and Technology, Voluntary Laboratory Accreditation Program for selected test method for asbestos. The accreditation or any reports generated by this laboratory in no way constitutes or implies product certification, approval, or endorsement by the National Institute of Standards and Technology. The report must not be used by the client to claim product certification, approval, or endorsement by the National Institute of Standards and Technology. The report must not be used by the client to claim product certification, approval, or endorsement by the National Institute of Standards and Technology. The report must not be used by the client to claim product certification, approval, or endorsement the National Institute of Standards and Technology. T

Page	of		HAIN OF CUSTODY EMC Labs, Inc. 9830 S. 51 st St., Ste B-109 Phoenix, AZ 85044	LAB#: 7(8704 ТАТ: 3 Дагр	
			362-3373 Fax (480) 893-1726	Rec'd: APR 17 P.M.	
COMPANY NA		-	NG CENTER, LLC BILL TO:	(If Different Location)	
	505 Ward Ave. Sui		Trina Oshi	ro	
	Honolulu, HI 96814	ł			
CONTACT:	Daniel Woo (808) 839-7222 ext	225 / (610)	495 6559	·····	
Phone/Fax:	dwoo@gotoetc.cor		495-6559		
Now Acce			Price Quoted: \$	/ Sample \$ / Layer	
			any items may cause a delay in pro	-	
**** <u>Prior</u> con ****Addition ****Laborate 2. TYPE	nfirmation of turnaround time is <u>re</u> nal charges for rush analysis (pleas ory analysis may be subject to dele OF ANALYSIS: SAL INSTRUCTIONS:	e call marketin av if credit term PLM] [Air (Dispose o	g department for pricing details) is are not met	ungi: AOC, W-C, Bulk, Swab, es to me at <u>my expense]</u>	Tape]
4. Project	Name: Kaipapau Ti	MK 5-4-	18 bldg B Proje	ct Number: 19 - 400 7	
EMC SAMPLE #	CLIENT SAMPLE #	DATE & TIME SAMPLED	LOCATION/MA TYPE	ATERIAL	Samples Accepted Yes / No
1,2,3	1907-003B-A01-A03	4/15/19	12" x12" coramic Floor tile	with grout	Q N
4,5,6	1907-003B-A04-A06	,	Black mastic on pipe penetrati	ion on roof	Ϋ́N
7,8,9	1907-0038-407-409		white caulking around tail	let	N
10,11,12	1907-003B-A10-A12		Grey shk insulation		Y N
13,14,15	1907-003B-A13-A15		Grey felt on perimeter . Black felt on perimeter o	of reaf	Y N
16, 1718	1907-003B-A16-A18		Black felt on perimeter o	front	N
19,20,21	1907-003B-A19-A21		White caulking on pipe pone	Artian with black mestic and	Y N
22,23,24	1907-003B-A22-A24		door caulking white		Y N
25,26,27	1907-003B-AZS-AZ7		Drywall wall and ceiling J	oint compound	N N
28,29,30	1907-003B - A28 - A30		Biege mastic on electric cabl		N
31,32,33	1907-0638-431-433	\checkmark	Rolled on roofing on reat	2	N N
					Y N
	NSTRUCTIONS: Stop of		positive		
Sample Co	Illector: (Print) Daniel W/	Jacob V	(Signature)_ <i>Bulli</i>	Wee 1	1
Relinquish	ed by <u>D.Woo</u> Date/Time_ ^C	1/15/19 R	eceived by: Dian Federico	Date/Time://۱	119 950
	ed by: Diana Federico		: 4/12/19 3: 5 Received by:	Date/Time:_(11 719 535
Relinquish			Received by:	Date/Time:	
			s for these services or otherwise, parti		ue will be

È

** In the event of any dispute between the above parties for these services or otherwise, parties agree that jurisdiction and venue will in Phoenix, Arizona and prevailing party will be entitled to attorney's fees and court costs. Rev. 09/27/08



9830 South 51st Street, Suite B-109 / PHOENIX, ARIZONA 85044 / 480-940-5294 or 800-362-3373 / FAX 480-893-1726 emclab@emclabs.com

LEAD (Pb) IN PAINT CHIP SAMPLES EMC SOP METHOD #L01/1 EPA SW-846 METHOD 7420

EMC LAB	#:	L74587		DATE RECEIVE	ED:	04/17/19
CLIENT:		Enviroservices & 7	raining Center, LLC	REPORT DATE	:	04/22/19
				DATE OF ANAL	AYSIS:	04/19/19
		505 Ward Ave. Sui Honolulu, HI 9681		P.O. NO.:		
PROJECT NAME:		Kaipapau Building Replacement	gs – Kaipopou Stream Bridge PROJECT N		: 19-4007	
EMC # L74587-	SAMPLE DATE /19	CLIENT SAMPLE #	DESCRIPTION		REPORTING LIMIT (%Pb by weight)	%Pb BY WEIGHT
1	04/15	1907-L01	Interior – White – On Drywall – Ceiling/ Walls-/ Wood Door and Door Frames/ Window Frames/ Baseboard		0.010	BRL
2	04/15	1907-L02	Exterior – White on Concrete Wall and Building Foundation		0.010	BRL
3	04/15	1907-L03	Exterior – Brown – Wood Fence, Railings Steps, Porch/ Window Frames and Roof Metal		0.010	BRL
4	04/15	1907-L04	Exterior – Beige – Wood, Walls, Be Overhang – Concrete Support Poles	ams, Eaves,	0.010	BRL

A = Dilution Factor Changed * = Excessive Substrate May Bias Sample Results BRL = Below Reportable Limits # = Very Small Amount Of Sample Submitted, May Affect Result

This report applies to the standards or procedures identified and to the samples tested only. The test results are not necessarily indicative or representative of the qualities of the lot from which the sample was taken or of apparently identical or similar products, nor do they represent an ongoing quality assurance program unless so noted. Unless otherwise noted, all quality control analyses for the samples noted above were within acceptable limits.

Where it is noted that a sample with excessive substrate was submitted for laboratory analysis, such analysis may be biased. The lead content of such sample may, in actuality, be greater than reported. EMC makes no warranty, express or implied, as to the accuracy of the analysis of samples noted to have been submitted with excessive substrate. Resampling is recommended in such situations to verify original laboratory results.

These reports are for the exclusive use of the addressed client and are rendered upon the condition that they will not be reproduced wholly or in part for advertising or other purposes over our signature or in connection with our name without special written permission. Samples not destroyed in testing are retained a maximum of sixty (60) days.

ANALYST:

Jason Thompson

QA COORDINATOR:

Kurt Kettler

Page	of		HAIN OF CUSTODY EMC Labs, Inc. 9830 S. 51 st St., Ste B-109 Phoenix, AZ 85044 362-3373 Fax (480) 893-1726	LAB#: X74587 TAT: 3day Rec'd:4/17/19	
COMPANY NA		S & TRAINI	NG CENTER, LLC BILL TO:	(If Different Location)	_
	505 Ward Ave. Su		Trina Osh		
	Honolulu, HI 9681	4			
CONTACT:	Daniel Woo				
Phone/Fax:	(808) 839-7222 ex	· · · · ·	495-6559	,,,,,	
Email:	dwoo@gotoetc.co		······································		<u>-</u>
Now Acce			Price Quoted: \$ any items may cause a delay in pr		
**** <u>Prior</u> cor ****Addition ****Laborate 2. TYPE (nfirmation of turnaround time is <u>r</u> al charges for rush analysis (plea ory analysis may be subject to del OF ANALYSIS: [Bulk SAL INSTRUCTIONS:	se call marketin ay if credit term -PLM] [Air [Dispose d	ng department for pricing details) ns are not met -PCM] [Lead] [Point Count] [I of samples at EMC] / [Return samp pence, EMC will dispose of samples <u>60 c</u>	Fungi: AOC, W-C, Bulk, Swab, les to me at <u>my expense</u>]	Tape]
4. Project	Name: Kaipapan B	ouildings	Kaipopour Stream Bridge Leplacement Proje	ect Number: 19-4007	
EMC SAMPLE #	CLIENT SAMPLE #	DATE & TIME SAMPLED	LOCATION/M. TYPE		Samples Accepted Yes / No
	1907-201	04/15/19	Interior - White - on Drywall-C	eilines Walls - Word Door	Y N
			al Door Frances / Dear Window F		Y N
	1907-202	04/15/19	Exterior - White m concrete	Wall and Building Foundation	✓ Y N
	1907-263	04/15/19	Exterior - Brown-Wood Fince, K	slings Stens Dorch	Y N
	1907-104/12-		Window France and Roof M	Tetal Elashing	Y N
	1907-204	oulistig	Extrior - Beige - Dood, wills, Been	-s, eaves prevary	Y N
			- Coverate Supp	ont places Poles	Y N
			· · · · · · · · · · · · · · · · · · ·		Y N
					Y N
					Y N
					Y N
					Y N
Sample Co	ISTRUCTIONS:	m3	(Signature)	Á	
	ed by <u>D.Woo</u> Date/Time <u>4</u>		eceived by:	Date/Time:	1,950
Relinquish	15	Date/Time	11/10/10/0	Date/Time:	1 7/19
	ent of any dispute between th		e <u>9779779</u> Received by: es for these services or otherwise, part to attorney's fees and court costs.	by agree that jurisdiction and ver	

-

April 18, 2019



Vel Roberts EnviroServices & Training Center, LLC 505 Ward Avenue, Suite 202 Honolulu, HI 96814

RE: Metals Analysis; NVL Batch # 1907712.00

Dear Ms. Roberts,

Enclosed please find the test results for samples submitted to our laboratory for analysis. Preparation of these samples was conducted following protocol outlined in EPA Method SW 846 -3051 unless stated otherwise. Analysis of these samples was performed using analytical instruments in accordance with U.S. EPA, NIOSH, OSHA and other ASTM methods.

For matrix materials submitted as paint, dust wipe, soil or TCLP samples, analysis for the presence of total metals is conducted using published U.S. EPA Methods. Paint and soil results are usually expressed in mg/Kg which is equivalent to parts per million (ppm). Lead (Pb) in paint is usually expressed in mg/Kg (ppm), Percent (%) or mg/cm² by area. Dust wipe sample results are usually expressed in ug/wipe and ug/ft². TCLP samples are reported in mg/L (ppm). For air filter samples, analyses are conducted using NIOSH and OSHA Methods. Results are expressed in ug/filter and ug/m³. Other matrix materials are analyzed accordingly using published methods or specified by client. The reported test results pertain only to items tested and are not blank corrected.

For recent regulation updates pertaining to current regulatory levels or permissible exposure levels, please call your local regulatory agencies for more details.

This report is considered highly confidential and will not be released without your approval. Samples are archived for two weeks following analysis. Samples that are not retrieved by the client are discarded after two weeks.

Thank you for using our laboratory services. if you need further assistance please feel free to call us at 206-547-0100 or 1-888-NVLLABS.

Jasmi Him

Yasuyuki Hida, Laboratory Analyst

Enc.: Sample results



Phone: 206 547.0100 | Fax: 206 634.1936 | Toll Free: 1.888.NVL.LABS (685.5227) 4708 Aurora Avenue North | Seattle, WA 98103-6516

Analysis Report



Total Metals

Client: EnviroServices & Training Center, LLC Address: 505 Ward Avenue, Suite 202

Honolulu, HI 96814

Attention: Ms. Vel Roberts

Project Location: 54-260 Kamehameha Hwy

Batch #: 1907712.00 Matrix: Bulk Method: EPA 3051/6010C Client Project #: 19-4007 Kaipapau TMK 5-4-18 Date Received: 4/17/2019 Samples Received: 1 Samples Analyzed: 1

Lab ID	Client Sample #	Elements	Sample wt (g)	RL mg / kg	Results in mg / kg	Results in ppm	
19039792	1907-003A-Ars01	Arsenic (As)	0.1997	20.0	< 20.0	< 20.0	

Sampled by:	Client			Jasmi Him
· · ·	Shalini Patel	Date Anal	yzed: 04/18/2019	
Reviewed by:	Yasuyuki Hida	Date Iss	sued: 04/18/2019	Yasuyuki Hida, Laboratory Analyst
mg/ kg = Milligrar	ms per kilogram			RL = Reporting Limit
ppm = Parts per	⁻ million			'<' = Below the reporting Limit
Note : Method Q	C results are accep	able unless sta	ted otherwise.	
Unless ot	herwise indicated, th	e condition of a	III samples was accep	table at time of receipt.
ICP-M2	Bench Run No: 20	19-0418-01	$n_{2}a_{2} 2 of 4$	

METAL LABORATORY SERVICES



Rush Samples _____

Company EnviroServices & Training Center, LLC	NVL Batch Number 1907712.00
Address 505 Ward Avenue, Suite 202	TAT 5 Days AH No
Honolulu, HI 96814	Rush TAT
Project Manager Ms. Vel Roberts	Due Date 4/24/2019 Time 9:35 AM
Phone (808) 839-7222	Email vel@gotoetc.com
Cell (808) 384-9590	Fax (808) 839-4455

Project Nan	ne/Number: 19-400 TMK 5	7 Kaipapau -4-18 Project Location: 54-260 Kamehameha Hwy
Subcategory	Inductively Couple	d Plasma (ICP) - Group Tests
Item Code	ICP-M2	EPA 6010 (price per analyte) <paint></paint>
Metals	Arsenic (As)	

Total Number of Samples ____1

	Lab ID	Sample ID	Description	A/R
1	19039792	1907-003A-Ars01		Α

	Print Name	Signature	Company	Date	Time
Sampled by	Client				
Relinquished by	Federal Express				
Office Use Only	Print Name	Signature	Company	Date	Time
Received by	Emily Schubert		NVL	4/17/19	935
Analyzed by	Shalini Patel		NVL	4/18/19	
Results Called by					
Faxed Emailed					
Special Instructions:					

Date: 4/17/2019 Time: 12:43 PM Entered By: Kelly AuVu

1907712



METALS CHAIN OF CUSTODY

Turn Around Time		
⊒ 2 Hour	🗅 4 Hours	🖵 24 Hours
🔟 2 Days	□ 3 Days	🔄 4 Days
🖌 5 Days	🖵 6-10 Days	
Please call for T	AT less than 24 Hou	Jrs

Company	EnviroServices & Train	.C Project Manager	Project Manager Vel Roberts			
Address	505 Ward Avenue, S	Cell	(808)	398 - 2174		
	Honolulu, Hawaii 90	Email	-			
Phone	(808) 839-7222		Fax	()		_
Project Name/N	umber 19-4007 Kaipapau TMK 5-4-18	Project Location	54-260 Kame	ehame	ha Hwy	

L Call ()	° a	Fax ()	08	고 Ema	, vel@go	ptoetc.c	om
Reporting In	nstructions							
ļ	ြ CVAA (ppb)	외 Other			🗆 Selenīum	⊒ Cadmium		□ Other
	🖵 GFAA (ppb)	Drinking Water	🗅 Waste Water		괴 Arsenic	□ Mercury	Lead	⊒ Zinc
I TCLP	입 ICP (PPM	🗆 Paint Chips (cm)	❑ Dust Wipes		🗀 Banum	L Chromium	🕒 Silver	⊒ Coppei
Total Metals	🖵 FAA (ppm	💷 Air Filter	l Paint Chips (%)	🔲 Soil	RCRA 8			RCRA 11

Total Number of Samples 1

	Sample ID	Description	A/R
1	1907-003A-Ars01	Fiber board ceiling panel	
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			

1	Print Name	Signature	Company	Date	Time
Sampled by	Daniel Woo	Danill Wae	ETC	4/15/19	
Relinquish by	Velverdee Roberts	1.1.1	ETC	4/15/19	
Office Use O Received Analyzed Called Faxed/Email	by Print Name by by by	signature	Company	U 17/9	Time 935 Peder

4708 Aurora Ave N, Seattle, WA 98103 | p 206.547.0100 | f 206.634.1936 | www.nvllabs.com




PHOTO DOCUMENTATION



1907-003B-A04: Black Mastic on Pipe Penetration Building B Studio Roof



1907-003B-A19: White Caulking on Pipe Penetration with Black Mastic Building B Studio Roof



Page 1 of 2 April 2019 **Photographic Documentation** Asbestos Containing Materials Kaipapau Stream Bridge Replacement



1907-003B-A31: Rolled on Roofing Building B Studio Roof



Page 2 of 2

Photographic Documentation Asbestos Containing Materials Kaipapau Stream Bridge Replacement