


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	62	161

INDEX OF BRIDGE DRAWINGS	
<u>SHEET NO.</u>	<u>DESCRIPTION</u>
S0.1	INDEX OF BRIDGE DRAWINGS
S0.2	INDEX OF BRIDGE DRAWINGS
S0.3	SYMBOLS AND ABBREVIATIONS
S0.4	STRUCTURAL GENERAL NOTES
S0.5	STRUCTURAL GENERAL NOTES
S0.6	STRUCTURAL GENERAL NOTES
S0.7	CONSTRUCTION SEQUENCE PHASE 1
S0.7A	CONSTRUCTION SEQUENCE PHASE 1
S0.7B	OVERALL CONSTRUCTION SEQUENCE STRUCTURAL PHASE 1
S0.8	CONSTRUCTION SEQUENCE PHASE 2
S0.8A	CONSTRUCTION SEQUENCE PHASE 2
S0.8B	OVERALL CONSTRUCTION SEQUENCE STRUCTURAL PHASE 2
SI.1	LAYOUT PLAN
SI.2	FOUNDATION PLAN
SI.3	DECK FRAMING PLAN
SI.4	LONGITUDINAL SECTION
SI.5	TYPICAL SECTION
SI.6	FINAL DECK ELEVATION PLAN
S2.1	EXISTING BRIDGE DEMOLITION PLAN
S2.2	EXISTING BRIDGE DEMOLITION SECTIONS
S3.1	DECK REINFORCING PLAN
S3.2	PARTIAL DECK SECTION AND DUCT ENCASEMENT DETAIL
S3.3	PARTIAL DECK SECTION
S3.4	PARTIAL DECK SECTION
S3.5	PARTIAL DECK SECTION
S3.6	DECK REINFORCING AT QUADGUARD
S3.7	PRECAST DECK FORM

[illegible]

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY _____	" _____
	TRACED BY _____	" _____
	DESIGNED BY _____	" _____
	QUANTITIES BY _____	" _____
No. _____	CHECKED BY _____	" _____

DRAWING NAME: T: \PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S001 SW FIXED.DWG PLOT TIME: 06-09-21, 2:48 PM)



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

SIGNATURE LIC. EXPIRATION
4/30/22

MITSUBUANA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


INDEX OF BRIDGE DRAWINGS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: None Date: November 2020

SHEET No. *50.1* OF *12* SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	63	161

[illegible][illegible]

THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

 4/30/2

SIGNATURE LIC. EXPIRATION
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

INDEX OF BRIDGE DRAWINGS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: None Date: November 2020

SHEET No. *50.2* OF *12* SHEETS

SYMBOLS AND ABBREVIATIONS


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	64	161

¢	And	Dbl.	Double	(H)	Hinge	PCF	Pounds per Cubic Foot	T	Top
@	At	Det.	Detail	HECO	Hawaiian Electric Company	Perf.	Perforated	Tan.	Tangent
Ⓔ	Baseline	DI	Drain Inlet, Ductile Iron	Horiz., H	Horizontal	PI	Point of Intersection of Tangents	T&B	Top and Bottom
Ⓒ	Centerline	Dia.	Diameter	HS	High strength	PIVC	Point of Intersection of Vertical Curve	Temp.	Temporary
∅	Diameter	Diaph.	Diaphragm	Ht.	Height	PL	Plate	Thk.	Thick
≥	Greater Than or Equal to	Dim.	Dimension	IB	Inbound	PLF	Pounds per Linear Foot	TFE	Top of Footing Elevation
≤	Less Than or Equal to	Dist.	Distance	ID	Inside Diameter	PP	Precast Plank	TOD	Top of Deck
#	Number	Dn.	Down	I.F.	Inside Face	PRC	Point of Reverse Curvature	TOF	Top of Footing
±	Plus or Minus	DO	Ditto	In.	Inch	Prestr.	Prestressed	Tot.	Total
		DS	Drilled Shaft	Int.	Interior	P/S	Prestressed Strands	TOW	Top of Wall Elevation
AB	Anchor Bolt	Dwg., Dwgs.	Drawing, Drawings	Inv.	Invert	PSF	Pounds per Square Foot	Transv.	Transverse
Abut.	Abutment	Dwls.	Dowels			PSI	Pounds per Square Inch	TS	Structural Tubing
AC	Asphaltic Concrete			Jt.	Joint	Pt., Pts.	Point, Points	Typ.	Typical
Add.	Additional, Added	E	East	K	Kips	PT	Point of Tangency, Post Tensioned	Undergrd.	Underground
Alt.	Alternate	(E), Exp.	Expansion	KF	Kip Foot	PVC	Polyvinyl Chloride	UNO	Unless Noted Otherwise
Approx.	Approximate	EA, Ea., ea.	Each	KLF	Kips Per Linear Foot				
Az.	Azimuth	EF	Each Face	KSF	Kips Per Square Foot	Q	Flow Rate	V, Vert.	Vertical
		EFH	Each Face Horizontal	KSI	Kips Per Square Inch			Var.	Varies
B, Bot., Bott.	Bottom	EFV	Each Face Vertical			R, Rad.	Radius	VESLMC	Very Early Strength Latex Modified Concrete
Bal.	Balance	EJ	Expansion Joint	L	Length	Rdwy.	Roadway	VC	Vertical Curve
Bet.	Between	El., Elev.	Elevation	lb., lbs., LBS.	Pound, Pounds	Rebar	Reinforcing Bar		
BF	Both Faces, Back Face	Elec.	Electrical	LF, Lin. Ft.	Linear Feet/Foot	Ref.	Reference	W	West
BFE	Bottom of Footing Elevation	EMH	Electrical Manhole	Longit.	Longitudinal	Reinf.	Reinforced, Reinforcing, Reinforcement	w/	With
Bk.	Back	Emb.	Embankment	LS	Lump Sum	Req'd.	Required	W/C	Water/Cement Ratio
Blt.	Bolt	Embed.	Embedded, Embedment	Ltg. Std.	Lighting Standard	Ret.	Retaining	WP	Work Point, Working Point
Bm.	Beam	EP	Edge of Pavement	M	Modified	RF	Rear Face	WS	Water Surface
BOF	Bottom of Footing	EPS	Expanded Polystyrene	Max.	Maximum	R/W, ROW	Right of Way	WW	Wing Wall
Br.	Bridge	Eq.	Equal	Mech.	Mechanical			WWR	Welded Wire Reinforcing
Brg., Brgs.	Bearing, Bearings	Est.	Estimated	MH	Manhole	S	South		
BVC	Beginning of Vertical Curve	EVC	End of Vertical Curve	Min.	Minimum	SDMH	Sewer Drain Manhole	Yr.	Year
BW	Both Ways	EW	Each Way	Misc.	Miscellaneous	SE	Super Elevation		
		Ex., Exist.	Existing	MPH	Miles Per Hour	Sect.	Section		
Cant.	Cantilever	Exc.	Excavation	N	North	SF	Square Feet		
CBW	Concrete Barrier Wall	Excl.	Excluding	N/A	Not Applicable	Sht.	Sheet		
cc	Center to Center	Ext.	Exterior	NF	Near Face	Sim.	Similar		
CF	Cubic Feet			NIC	Not in Contract	Sl.	Slope		
CFCW	Continuous Flashing Compound Waterproofing	(F)	Fixed	No.	Number	Spc., Spg.	Spaces, Spacing		
CG	Center of Gravity	F'c	Specified Strength of Concrete	NTS	Not to Scale	Spec.	Specification		
cgs	Center to Gravity of Strands	F'ci	Strength of Concrete at Time of Initial Prestress			Sprd.	Spread		
CIP	Cast-in-Place	FF	Far Face, Front Face	OB	Outbound	SS	Stainless Steel		
CJ	Control Joint	Fig.	Figure	oc	On Center	Sta.	Station		
Cl.	Class	Fin. Gr.	Finish Grade	OD	Outside Diameter	Stagg.	Staggered		
Clr.	Clearance	FRP	Fiber Reinforced Plastic	O.F.	Outside Face	Std.	Standard		
CLSM	Controlled Low Strength Material	Ft.	Feet, Foot	OG	Outside Girder, Outbound Girder	Stiff.	Stiffener		
CO	Clean Out	Ftg.	Footing	Opn'g	Opening	Stirr.	Stirrup		
Col.	Column			O/S	Offset	Stl.	Steel		
Conc.	Concrete	Ga.	Gage, Gauge			Str.	Straight		
Conn.	Connection	Galv.	Galvanized	PB	Pull Box	Struct.	Structure		
Const.	Construction	GFRP	Glass Fiber Reinforced Polymer	P(e)	Effective Prestressing Force	SY	Square Yard		
Const. Jt.	Construction Joint	Gr.	Grade	PC	Point of Curvature	Symm.	Symmetrical		
Cont.	Continuous	Grd.	Ground	PCC	Portland Cement Concrete				
CSL	Cross Hole Sonic Logging	GRP	Grouted Rubble Pavement						
CY, Cu. Yd.	Cubic Yard								

ORIGINAL DRAWN BY	DATE
DESIGNED BY	
NOTED BY	
CHECKED BY	

NO.

DRAWING NAME: I:\PROJECTS\1-01-KAIPAPAU BRIDGE\1-01-REVISED-STRUCT\1-01-051221\KSB-S003.DWG PLOT TIME: 06-09-21, 2:54 PM



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: [Signature] LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SYMBOLS AND ABBREVIATIONS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: None Date: February 2021

SHEET No. S03 OF 12 SHEETS

STRUCTURAL GENERAL NOTES

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	ADD. 65	161

1. GENERAL SPECIFICATIONS:

(A) Hawaii Department of Transportation, Hawaii Standard Specifications for Road and Bridge Construction, 2005, together with Special Provisions prepared for this Contract.

2. DESIGN SPECIFICATIONS:

(A) AASHTO 2012 LRFD Bridge Design Specifications (Sixth Edition) and its subsequent interim specifications with interim supplements and modifications by the HDOT Highways Division.

(B) HDOT Document dated March 1, 2013 with subject title "Design Criteria for Bridges and Structures"

(C) AASHTO 2013 Standard Specifications for structural supports for Highways, Signs, Luminaires, and Traffic Signals (Sixth Edition) and its subsequent interim specifications with interim supplements and modifications by the HDOT Highways Division.

3. LOADS:

(A) Dead Load: A 25 psf allowance for future wearing surface of asphalt concrete has been included in Dead Load calculations. Concrete unit weight of 160 pcf has been assumed for Dead Load calculations. A future utilities load on each side of the Bridge of 150 plf has been included.

(B) Live Load: HL-93 Service and Strength Limit States

(C) Seismic: In accordance with AASHTO LRFD Bridge Design Specifications, 6th Edition, 2012:

Peak Ground Acceleration (PGA = 0.18g), modified by the Site Coefficient ($F_{PGA} = 1.44$) to give a spectrum acceleration, $A_S = 0.26g$

Short period acceleration at 0.2 seconds ($S_S = 0.40g$) modified by the Site Coefficient ($F_a = 1.48$) to give the short period spectrum acceleration, $S_{DS} = 0.592g$

Long Period acceleration at 1.0 seconds ($S_1 = 0.11g$) modified by the Site Coefficient ($F_v = 2.36$) to give the long period spectrum acceleration, $S_{D1} = 0.260g$

Site Class = D
Seismic Zone = 2
Operational Category = Essential

(D) Federal Emergency Management Agency (FEMA)
-Flood Hazard Designation:

Zone: _____ AE
Base Flood Elevation: _____ El. = 14
(Upstream of Bridge)
Non-Bore Tsunami Run up: _____ El. = 10

3. LOADS (Cont.):

(E) Combined Scour Elevations:
Abutment No. 1: _____ 100 year Scour El. = -8.0

Abutment No. 2: _____ 100 year Scour El. = -8.0

(F) Railing Test Level TL-3

(G) Seismic Parameters for Segmental Retaining Wall - Refer to S12.5.

4. MATERIALS:

(A) All concrete strengths shall be as noted below:

Item No.	Structural Parts	Compressive Strength f'c (28 Days)	Maximum Water (W/C)	Maximum Cement (lbs/cyd)	Maximum Cementitious Material Content (lbs/cyd)
(1)	Drilled Shafts including Trial and Load Test Shafts See Note (E) in this section	4500 psi	0.45	720	720
(2)	Drilled Shaft Cap Beam, End Beam, Aesthetic Railing, End Post, Concrete Barrier, Corbel for Approach Slab, Corbel for Conc. Encased Ducts, Diaphragms, Girder Seats, Barrier Wall, Wing Walls and Wing Wall return See Notes (D), (E), and (F) in this section	5000 psi	0.40	670	670
(3)	Prestressed Girders See Note (E) in this section and Sheet S4.5	10000 psi (12000 psi at 56 days)	0.40	670	752
(4)	Precast Deck Form See Notes (D), (E) and (F)	6000 psi	0.40	670	670
(5)	Bridge Deck, Topping over End Beam, Approach Slabs, Concrete encasing ducts within bridge, and Sleeper Slab. See Notes (D), (E) and (F).	SBD (See Section 601)	--	--	--
(6)	Temporary Bridge Abutments, Piers, Footings, and Miscellaneous Concrete	4000 psi	0.45	670	670
(7)	Deck and End beam Closure Pours (Including Corbel), See Note (E)	VESLMC (See Section 540)	-	-	-
(8)	Concrete for Waterline: a. Cradle See notes (D), (E), and (F) b. Curtain wall shall be light weight concrete (Density < 120 lbs/cu. ft.) (See Section 627)	5000 psi 3000 psi	0.40 -	670 -	670 -
(9)	All others, except as noted otherwise	4000 psi	0.45	670	670

4. MATERIALS (Cont.):

(B) Concrete mixes shall be designed to be pumpable and flowable with minimum segregation and separation.

(C) The use of calcium chloride in any concrete is prohibited.

(D) A shrinkage reducing admixture (SRA), such as Master Life SRA35 by BASF or Eclipse by W.R. Grace & Co., or accepted equal, shall be added to the concrete mix for Items No. (2), (4), (5) and (8)a, under note 4.(A). The minimum dosage requirement shall be 128 ounces per cubic yard of concrete. Include the weight of the SRA with the total water in computation of the Water to Cement Ratio.

(E) A migrating corrosion inhibitor amine carboxylate water-based admixture shall be added to the concrete mix for Item Nos. (1), (2), (3), (4), (5), (7) and (8). under Note 4.(A). The minimum dosage shall be 24 ounces per cubic yard of concrete.

(F) A 1 1/2" long macro synthetic fiber such as Forta Ferro, Strux 90/40, Max Matrix, or approved equal shall be added to the concrete mix for items No. (2), (4), (5) and (8)a. under note 4.(A). The minimum dosage shall be 7.5 pounds per cubic yard of concrete.


(G) Non-shrink Grout shall be a pre-mixed product consisting of non-staining, non-metallic aggregate cement, water reducing and plasticizing agents capable of developing a minimum compressive strength of 4000 psi in 3 days and 7000 psi in 28 days. The non-shrink grout shall contain at least 10 grams of migrating amine carboxylate corrosion inhibiting admixture per 0.4 to 0.5 cubic feet of non-shrink grout.

(H) Cure concrete as specified in the Contract documents. Remove curing that may affect binding from all areas requiring future bonding unless a curing agent such as SINAK Lithium Cure or accepted equal that does not affect bond and provide equal or better curing is used.

(I) All concrete shall include at least one of the three methods stated in Section 601 of the Special Provisions, or approved equal, to reduce the embodied carbon footprint in concrete.

3

7/21/21	Revised Comp. Strength for Prestressed Girders
DATE	REVISION
STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION	
STRUCTURAL GENERAL NOTES	
KAMEHAMEHA HIGHWAY Kaipapau Stream Bridge Replacement Federal Aid Proj. No. BR-083-1(48)	
Scale: None	Date: February 2021
SHEET No. S04 OF 12 SHEETS	



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: _____ LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	66	161

5. FOUNDATION NOTES (Cont.):


- (1) 4'-0" Diameter Drilled Shaft Foundations - See S8.1 for estimated shaft tip elevations.
 - a. The drilled shaft foundations will derive support principally from adhesion between the sides of the drilled shaft and the dense old alluvium, conglomerate and/or basalt formation encountered in the Geotechnical Engineering borings.
- (2) Design Soil Parameters
 - a. Static Lateral Earth Pressures at Abutments and Wing Walls above ground water:
 1. Active Condition, level backfill = 40 pcf
 2. At-Rest Condition, level backfill = 58 pcf
 - b. Static Lateral Earth Pressures at Abutments and Wing Walls below ground water:
 1. Active Condition, level backfill = 80 pcf
 2. At-Rest Condition, level backfill = 88 pcf
 - c. Seismic

<i>Dynamic Lateral Earth Forces for Retaining Structures</i>	
<i>Allowable Lateral Wall Movement</i> <i>(inches)</i>	<i>Dynamic Lateral Earth Forces</i> <i>(H² pounds per linear foot)</i>
<i>0.5</i>	<i>19.6</i>
<i>1.0</i>	<i>14.8</i>
<i>1.5</i>	<i>11.5</i>
<i>2.0</i>	<i>8.1</i>
<i>2.5</i>	<i>5.8</i>

- (B) For Drilled Shaft notes, see shts. S8.1 and S8.2.

5. FOUNDATION NOTES:

- (A) *The Foundation Design is based upon recommendations contained in the Geotechnical Engineering Exploration report entitled "Geotechnical Exploration, Kamehameha Highway (Route 83), Kaipapau Stream Bridge Replacement, Koolauloa, Oahu, Hawaii, August 6, 2014. The Report shall be considered as a part of the contract documents and its recommendations shall be implemented unless otherwise directed by the Engineer. The Contractor may obtain a copy of the report at the State of Hawaii, Department of Transportation - Highways Division - upon written request to the Engineer.*



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

STRUCTURAL GENERAL NOTES

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: None Date: February 2021

SHEET No. **S05** OF **12** SHEETS

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S004 SW FIX KSI R1.DWG PLOT TIME: 06-09-21, 2:55 PM)

STRUCTURAL GENERAL NOTES

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	67	161

6. CONSTRUCTION REQUIREMENTS:

- (A) Exact location of bars shall be arranged so that no interference will occur between vertical reinforcement and foundation or drilled shaft cap horizontal reinforcements.
- (B) Except as noted otherwise, all vertical dimensions are measured plumb.
- (C) The Contractor shall verify all grades and dimensions before commencing with any work.
- (D) The Contractor shall verify the locations of all existing utility lines near the bridge, abutments and retaining walls and notify their respective owners before commencing with the work of excavation, underpinning or drilling of shafts.
- (E) Any damage to utility lines caused by the Contractor or his agents or Sub-Contractors, shall be repaired at his expense and to the satisfaction of the Engineer.
- (F) Unless noted otherwise, all exposed concrete edges shall have a chamfer of 3/4 inch.
- (G) Temporary shoring/under-pinning and dewatering may be required for foundation excavations.
- (1) The Contractor shall refer to the Geotechnical Engineering Exporation Report Referenced at "FOUNDATION NOTES" above for recommendations.
- (2) Vibratory shoring (such as interlocking Steel Sheetpiling) will not be allowed.
- (3) Temporary shoring / under-pinning and dewatering shall be in accordance with the Specifications and shall not proceed without the Engineer's Review and Approval.
- (4) Temporary Shoring / under-pinning and dewatering shall be considered incidental to Structural Excavation.
- (5) All Temporary Shoring / under-pinning and dewatering specifications, working drawings and structural calculations shall be signed and sealed by Hawaii licensed professional engineers specializing in Geotechnical and Structural Engineering. This work shall be acceptable to the Engineer before the start of construction and shall be considered incidental to the related Contract item.

6. CONSTRUCTION REQUIREMENTS (Cont.):

- (H) Bridge deck riding surface shall be longitudinally, mechanically ground a minimum of 1/8" over entire travel way and shoulder. The ground surface shall have a textured surface with peaks 1/16" above the bottom of the groove and 55 to 60 grooves per foot of width. After grinding, the deck shall also be longitudinally, mechanically grooved. See Section 503 of the specifications for additional information. The bridge shall not be open to public traffic until the mechanical grooving, all traffic safety devices and markers are complete and acceptable to the Engineer. Sidewalks on bridge shall receive a medium broom finish transverse to the sidewalk. Finish all other elements as directed in Section 503.
- (J) Explosive blasting is prohibited for demolition or any other work on this project.
- (K) Contractor's temporary shoring and falsework design and construction shall comply with the specifications, Special Provision 503.03 (B), AASHTO Guide Design Specifications for Bridge Temporary Work (latest edition) and AASHTO Construction Handbook for Bridge Temporary Works (latest edition). The most stringent requirements shall govern.
- (L) Girders shall be rinsed with potable water to remove salt spray from ocean transport before arrival at jobsite. Notify Engineer for verification of rinsing operation.


7. PRESTRESSED GIRDER BEARING SURFACES:

- (A) Prestressed girder bearing surface shall be smooth.
- (B) Girders shall be set on fresh layers of slush grout to ensure full bearing.
- (C) When a Girder is removed from its casting bed, all bars and strands projecting from the Girder shall be cleaned and painted with a miniumum dry film thickness of 1-mil galvanizing high zinc dust paint conforming to Federal Specification MIL-P-21035B. During handling and shipping, projecting reinforcement shall be protected from bending or breaking. Just before placing concrete around the painted projecting bars or strands, the Contractor shall remove from them all spattered concrete remaining from girder casting, dirt, oil, and other foreign matter.

8. LOAD RATING:

- (A) New governing Load Rating results are as follows:

		RATING FACTOR	DISTRIBUTION FACTOR	LOAD EFFECT
DESIGN	HL-93 Inventory	1.28	0.378	Neg. Moment
	HL-93 Operating	1.66	0.378	Neg. Moment



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

STRUCTURAL GENERAL NOTES

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: None Date: February 2021

SHEET No. S06 OF 12 SHEETS

ORIGINAL PLAN	DESIGNED BY	DATE
NOTE BOOK	DESIGNED BY	
No.	QUANTITIES BY	
	CHECKED BY	

DRAWING NAME: I:\PROJECTS\13-01-KAIPAPAU BRIDGE\13-01-REVISED-STRUCT\13-01-051221\KSB-S004-SW-ITX-KSI-RL.DWG PLOT TIME: 06-09-21, 2:56 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	68	161



CONSTRUCTION SEQUENCE NOTES:

- Order of construction sequence shall not be changed.
- Each sequence stage shall be completely finished before proceeding to the next stage unless otherwise noted. The Engineer will be the sole judge of whether the sequence stage is complete, and may direct the Contractor to stop work on a sequence stage to complete work on the preceding sequence stage.
- Contractor shall submit overweight vehicular details for approval prior to their use.

CONSTRUCTION SEQUENCE

Scale: 1/8" = 1'-0"

LEGEND:


Phase 1 Stages

CONSTRUCTION SEQUENCE ELEVATION

- Relocate existing utility lines.
- Construct trial and load test shafts. Perform load test.
- Install detour road and temporary bridge.
- Demolish existing bridge after obtaining demolition plan acceptance.
- Construct precast girders. (May be done concurrently with Stages 1 through 4)
- Construct 4 ft diameter drilled shafts. Shaft numbers 1, 2, 3, 5, 6, 7.
- Cast Phase 1 drilled shaft cap beams, girder seats, and corbels for concrete encased ducts at least 7 days after the final drilled shaft concrete pour in Stage 6 or until the concrete in Stage 6 has attained a compressive strength of 4,500 psi, whichever occurs later.
- Erect Phase 1 precast girders at least 15 days after the concrete pour in Stage 7 or until the concrete in Stage 7 has attained a compressive strength of 5,000 psi, whichever occurs later. Place slush grout immediately prior to placement of precast girders.
- Construct Phase 1 diaphragm "A".
- Set ducts and pour duct encasement in Bay 3.
- Pour Phase 1 cast-in-place deck except areas over end beams a minimum of 24 hours after the concrete pour in Stage 9A.
- Pour Phase 1 corbel and end beams to top of precast girder at least 30 days after the concrete pour in Stage 10. The concrete pour shall occur between midnight and 3:00 AM (3 hour window).
- Pour remainder of Phase 1 deck concrete a minimum of 24 hours after the concrete pour in Stage 11.

- Construct Phase 1 wing walls at least 8 days after the concrete pour in Stage 12 or after the concrete in Stage 12 has attained a compressive strength of 5,000 psi, whichever occurs later.
- Backfill to Phase 1 limits and to bottom of approach slab at least 14 days after the concrete pour in Stage 13 or until the concrete in Stage 13 has attained a compressive strength of 5,000 psi, whichever occurs later. Maximum height difference of backfill between abutments shall not exceed 2 feet. Install concrete encased ducts behind abutments when backfill height is at the elevation of the bottom of the concrete encased electrical ducts. Continue backfilling after concrete for encased electrical ducts has attained its 28 day compressive strength.
- Construct concrete barrier wall. (Coordinate construction of concrete barrier wall with stage 14A construction).
- Construct Phase 1 sleeper slabs.
- Construct Phase 1 approach slabs.
- Blanket grind deck, approach slabs, and sleeper slabs where traffic will be allowed during construction of phase 2.
- Mechanically groove deck, approach slabs, and sleeper slabs where traffic will be allowed during construction of phase 2.
- Construct mauka aesthetic railing and concrete barrier.
- Install mauka quadguards.
- Install temporary barriers.

GRAPHIC SCALE:
8 6 4 2 0 8 16
SCALE: 1/8" = 1'-0"



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: [Signature] LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
CONSTRUCTION SEQUENCE
PHASE 1
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. S07 OF 12 SHEETS

ORIGINAL PLAN
DATE
DRAWN BY
DESIGNED BY
NOTED BY
QUANTITIES BY
CHECKED BY
No.

PROJECT NAME: KAIPAPAU STREAM BRIDGE REPLACEMENT - OVERALL CONSTRUCTION SEQUENCE - PHASE 1

STRUCTURAL PHASE 1


KAIPAPAU STREAM BRIDGE REPLACEMENT – OVERALL CONSTRUCTION SEQUENCE

Structural Construction Stage	Description	References				Waterline Work	Exist Bridge Open	Detour Open	Detour Off Peak Lane Closures Anticipated	Remarks
		Civil	Electrical	Geotech.	Structural					
Prior to Site Mobilization for Demolition	1. Prior to Site Mobilization, the Contractor shall submit required BMP's and other Municipal and National permit applications as indicated in the project Plans, Special Provisions and Specifications. 2. The Contractor shall submit Prefabricated Steel Beam Bridge Structural Computations and Erection drawings to the Owner for Review and Approval Prior to Fabrication.	Civil Sequence See C-11. See Civil [7] & Civil [3]			Structural Sequence S0.7, S0.7A, S0.8, S0.8A		Exist Bridge Open to Traffic			
[1]	1. Install approved BMP measures. 2. Relocate Existing overhead utility lines.	C-18, C-21 to C-23	E-8, E-9, E-10, E-11							
[2]	1. Construct Trial and Load Test shafts * 2. Perform Load Test. Demobilize drilled shaft equipment off site.	See Civil [4]		Special drilling equipment*	S1.1, S8.3					Special *Provisions Section 511
[3]	1. Install Detour Pier, Abutments and Temporary Bridge. Construct Civil temporary 16" on temporary bridge C-32; C-31. 2. Construct Detour Approach Retaining Wall, Fills and Roadway – chainlink fence see C-24. 3. Open Detour to vehicles and pedestrians. Close existing bridge. 4. Install temporary 12" fusible PVC waterline on existing (upstream) pedestrian walkway and relocate 12" waterline C-21 to C-23. 5. Connect temporary 16" waterline to existing 16" waterline, see C-31; C-33. See remark	See Civil [5] C-21 to C-24, C-31 to C-33. See Civil (5A), (5B), & (5C).	E-10, E-11, E-15	Excavation Bracing-Spec. Prov. 205*	S12.1, S12.2 S12.3, S12.4 S12.5	Phase 1 (W16) then Phase 1, 2, & 3 (W12), then Phase 2 (W16)		Detour Open to Traffic		Connection of the temp. 16" waterline to the existing 16" waterline cannot begin until after the permanent 12" waterline has been pressure tested, accepted by BWS and placed into service and the temp. 12" waterline has been removed.
[4]	1. Demolish existing bridge after obtaining demolition plan acceptance. 2. Demolish and remove portion of ex. 16" waterline and concrete support system as required to construct new bridge. See C-31, C-33.	C-16, C-31, C-33. See Civil [6]		Excavation Bracing-Spec. Prov. 205*	S2.1, S2.2	Phase 2 (W16)	Exist Bridge Demolition			*Exc. Bracing upstream of existing.
[5]	Construct precast girders. (May be done concurrently with stages 1 through 4.)	See Civil [7]			S4.x series					
[6]	Construct 4 ft. diameter drilled shafts. 1, 2, 3, 5, 6, 7. *			Special drilling equipment*	S1.1, S1.2, S6.1, S6.2, S8.1, S8.2					*Special Provisions Section 511
[7]	Cast phase 1 drilled shaft cap beams, girder seats, and corbels for concrete encased ducts at least 7 days after the final drilled shaft concrete pour in stage 6 or until the concrete in stage 6 has attained a compressive strength of 4,500 psi, whichever occurs later.			Structure – Excavation Bracing per Spec. Prov. 205 Required at Makai Limit	S0.7, S0.7A, S6.x series					Marks [7] through [18] are PHASE 1 Structural see [20] for PHASE 2
[8]	Erect phase 1 precast girders at least 15 days after the concrete pour in stage 7 or until the concrete in stage 7 has attained a compressive strength of 5,000 psi, whichever occurs later. Place slush grout immediately prior to placement of precast girders.				S0.7, S0.7A, S1.2, S1.3, S6.x series					
[9]	Construct phase 1 diaphragm "A".				S0.7, S0.7A, S5.x series					
[9A]	Set ducts and pour duct encasement in Bay 3				S0.7, S0.7A S1.6, S3.x series					
[10]	Pour phase 1 cast-in-place deck except areas over end beams.				S0.7, S0.7A, S6.x series					
[11]	Pour phase 1 end beams to top of precast girder and corbel at least 30 days after the concrete pour in Stage 10. The concrete pour shall occur between midnight and 3:00 AM (3 hours).									Concrete Placement At Night
[12]	Pour remainder of phase 1 deck concrete a minimum of 24 hours after the concrete pour in stage 11.									
[13]	Construct phase 1 wing walls at least 8 days after the concrete pour in stage 12 or after the concrete in stage 12 has attained a compressive strength of 5,000 psi, whichever occurs later.				S0.7, S0.7A, S7.x series				Lane Closure Duration Approx 3 weeks each abutment with Further Lane Closure Duration Approx 2 weeks each approach	
[14A] [14B]	Backfill to phase 1 limits and to bottom of approach slab and at least 14 days after the concrete pour in Stage 13 or until the concrete in Stage 13 has attained a compressive strength of 5,000 psi, whichever occurs later. Maximum height difference of backfill between abutments shall not exceed 2 feet. Install concrete encased ducts when backfill height is at the elevation of bottom of concrete encased ducts. Continue backfilling after concrete for encased ducts has attained its 28 day compressive strength. Construct Barrier Wall. (Coordinate with 14A.)		Signal Corps Work E-1, E-5 E-12, E-13, E-16		S0.7, S0.7A, S6.x S9.x					
[15]	Construct phase 1 sleeper slabs.									
[16]	Construct phase 1 approach slabs.		Signal Corps Work E-1, E-5 E-12, E-13, E-16							
[17]	Blanket grind deck, approach slabs, and sleeper slabs where traffic will be allowed during construction of phase 2.									
[18]	Mechanically groove deck, approach slabs and sleeper slabs where traffic will be allowed during construction of phase 2									
[19A]	Construct mauka aesthetic railings and concrete barrier.									*Special Provisions Section 503
[19B]	Install mauka quadguards.									
[19C]	Install Temporary Barriers and Temporary Striping on PHASE 1 of New Bridge.	See Civil for Barriers								

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	70	161


CONSTRUCTION SEQUENCE NOTES:

- Order of construction sequence shall not be changed unless authorized in writing by the Engineer.
- Each sequence stage shall be completely finished before proceeding to the next stage unless otherwise noted. The Engineer will be the sole judge of whether the sequence stage is complete, and may direct the Contractor to stop work on a sequence stage to complete work on the preceeding sequence stage.
- Contractor shall submit overweight vehicular details for approval prior to their use.
- Construction shall be conducted such that no construction debris, wash water or other contaminants shall enter the Stream Waters.
- Closing of the Prefabricated Steel Beam Bridge Structure:
(a) If for any reason or at any time, the Prefabricated Beam Bridge Structure's ability to safely carry traffic is in question, the Contractor shall be responsible for immediately taking the actions necessary to protect the public by closing, repairing and reopening the Prefabricated Steel Truss Bridge. When the Contractor closes the
(b) Prefabricated Steel Beam Bridge Structure, the Contractor shall immediately notify the Engineer and the appropriate Law Enforcement Agency. Closing of the Prefabricated Steel Beam
(c) Bridge shall be included as incidental to Maintenance of Traffic Control.
- The Contractor shall phase 16 inch waterline (W16) to allow no more than 8 hours of down time. Liquidated Damages of \$100,000 per day will be imposed if the Contractor exceeds the 8 hour restriction.

APPROVED:


MAY 24 2021

Manager and Chief Engineer, BWS, (for work affecting BWS facilities State R/W & BWS easements only)



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

 4/30/22

SIGNATURE: DENNIS K. MITSUNAGA, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

OVERALL CONSTRUCTION SEQUENCE

STRUCTURAL PHASE 1

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021


SHEET No. S0.7B OF 5 SHEETS

To Kahuku

To Kaneohe

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	71	161

APPROVED:  MAY 24 2021
DATE
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)



CONSTRUCTION SEQUENCE

Scale: 1/8" = 1'-0"

LEGEND:

Phase 2 Stages

CONSTRUCTION SEQUENCE ELEVATION

- 20 Partially remove temporary bridge as required to construct Phase 2 of Kaipapau Stream Bridge
- 21 Construct 4 ft diameter shafts - Shaft nos. 4 and 8.
- 22 Cast Phase 2 drilled shaft cap beams and girder seats at least 7 days after the final drilled shaft concrete pour in Stage 21 or until the concrete in Stage 21 has attained a compressive strength of 4,500 psi, whichever occurs later.
- 23 Erect Phase 2 precast girders at least 15 days after the concrete pour in Stage 22 or until the concrete in Stage 22 has attained a compressive strength of 5,000 psi, whichever occurs later. Place slush grout immediately prior to placement of precast girders.
- 24A Construct Phase 2 diaphragms "A" and "B", except diaphragms between girders G-8 and G-9.
- 24B Construct waterline cradles.
- 25 Pour Phase 2 cast-in-place deck except areas over end beams and closure pour.
- 26 Pour Phase 2 corbel and end beams (except at closure pour) to top of precast girder at least 30 days after the concrete pour in Stage 25. The concrete pour shall occur between midnight and 3:00 AM (3 hour window).
- 27 Pour remainder of Phase 2 deck concrete (except at closure pour) a minimum of 24 hours after the concrete pour in Stage 26.
- 28 Pour Phase 2 diaphragm "A" between girders G-8 and G-9 at least 4 days after the concrete pour in Stage 27.
- 29 Pour Phase 2 cast-in-place deck closure except over end beams. Material for cast-in-place deck closure pour shall be VESLMC. (See Special Provisions).


CONSTRUCTION SEQUENCE NOTES:

1. Order of construction sequence shall not be changed.
2. Each sequence stage shall be completely finished before proceeding to the next stage unless otherwise noted. The Engineer will be the sole judge of whether the sequence stage is complete, and may direct the Contractor to stop work on a sequence stage to complete work on the preceding sequence stage.
3. Contractor shall submit overweight vehicular details for approval prior to their use.

- 30 Pour Phase 2 corbel and end beam closure from top of drilled shaft cap beam to top of deck. Material for end beam closure pour shall be VESLMC. (See Special Provisions).
- 31A Construct Phase 2 wing walls and return wall at least 8 days after the concrete pour in Stage 30 or after the concrete in Stage 30 has attained a compressive strength of 5,000 psi, whichever occurs later.
- 31B Install W16, W16 reaction blocks and W16 curtain wall.
- 32A Backfill to bottom of approach slab at least 14 days after the concrete pour in Stage 31A or until the concrete in stage 31A has attained a compressive strength of 5,000 psi, whichever occurs later. Maximum height difference of backfill between abutments shall not exceed 2 feet.
- 32B Construct Concrete Barrier Wall. (Coordinate construction of Concrete Barrier Wall with Stage 32A).
- 33 Construct Phase 2 sleeper slabs.
- 34 Construct Phase 2 approach slabs.
- 35 Blanket grind deck, approach slabs, and sleeper slabs.
- 36 Mechanically groove deck, approach slabs, and sleeper slabs.
- 37 Construct Makai aesthetic railing and concrete barrier.
- 38 Install Makai quadguards.
- 39 Remove remainder of temporary bridge.

GRAPHIC SCALE:

8 6 4 2 0 8 16
SCALE: 1/8" = 1'-0"




STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
CONSTRUCTION SEQUENCE
PHASE 2
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021
SHEET No. 508 OF 12 SHEETS

SURVEY PLOTTED BY	DATE
DRAWN BY	
DESIGNED BY	
CHECKED BY	
ORIGINAL PLAN	
NOTE BOOK	
No.	

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\313-01 KAIPAPAU BRIDGE\313 REVISED STRUCT\313-051221\WCB-5008.DWG PLOT TIME: 05-13-21 8:56 AM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	72	161




CONSTRUCTION SEQUENCE PLAN (PHASE 2)

Scale: 3/32" = 1'-0"

LEGEND:


- # Construction Sequence Stage
- # Drilled Shaft ID
- (TS) Trial Shaft
- (LT) Load Test Shaft
- Closure Pour




CONSTRUCTION SEQUENCE (PHASE 2)

Scale: 1/4" = 1'-0"

GRAPHIC SCALES:



APPROVED:  DATE: MAY 24 2021
 Manager and Chief Engineer, BWS
 (for work affecting BWS facilities
 State R/W & BWS easements only)

STATE OF HAWAII
 DEPARTMENT OF TRANSPORTATION
 HIGHWAYS DIVISION
CONSTRUCTION SEQUENCE
PHASE 2
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
 Scale: As Noted Date: February 2021
 SHEET No. S0.8A OF 12 SHEETS

SURVEY PLOTTED BY	DATE
DRAWN BY	
TRACED BY	
CHECKED BY	
QUANTITIES BY	
NO.	

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\11-REVISED_STRUCT\11-KSB-S008A.DWG PLOT TIME: 05-13-21, 8:07 AM

ORIGINAL PLAN

DATE

SURVEY PLOTTED BY

DRAWN BY

DESIGNED BY

QUANTITIES BY

CHECKED BY

No.

DRAWING NAME: E:\PROJECTS\1-ACTIVE FILES\913-01 KAIPAPAU BRIDGE\14 REVISED STRUCTURE\05121\ASB-508B.DWG PLOT TIME: 05-11-21 8:12 AM

STRUCTURAL PHASE 2

KAIPAPAU STREAM BRIDGE REPLACEMENT – OVERALL CONSTRUCTION SEQUENCE										
Structural Construction Stage	Description	References				Waterline Work	Exist Bridge Open	Detour Open	Detour Off Peak Lane Closures Anticipated	Remarks
		Civil	Electrical	Geotech.	Structural					
20	1. Open PHASE 1 of New Bridge to traffic. Close Temporary Bridge and Detour Roadway to traffic. 2. Remove Mauka portion of Temporary Bridge Only (Remainder to remain in place to support construction equipment for construction of PHASE 2 portion of New Bridge and to support temporary W16 until Final W16 is constructed).	See Civil 8			S0.8, S0.8A		PHASE 1 of New Bridge Open to Traffic to allow Detour Closure	Close Detour and Remove Limited Portion of Temporary Bridge	Not Applicable	Close Detour; Open PHASE 1 of New Bridge; Start Construction of PHASE 2 of New Bridge
21	Construct 4 ft. diameter drilled shafts – Shaft nos. 4 and 8.	See Civil 8		Special drilling equipment*	SI.1, SI.2, S6.1, S6.2, S8.1, S8.2			Detour Closed		*Special Provisions Section 511
22	Cast Phase 2 drilled shaft cap beams and girder seats at least 7 days after the final drilled shaft concrete pour in stage 21 or until the concrete in stage 21 has attained a compressive strength of 4,500 psi, whichever occurs later.			Structure Excavation Bracing per Spec for 205 Required at Approaches.	S0.8, S0.8A, S6.x series					Special Provisions Section 205
23	Erect Phase 2 precast girders at least 15 days after the concrete pour in stage 22 or until the concrete in stage 22 has attained a compressive strength of 5,000 psi, whichever occurs later. Place slush grout immediately prior to placement of precast girders.				S0.8, S0.8A, SI.2, SI.3, S6.x series	Civil Phase 3 (W16) waterline improvements see C-30, C33				Connection of the temp. 16" waterline to the existing 16" waterline cannot begin until after the permanent 12" waterline has been pressure tested, accepted by BWS and placed into service and the temp. 12" waterline has been removed.
24A	Construct Phase 2 diaphragms "A" and "B", except diaphragms between girders G-8 and G-9.	C-34			S0.8, S0.8A, S5.x series					
24B	Construct Waterline cradles									
25	Pour Phase 2 cast-in-place deck except areas over end beams and closure pour.				S0.8, S0.8A SI.6, S3.x series					
26	Pour Phase 2 end beams (except at closure pour) to top of precast girder and corbel at least 30 days after the concrete pour in Stage 25. <u>The concrete pour shall occur between midnight and 3:00 AM (3 hours).</u>				S0.8, S0.8A, S6.x series					Concrete Placement At Night
27	Pour remainder of Phase 2 deck concrete (except at closure pour) a minimum of 24 hours after the concrete pour in stage 26.									
28	Pour Phase 2 diaphragm "A" between girders G-8 and G-9 at least 4 days after the concrete pour in stage 27.									
29	Pour Phase 2 cast-in-place deck closure except over end beams. Material for cast-in-place deck closure pour shall be VESLMC.									
30	Pour Phase 2 end beams closure from top of drilled shaft cap beam to top of deck. Material for end beam closure pour shall be VESLMC.									
31A	Construct Phase 2 wing walls and return wall at least 8 days after the concrete pour in stage 30 or after the concrete in stage 30 has attained a compressive strength of 5,000 psi, whichever occurs later.				S0.8, S0.8A, S7.x series					
31B	Install W16, W16 reaction blocks and W16 curtain wall.	C-34								
32A	Backfill to bottom of approach slab at least 14 days after the concrete pour in Stage 31A or until the concrete in Stage 31A has attained a compr. strength of 5,000 psi, whichever occurs later. Max. height difference of backfill between abutments shall not exceed 2 feet. Install jacketed waterline when backfill height is at the elevation of bot. of the jacketed waterline. Continue backfilling after concrete for jacketed waterline has attained its 28 day compr. strength. Construct Barrier Wall.				S0.8, S0.8A, S6.x S9.x					
32B										
33	Construct Phase 2 sleeper slabs.									
34	Construct Phase 2 approach slabs.									
35	Blanket grind deck, approach slabs and sleeper slabs									
36	Mechanically groove deck, approach slabs, and sleeper slabs									
37	Construct Makai aesthetic railings and concrete barrier.									
38	Install Makai guardguard. Remove Detour; construct stream hardening. Remove Temporary Barriers at New Bridge. Open Phase 1 and Phase 2 of New Bridge to traffic.	See Civil 8 thru 12	Permanent Electrical Plan See E-12, E-13, E-14			Remove temp W16 at Closed Detour	PHASE 1 and PHASE 2 of New Bridge Open	Remove Remainder of Detour		

FED. ROAD DIST. NO.

STATE

FEDERAL AID PROJ. NO.

FISCAL YEAR

SHEET NO.

TOTAL SHEETS

HAWAII

HAW.

BR-083-1(48)

2021

73

161

CONSTRUCTION SEQUENCE NOTES:

1. Order of construction sequence shall not be changed unless authorized in writing by the Engineer.

2. Each sequence stage shall be completely finished before proceeding to the next stage unless otherwise noted. The Engineer will be the sole judge of whether the sequence stage is complete, and may direct the Contractor to stop work on a sequence stage to complete work on the preceeding sequence stage.

3. Contractor shall submit overweight vehicular details for approval prior to their use.

4. Construction shall be conducted such that no construction debris, wash water or other contaminants shall enter the Stream Waters.

5. Closing of the Prefabricated Steel Beam Bridge Structure:

(a) If for any reason or at any time, the Prefabricated Beam Bridge Structure's ability to safely carry traffic is in question, the Contractor shall be responsible for immediately taking the actions necessary to protect the public by closing, repairing and reopening the Prefabricated Steel Truss Bridge.

(b) When the Contractor closes the Prefabricated Steel Beam Bridge Structure, the Contractor shall immediately notify the Engineer and the appropriate Law Enforcement Agency.

(c) Closing of the Prefabricated Steel Beam Bridge shall be included as incidental to Maintenance of Traffic Control.

The Contractor shall phase 16 inch waterline (W16) to allow no more than 8 hours of down time. Liquidated Damages of \$100,000 per day will be imposed if the Contractor exceeds the 8 hour restriction.

6. APPROVED:

MAY 2 4 2021

Manager and Chief Engineer, BWS

DATE

(for work affecting BWS facilities State R/W & BWS easements only)

DENIS K. MITSUNAGA

LICENSED PROFESSIONAL ENGINEER

No. 2422-S

HAWAII, USA

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

4/30/22

SIGNATURE

LIC. EXPIRATION

MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII

DEPARTMENT OF TRANSPORTATION

HIGHWAYS DIVISION

OVERALL CONSTRUCTION SEQUENCE

STRUCTURAL PHASE 2

KAMEHAMEHA HIGHWAY

Kaipapau Stream Bridge Replacement

Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted

Date: February 2021


SHEET No. S0.8B OF 5 SHEETS

73

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	74	161



LAYOUT PLAN
Scale: 1/8" = 1'-0"




ORIGINAL PLAN	DATE
DRAWN BY	
DESIGNED BY	
QUANTITIES BY	
CHECKED BY	
No.	


LEGEND:

- (#) Drilled Shaft ID
- (TS) Trial Shaft
- (LT) Load Test Shaft

Note:

Balance of W16 cradles are not shown for clarity. See sheet S11.1 and S11.1A for details.

APPROVED:  MAY 24 2021
DATE
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

SIGNATURE DATE
MITSUNAGA & ASSOCIATES, INC. LIC. EXPIRATION 4/30/22

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


LAYOUT PLAN

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. **S11** OF 6 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	75	161



FOUNDATION PLAN
Scale: 1/8" = 1'-0"





LEGEND:

- # Drilled Shaft ID
- TS Trial Shaft
- LT Load Test Shaft

References:


1. See Sheet S6.1 for Abutment No. 1 Plan.
2. See Sheet S6.2 for Abutment No. 2 Plan.
3. See Sheets S8.1 through S8.3 for Drilled Shaft Details (Including Load Test Shaft)

APPROVED:  DATE: MAY 24 2021
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
FOUNDATION PLAN
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. S12 OF 6 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	76	161





LEGEND:

(#) Drilled Shaft ID

References:

1. See Sheets S4.1 through S4.5 for Precast Girder Details.
2. See Sheets S5.1 through S5.2 for Diaphragm Details.
3. W16 Cradles are not shown for clarity. See Sheet S11.1 for Details.

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

DECK FRAMING PLAN




KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. **S1.3** OF 6 SHEETS

DESIGNED BY	DATE
DRAWN BY	
CHECKED BY	
NOTED BY	
QUANTITIES BY	
NO.	

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	77	161



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
[Signature]
SIGNATURE
LIC. EXPIRATION
4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

LONGITUDINAL SECTION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. *SI.4* OF 6 SHEETS

ORIGINAL PLAN	DATE
DESIGNED BY	
NOTED BY	
CHECKED BY	

DRAWING NAME: I:\PROJECTS\15-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\15-REVISED STRUCT\15-051221\KCB-S104.DWG PLOT TIME: 06-09-21, 2:59 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	79	161



LEGEND:

 *Drilled Shaft ID*



0.00 Denotes Finish Deck Elevation
at 10 ft. Intervals.
See Civil Drawings for Baseline Profile

FINAL DECK ELEVATION PLAN

Scale: $1/8'' = 1'-0''$

A diagram of a semi-circular arch. A horizontal line represents the span, with a total length of 3.2m. A vertical line divides this span into two equal segments, each labeled 1.6m. Above the span, a semi-circular arch is drawn, labeled 'A' at its peak.

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

FINAL DECK ELEVATION PLAN

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. *Sl.6* OF *6* SHEETS

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S106.DWG PLOT TIME: 06-09-21, 3:00 PM)

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	80	161

Notes to Demolition Plan:


1. Structure backfill after removal shall comply with Special Provisions Section 205 and shall be incidental to Removal of Existing Concrete Bridge.
2. Removal of Existing End Posts and End Post Footings shall be incidental to Removal of Existing Concrete Bridge.
3. Explosive blasting is prohibited.
4. Demolition work Shall Comply with the specifications, Special Provision Section 202; AASHTO Guide Design Specification for Bridge Temporary Works and AASHTO Construction Handbook for Bridge Temporary Works; Including all subsequent interim revisions. The most stringent requirements shall govern.
5. The Demolition work shall:
 - a. Facilitate Removal of Existing Concrete Bridge and Drilled Shaft Work.
 - b. Promote/ensure Best Management Practices Required for Construction.
 - c. Be incidental to Removal of Existing Concrete Bridge.

Note "A"



24" dia. 20T Caisson estimated to be embedded 5 ft. into mudrock.
Approx. Tip Elev.= -20.0

Note "B"

24" dia. 30T Caisson estimated to be embedded 10 ft. into hardrock.
Approx. Tip Elev.= -25.0



Note:
Load test shaft and trial shaft
not shown for clarity.




THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
4/30/22
SIGNATURE: [Signature] LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
**EXISTING BRIDGE
DEMOLITION PLAN**
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. S21 OF 2 SHEETS

ORIGINAL PLAN	DATE
DESIGNED BY	
NOTED BY	
CHECKED BY	

DRAWING NAME: 15\PROJECTS\15-ACTIVE FILES\13-01-KAIPAPAU BRIDGE\15-REVISED STRUCT\15-051221\KCB-S201.DWG PLOT TIME: 06-09-21 3:07 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	81	161




Note:

Abutment to be Removed. See detail 1/S-2 for reinforcing removal detail.

EXISTING BRIDGE DEMOLITION ELEVATION

Scale: 1/8" = 1'-0"

A
S2.1 S2.2




Note:

Top of existing abutment and pier after demolition shall be surface finished with a cement mortar paste.

REINFORCING REMOVAL DETAIL

Scale: 3" = 1'-0"

1
S2.2 S2.2




EXISTING CONCRETE JACKET & CAISSON FOUNDATION AT EXISTING 16" DIA. WATERLINE


Scale: 1/8" = 1'-0"


B
S2.1 S2.2


GRAPHIC SCALE:



ORIGINAL PLAN	DATE
DESIGNED BY	
TRACED BY	
DESIGNED BY	
QUANTITIES BY	
CHECKED BY	
No.	

APPROVED:  MAY 24 2021
Manager and Chief Engineer, BWS (for work affecting BWS facilities State R/W & BWS easements only)



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

SIGNATURE U.C. EXPIRATION 4/30/22
MITSUNAGA & ASSOCIATES, INC.


STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
EXISTING BRIDGE DEMOLITION SECTIONS
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. S22 OF 2 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	82	161

To Kaneohe

Mauka

To Kahuku



DECK REINFORCING PLAN

Scale: 1/8" = 1'-0"


Notes:

- #5 Bottom longitudinal rebars shall be composed of three equal lengths with two splice locations at 1/3 points of bridge span.
- See sheets S3.2 through S3.5. for rebar spacing.

GRAPHIC SCALE:



SCALE: 1/8" = 1'-0"



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *Dennis K. Mitsunaga*
LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

DECK REINFORCING PLAN

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted


Date: February 2021

SHEET No. S3/ OF 7 SHEETS

ORIGINAL PLAN	DATE
DESIGNED BY	
NOTED BY	
CHECKED BY	


DRAWING NAME: 15\PROJECTS\15-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\15-REVISED STRUCT\15-051221\KCB-S301.DWG PLOT TIME: 06-09-21 3:08 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	83	161




- References:**
1. See sheets S4.1 through S4.5 for balance of prestressed girder details.
 2. See sheets S10.3 through S10.5 for aesthetic railing details.
 3. See section B/S9.1 for concrete barrier details.
 4. See sheet S10.2 for joints in concrete barrier.

SECTION NEAR MIDSPAN
Scale: 1" = 1'-0"



DUCT ENCASEMENT DETAIL
Scale: 1 1/2" = 1'-0"



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22

MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

**PARTIAL DECK AND
DUCT ENCASEMENT DETAIL**

**KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)**


Scale: As Noted Date: February 2021

SHEET No. S32 OF 7 SHEETS

ORIGINAL PLAN	DATE
DESIGNED BY	
NOTED BY	
CHECKED BY	

DRAWING NAME: I:\PROJECTS\1-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\1-REVISED STRUCT\1-051221\KCB-S301.DWG PLOT TIME: 06-09-21 3:09 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	84	161



SECTION NEAR MIDSPAN

Scale: 1" = 1'-0"

- ### References:
1. See sheets S4.1 through S4.5 for balance of prestressed girder details.
 2. See sheets S10.3 through S10.5 for aesthetic railing details.
 3. See section B/S9.1 for concrete barrier details.
 4. See sheet S10.2 for joints in concrete barrier.
 5. See sheet S11.1 for W16 cradle.
 6. Precast deck forms shall be supported on a continuous, 1/4" minimum thick, non-shrink grout bed.
 7. Fill 1" gap with non-shrink grout over a length of 1'-6" centered on W16 cradle. Fill gap prior to pouring cradle.

GRAPHIC SCALE:

1 0 1 2

SCALE: 1"= 1'-0"



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

SIGNATURE LIC. EXPIRATION
4/30/22

MITSUBUNAGA & ASSOCIATES, INC.

APPROVED:  MAY 2 4 2021
 For _____ DATE _____
 Manager and Chief Engineer, BWS
 (for work affecting BWS facilities
 State R/W & BWS easements only)

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


PARTIAL DECK SECTION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021



SHEET No. **S33** OF **7** SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	85	161



SECTION NEAR ABUTMENT A
Scale: 1" = 1'-0"

- References:
- See sheets S4.1 through S4.5 for balance of prestressed girder details.
 - See sheets S10.3 through S10.5 for aesthetic railing details.
 - See section B/S9.1 for concrete barrier details.
 - See sheet S10.2 for joints in concrete barrier.



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
[Signature]
SIGNATURE LIC. EXPIRATION
MITSUNAGA & ASSOCIATES, INC. 4/30/22

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

PARTIAL DECK SECTION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S34 OF 7 SHEETS

DESIGNED BY	DATE
DRAWN BY	
CHECKED BY	
NOTED BY	
QUANTITIES BY	
CHECKED BY	


DRAWING NAME: I:\PROJECTS\15-PROJECTS\15-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\15-REVISED STRUCT\15-051221\KCB-S301.DWG PLOT TIME: 06-09-21 3:10 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	86	161




- References:**
1. See sheets S4.1 through S4.5 for balance of prestressed girder details.
 2. See sheets S10.3 through S10.5 for aesthetic railing details.
 3. See section B/S9.1 for concrete barrier details.
 4. See sheet S10.2 for joints in concrete barrier.
 5. See sheet S11.1 for W16 cradle.
 6. Precast deck forms shall be supported on a continuous, 1/4" minimum thick, non-shrink grout bed.
 7. Fill 1" gap with non-shrink grout over a length of 1'-6" centered on W16 cradle.
 8. Fill gap prior to pouring cradle.

SECTION NEAR ABUTMENT
Scale: 1" = 1'-0"



APPROVED:
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)

MAY 2 4 2021
DATE



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

PARTIAL DECK SECTION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S35 OF 7 SHEETS


ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
No.	DESIGNED BY	
	CHECKED BY	

DRAWING NAME: I:\PROJECTS\1-ACTIVE FILES\313-01 KAIAPAU BRIDGE\35 REVISED STRUCT\35-051221MSE-S301.DWG PLOT TIME: 05-12-21, 8:28 AM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	87	161




PARTIAL REINF. PLAN AT KANEHOE-MAUKA QUADGUARD 1
Scale: 1/4" = 1'-0"



SECTION A A
Scale: 1" = 1'-0"
S3.6



PARTIAL REINF. PLAN AT KAHUKU-MAKAI QUADGUARD 2
Scale: 1/4" = 1'-0"



DENNIS K. MITSUNAGA
LICENSED PROFESSIONAL ENGINEER
No. 2422-S
HAWAII, U.S.A.

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

DECK REINFORCING AT QUADGUARD

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S36 OF 7 SHEETS

ORIGINAL PLAN	DATE
DESIGNED BY	
NOTED BY	
QUANTITIES BY	
CHECKED BY	

DRAWING NAME: 15\PROJECTS\15-01\KAIPAPAU BRIDGE\15-01\REVISED STRUCT\15-01\15-01\15-01.DWG PLOT TIME: 06-09-21 3:10 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	88	161




PLAN

Scale: 1" = 1'-0"

A

S3.7 | S3.7




SECTION

Scale: 1" = 1'-0"


B

S3.7 | S3.7



SECTION 

Scale: 1" = 1'-0" 



TRANSVERSE JOINT



Scale: 3" = 1'-0"

1
S3.7 | S3.7

Notes:

1. *Details and locations of lifting devices shall be submitted to the Engineer for approval. Such approval does not relieve the Contractor of his responsibilities if the precast deck form is damaged due to failure of lifting device.*
2. *Contractor shall submit alternative method to lift precast deck form if lifting devices are damaged for review and acceptance.*
3. *Roughen top surface of precast deck form to 1/4" minimum amplitude.*
4. *Precast deck form is incidental to deck concrete.*
5. *GFRP is incidental to the precast deck form.*

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

PRECAST DECK FORM


KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021


SHEET No. **S3.7** OF **7** SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	89	161

Note:
For Prestressed Girder notes,
see Sheet S4.5




TYPE I PRESTRESSED GIRDER ELEVATION (G-1 THROUGH G-9)
Scale: N.T.S.




GIRDER CAMBER DIAGRAM
SCALE: NONE

GIRDER CAMBER NOTES:

1. The calculated camber includes the effect of the initial prestress force and the weight of the girder after removal from the bed. The calculated camber value has been multiplied by creep factor to approximate the effect of camber growth and concrete creep. Positive values shown for initial camber indicate a net upward deflection. Maximum camber immediately prior to erection of girders shall not exceed the calculated camber by more than 1 inch. Girders with cambers exceeding the maximum camber will not be accepted.
2. The dead load deflection includes the combined effects of the weight of slab, drop panels, and diaphragms.
3. Contractor shall camber the deck form work as required to account for the calculated dead load deflection in order to provide the specified finish deck elevations.
4. All cambers and deflections are in inches.
5. Working force is designated as P_e .



TYPICAL END ELEVATION
Not to Scale



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TYPE I PRESTRESSED GIRDER

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S4J OF 5 SHEETS

ORIGINAL PLAN	DATE
NOTE BOOK	
No.	


DRAWING NAME: I:\PROJECTS\1-01-KAIPAPAU BRIDGE\1-01-REVISED STRUCT\1-01-REVISED STRUCT\1-01-REVISED STRUCT.dwg PLOT TIME: 06-09-21 3:15 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	91	161



Note:
For Prestressed Girder notes,
see Sheet S4.5.


TYPE II PRESTRESSED GIRDER ELEVATION (G-10 AND G-11)
Scale: N.T.S.




GIRDER CAMBER DIAGRAM
SCALE: NONE

GIRDER CAMBER NOTES:

1. The calculated camber includes the effect of the initial prestress force and the weight of the girder after removal from the bed. The calculated camber value has been multiplied by creep factor to approximate the effect of camber growth and concrete creep. Positive values shown for initial camber indicate a net upward deflection. Maximum camber immediately prior to erection of girders shall not exceed the calculated camber by more than 1 inch. Girders with cambers exceeding the maximum camber will not be accepted.
2. The dead load deflection includes the combined effects of the weight of slab, drop panels, and diaphragms.
3. Contractor shall camber the deck form work as required to account for the calculated dead load deflection in order to provide the specified finish deck elevations.
4. All cambers and deflections are in inches.
5. Working force is designated as P_e .



TYPICAL END ELEVATION
Not to Scale



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TYPE II PRESTRESSED GIRDER

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S4.3 OF 5 SHEETS


DESIGNED BY	DATE
CHECKED BY	
NOTED BY	
QUANTITIES BY	
NO.	

DRAWING NAME: 15\PROJECTS\15-01\KAIPAPAU BRIDGE\15-01\REVISED STRUCT\15-01\15-01\15-01.DWG PLOT TIME: 06-09-21 3:16 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	92	161



Notes:

1. *Sawteeth Shown by Hatched Area* 
2. *Strands Not Shown*
3. *Type II Girders (G-10 and G-11)*
4. *For G Type Reinforcing see Sht. S4.5*

END ELEVATION

Scale: 1" = 1'-0"

A


S4.3 S4.4

TYPICAL SECTION

Scale: 1" = 1'-0"

B

S4.3 | S4.4



Notes:



1. Contractor shall field bend rebars and strands as shown on sheet S6.6.
2. See S4.3 for additional reinforcing details.

TYPE II GIRDER END DETAIL

Scale: 1" = 1'-0"

1
S43 | S44

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TYPE II GIRDER SECTIONS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. **S4.4** OF **5** SHEETS



ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY _____	_____
	TRACED BY _____	_____
	DESIGNED BY _____	_____
	QUANTITIES BY _____	_____
	CHECKED BY _____	_____
No. _____		

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S401.DWG PLOT TIME: 06-09-21, 3:17 PM)

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	93	161

PRESTRESSED GIRDER NOTES:

1. Prestressed steel shall be 7-wire 0.6-inch diameter ASTM A416 Grade 270 low-relaxation strand.
2. See framing plans for location of diaphragms, ϕ bearing to ϕ bearing, and girder spacing.
3. Strand pattern shall be symmetrical about the longitudinal ϕ of the girder.
4. Strand release sequence shall not induce any lateral deflection of the girder.
5. Contractor shall submit shop drawings indicating proposed strand pattern, holes, inserts, releasing sequence, reinforcing details and hold down device details to the Engineer prior to fabrication.
6. The Contractor shall incorporate all holes, inserts, and other embedded items required in girders during fabrication of the girders.
7. Lifting devices shall be placed as close as possible to the center line bearing of the girder. Details and locations of lifting devices shall be submitted to the Engineer for approval. Such approval does not relieve the Contractor of his responsibilities if the girder is damaged due to failure of lifting device.
8. Prior to casting girder Contractor shall field verify span lengths at each abutment.
9. Contractor shall inspect all lifting devices for damage prior to delivery and immediately before installation.
10. Contractor shall submit alternative method to lift girder if lifting devices are damaged for review and acceptance.
11. Roughen top surface of girder to 1/4" min. amplitude.
12. The compressive strength of the girder at strand release shall be at least 8,500 psi.
13. See sheets S4.1 through S4.4 for rebar ϕ strand extensions.
14. Contractor may adjust locations of holes ϕ inserts with the approval of the Engineer.
15. The concrete shall pass a charge of less than 1000 Coulombs at 90-days from casting as determined by AASHTO T277. Concrete test specimens shall be cured under the same conditions as the Precast Girders.



SAWTEETH DETAIL
Not to Scale

1
S4.5 S4.5

ORIGINAL PLAN	DESIGNED BY	CHECKED BY	DATE
NOTE BOOK	DESIGNED BY	CHECKED BY	
No.			

DRAWING NAME: 15\PROJECTS\15-ACTIVE FILES\13-01-KAIPAPAU BRIDGE\15-REVISED STRUCT\15-051221\KCB-S401.DWG PLOT TIME: 08-09-21 3:17 PM



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


**PRESTRESSED GIRDER NOTES
AND DETAIL**

**KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)**

Scale: As Noted Date: February 2021



SHEET No. S4.5 OF 5 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	94	161



Note:
Deck, Concrete Barrier, Aesthetic Railing
and Precast Girder Reinforcing are
not shown for clarity.

DIAPHRAGM "A" ELEVATION
Scale: 1" = 1'-0"



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

DIAPHRAGM ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S5.1 OF 3 SHEETS

Technical drawing of a bridge cross-section, showing the layout of girders, travel lane, shoulder, sidewalk, and various dimensions and reinforcement details.

Dimensions and Layout:

- Travel Lane:** 12'-0"
- Shoulder:** 8'-6"
- Sidewalk:** 5'-0"
- Concrete Barrier:** 1'-6"
- Aesthetic Railing:** 1'-8"
- Clearance:** 1'-6"

Reinforcement and Details:

- Bridge Deck:** 2-#6 Cont. (Continuous), #6 EF (Ends).
- Girders:** Girder G-6, Girder G-7, Girder G-8, Girder G-9, Girder G-10, Girder G-11.
- Reinforcement:** #4 Typ. (Typical), #8 x 4'-6" (At Girders 2-9), #8 x 4'-0" (At Girder 10), #8 x 2'-6" (At Girder 11).
- Clearance:** 2" Clr., typ. (Typical).
- Slope:** Slope 1.5%.
- Section Markers:** A S5.1AS5.2, C S5.1AS5.2, 1 S5.1AS5.2.

Other Labels:

- Maui (Left side)
- Makai (Right side)
- Bridge = Kamehameha Highway

Technical drawing of a bridge cross-section, showing the layout of girders, deck, and various dimensions. The drawing is oriented with "Mauka" (left) and "Makai" (right) directions.

Dimensions and Layout:

- Travel Lane:** 12'-0"
- Shoulder:** 8'-6"
- Sidewalk:** 5'-0"
- Concrete Barrier:** 1'-6"
- Aesthetic Railing:** 1'-8"
- Clearance:** 1'-6"
- Girder Spacing (from left to right):**
 - Girder G-6 to G-7: 5'-6"
 - Girder G-7 to G-8: 5'-6"
 - Girder G-8 to G-9: 5'-6"
 - Girder G-9 to G-10: 5'-0"
 - Girder G-10 to G-11: 3'-4 3/8"
- Other Dimensions:**
 - 1'-7" (between G-6 and G-7)
 - 1'-6" (between G-8 and G-9)

Structural Details and Reinforcement:

- Deck:** 2-#6 Cont. (top), #6 EF (bottom), Slope 1.5%.
- Concrete Barrier:** #8 x 3'-0"
- Aesthetic Railing:** #6 E.F., S5.1AS5.2
- Girder Reinforcement:**
 - Girder G-9: #6 E.F., #8 x 4'-0" (At Girder 10)
 - Girder G-10: #8 x 2'-6"
 - Girder G-11: #8 x 2'-6"
- Other Details:**
 - 3" Clr. typ. (typical clearance)
 - #4 Typ. (typical reinforcement)
 - S5.1AS5.2 (structural steel specification)


Professional Engineer Seal: DENNIS K. MITSUNO, LICENSED PROFESSIONAL ENGINEER.

Deck, Concrete Barrier, Aesthetic Railing and Precast Girder Reinforcing are not shown for clarity.

SCALE: 1"= 1'-0"

APPROVED:  MAY 24 2016


Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only) DATE



ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY _____	BY _____
	TRACED BY _____	BY _____
	DESIGNED BY _____	BY _____
	QUANTITIES BY _____	BY _____
No. _____	CHECKED BY _____	BY _____


DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\1_051221\KSB-S501.DWG PLOT TIME: 05-13-21, 8:30 AM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	96	161




#8 X 4'-6" Through Girders
Epoxy Into Hole (Hole Dia. is 1/8" Larger than Dia. of Bar)
After Bars are in Place, Typ.
(Inserts @ G-1 & G-10)

DIAPHRAGM SECTION A
Scale: 1" = 1'-0"




#8 X 4'-6" Through Girders
Epoxy Into Hole (Hole Dia. is 1/8" Larger than Dia. of Bar)
After Bars are in Place, Typ.

DIAPHRAGM SECTION AT ELECTRICAL DUCT B
Scale: 1" = 1'-0"






TYPICAL INSERT DETAIL 1
Scale: 1 1/2" = 1'-0"



DIAPHRAGM "B" SECTION C
Scale: 1" = 1'-0"

GRAPHIC SCALE:



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

**DIAPHRAGM
SECTIONS AND DETAIL**

**KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)**


Scale: As Noted Date: February 2021

SHEET No. S52 OF 3 SHEETS

DESIGNED BY	DATE
DRAWN BY	
CHECKED BY	
NOTED BY	
QUANTITIES BY	
ORIGINAL PLAN	
NO.	

DRAWING NAME: I:\PROJECTS\13-01-KAIPAPAU BRIDGE\13-01-REVISED-STRUCT\13-01-22\KCB-S501.DWG PLOT TIME: 06-09-21 3:20 PM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	98	161





ABUTMENT NO. 2 PLAN
Scale: 1/4" = 1'-0"

Note:

- Balance of W16 cradles are not shown for clarity, See Sheets S11.1 and S11.1A for details.
- Contractor shall submit locations of W16 Cradles. Contractor shall coordinate W16 Cradle locations with precast girder manufacturer, deck reinforcing, wing wall reinforcing and abutment reinforcing.
- 4" Diameter perforated drain pipe shall be included in the cost for structural backfill.



APPROVED:  MAY 24 2021
Manager and Chief Engineer, BWS (for work affecting BWS facilities State R/W & BWS easements only)


THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

MITSUNAGA & ASSOCIATES, INC. 4/30/22

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


ABUTMENT NO. 2 PLAN

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021


SHEET No. S6.2 OF 14 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	99	161





Note:
Add CFCW at all joints below finish grade.

ABUTMENT NO. 1 ELEVATION A
Scale: 3/8" = 1'-0" S6.3 S6.3



SURVEY PLOTTED BY	DATE
DRAWN BY	
DESIGNED BY	
QUANTITIES BY	
CHECKED BY	
ORIGINAL PLAN	No.
NOTE BOOK	

APPROVED:  MAY 2 4 2021
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


ABUTMENT NO. 1 ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S6.3 OF 14 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	100	161




ABUTMENT NO. 1 BACK ELEVATION A
Scale: 3/8" = 1'-0" S6.3A S6.3A



ORIGINAL PLAN	DATE
NO. 1	
DESIGNED BY	
CHECKED BY	
DATE	

APPROVED: *[Signature]* MAY 24 2021
 Manager and Chief Engineer, BWS
 (for work affecting BWS facilities
 State R/W & BWS easements only)



THIS WORK WAS PREPARED BY
 ME OR UNDER MY SUPERVISION
[Signature] 4/30/22
 SIGNATURE LIC. EXPIRATION
 MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
 DEPARTMENT OF TRANSPORTATION
 HIGHWAYS DIVISION


**ABUTMENT NO. 1
 BACK ELEVATION**

**KAMEHAMEHA HIGHWAY
 Kaipapau Stream Bridge Replacement
 Federal Aid Proj. No. BR-083-1(48)**

Scale: As Noted Date: February 2021

SHEET No. **S6.3A** OF **14** SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	102	161



ABUTMENT NO. 2 BACK ELEVATION

Scale: $3/8" = 1'-0"$

A
S6.4A S6.4A

Note:
Add CFCW at all joints below
finish grade.

GRAPHIC SCALE:


2 0 2 4FT

SCALE: $\frac{3}{8}" = 1'-0"$

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY _____	_____
	TRACED BY _____	_____
	DESIGNED BY _____	_____
	QUANTITIES BY _____	_____
No. _____	CHECKED BY _____	_____

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$.051221\KSB-S603.DWG PLOT TIME: 05-13-21, 8:34 AM)

APPROVED:  MAY 24 2022
 _____ DATE
 Manager and Chief Engineer, BWS
 (for work affecting BWS facilities
 State R/W & BWS easements only)



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

4/30/22

SIGNATURE LIC. EXPIRATION

MITSunAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


ABUTMENT NO. 2
BACK ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-II(48)

Scale: As Noted Date: February 2021

SHEET No. **S6.4A** OF **14** SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	103	161




Notes:



1. Deck reinforcing not shown for clarity.
2. See Sheets S7.* for wing wall details.
3. Coordinate stirrup spacing with #6  deck reinforcing.

ELEVATION
(Abutment No. 1 Shown)

Scale: 1" = 1'-0"



GRAPHIC SCALE:



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

 4/30/22

SIGNATURE LIC. EXPIRATION

MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ABUTMENT ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted

Date: February 2021

SHEET No. *S6.5* OF *14* SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY _____	" _____
	TRACED BY _____	" _____
	DESIGNED BY _____	" _____
	QUANTITIES BY _____	" _____
No. _____	CHECKED BY _____	" _____

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S605.DWG PLOT TIME: 06-09-21, 3:22 PM)


PLOT TIME: 06-09-21, 3:22 PM)

BRIDGE\\\$\$ _REVISED_STRUCT\\\$\$ _051221\\KSB-S605.DWG

T: \PROJECTS\1-ACTIVE FILES\913-01_KAIPAPA\


100

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	104	161




- Notes:**
- Deck reinforcing not shown for clarity.
 - See Sheets S7.* for wing wall details.
 - Coordinate stirrup spacing with #6 deck reinforcing.
 - See sheets S11.1 and S11.1A for W16 Cradle details.

ELEVATION
(Abutment No. 1 Shown)
 Scale: 1" = 1'-0"



APPROVED: *[Signature]* MAY 24 2021
 Manager and Chief Engineer, BWS
 (for work affecting BWS facilities
 State R/W & BWS easements only)



STATE OF HAWAII
 DEPARTMENT OF TRANSPORTATION
 HIGHWAYS DIVISION

ABUTMENT ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S6.5A OF 14 SHEETS

SURVEY PLOTTED BY	DATE
DRAWN BY	
DESIGNED BY	
CHECKED BY	
NOTE BOOK	
No.	

DRAWING NAME: T:\PROJECTS\ACTIVE FILES\011-01 KAIPAPAU BRIDGE\14 REVISED STRUCT\14-05-2021\ASB-5605.DWG PLOT TIME: 05-13-21 8:14 AM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	105	161




SECTION AT GIRDER
Scale: 1" = 1'-0"

A

S6.3 | S6.6



S6.4, S6.5A



SECTION BETWEEN GIRDERS $\frac{B}{56.3 \mid 56.6}$
Scale: 1" = 1'-0"

- Notes:
1. Apply bonding agent such as Dural prep A.C., Armatec 110 Epocem or approved equal to Vertical deck deck joint prior to pouring deck section over end beam.
 2. See Sheet S6.8 for concrete bearing details.
 3. #5 tie at middepth of drilled shaft cap beam is not required at drilled shaft spirals.
 4. See sheet S8.1 and S8.2 for drilled shafts.

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ABUTMENT SECTIONS


KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-I(48)

Scale: As Noted Date: February 2021

SHEET No. *S6.6* OF *14* SHEETS


DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S606.DWG PLOT TIME: 06-09-21, 3:23 PM)

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	106	161



SECTION AT GIRDER FLANGE 

Scale: 1" = 1'-0"





SECTION AT DRILLED SHAFT
CAP BEAM CONSTRUCTION JOINT

Scale: 1" = 1'-0"

B
S6.5A S6.7

- Notes:
1. Apply bonding agent such as Dural prep A.C., Arimatec 110 Epocem or approved equal to Vertical deck deck joint prior to pouring deck section over end beam.
 2. See Sheet S6.8 for concrete bearing details.
 3. #5 tie at middepth of drilled shaft cap beam is not required at drilled shaft spirals.
 4. See sheet S8.1 and S8.2 for drilled shafts.

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ABUTMENT SECTIONS


KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. *S6.7* OF *14* SHEETS

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S606.DWG PLOT TIME: 06-09-21, 3:24 PM)

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	107	161



Notes:

1. Apply bonding agent such as Dural Prep A.C., Arimatec 110 Epocem or approved equal to Vertical deck joint prior to pouring deck section over end beam.
2. For balance of reinforcing See Section B/S6.6.
3. For upper corbel reinforcing and approach slab details see sht. S9.1.



**SECTION AT
ELECTRICAL DUCTLINE**

Scale: 1" = 1'-0"

S6.3A, S6.4, S6.4A, S6.5

A
S6.3 S6.7A

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ABUTMENT SECTION


**KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)**

Scale: As Noted


Date: February 2021

SHEET No. S6.7A OF 14 SHEETS



FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	108	161



REAR ELEVATION (MAKAI SIDE)
Scale: 1" = 1'-0"



REBAR COUPLER DETAIL
Scale: 1" = 1'-0"



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ABUTMENT SECTION AND DETAIL

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S6.7B OF 14 SHEETS


DESIGNED BY	DATE
DRAWN BY	
CHECKED BY	
NOTED BY	
QUANTITIES BY	
NO.	

DRAWING NAME: I:\PROJECTS\13-01-KAIPAPAU BRIDGE\13-01-REVISED STRUCT\13-01-22\KCB-S606.DWG PLOT TIME: 06-09-21, 3:25 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	109	161

Legend:



- Structure Backfill
- Filter Material
- Impervious Material



BACKFILL DETAIL 1
Scale: 1" = 1'-0" S6.7C S6.7C

ORIGINAL PLAN	DRAWN BY	DATE
NOTE BOOK	DESIGNED BY	" "
No.	QUANTITIES BY	" "
	CHECKED BY	" "

DRAWING NAME: I:\PROJECTS\1-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\1-REVISED STRUCT\1-051221\KSB-S006.DWG PLOT TIME: 06-09-21, 3:26 PM



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


BACKFILL DETAIL

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021



SHEET No. S6.7C OF 14 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	111	161



WING WALL NO. 1 ELEVATION
Scale: 1/2" = 1'-0"

ORIGINAL PLAN	DESIGNED BY	DATE
NOTE BOOK	DRAWN BY	
No.	CHECKED BY	



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION
SIGNATURE: [Signature] LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


WING WALL NO. 1
ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S7J OF 11 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	112	161





WING WALL NO. 2 ELEVATION
Scale: 1/2" = 1'-0"

A
S6.2 | S7.2

ORIGINAL PLAN	DESIGNED BY	DATE
NOTE BOOK	DESIGNED BY	
No.	CHECKED BY	

DRAWING NAME: I:\PROJECTS\1-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\11-REVISED-STRUCT\11-051221\KCB-S701.DWG PLOT TIME: 06-09-21 3:28 PM



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


WING WALL NO. 2
ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S7.2 OF 11 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	113	161






Note:
W16 Cradle is not shown for clarity.

WING WALL NO. 3 ELEVATION
Scale: 1/2" = 1'-0" A
S6.1 | S7.3

ORIGINAL PLAN	DATE
SURVEY PLOTTED BY	
DRAWN BY	
DESIGNED BY	
QUANTITIES BY	
CHECKED BY	
NOTE BOOK	
No.	

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\013-01 KAIPAPAU BRIDGE\REVISED STRUCT\13 051221\KSP-S7.01.DWG PLOT TIME: 05-20-21 11:30 AM

APPROVED:  MAY 24 2021
Manager and Chief Engineer, BWS (for work affecting BWS facilities State R/W & BWS easements only) DATE



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


WING WALL NO. 3
ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S7.3 OF 11 SHEETS


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	114	161



RETURN WALL SECTION A
Scale: 1" = 1'-0"

Notes:


1. Wing Wall Reinforcement not shown for Clarity.
2. See D/S7.10 for Additional Information at 1'-10" Diameter Hole.




SECTION B
Scale: 1" = 1'-0"

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	

DRAWING NAME: I:\PROJECTS\1-ACTIVE FILES\513-01 KAIPAPAU BRIDGE\1-REVISED STRUCT\513-01 KAIPAPAU BRIDGE.dwg PLOT TIME: 05-20-21 11:31 AM

APPROVED: 
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)
MAY 24 2021
DATE

GRAPHIC SCALE:
2 1 0 2 4
SCALE: 1/2" = 1'-0"



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


RETURN WALL SECTIONS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S7.3A OF 11 SHEETS


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	115	161



WING WALL NO. 4 ELEVATION
 Scale: 3/4" = 1'-0"



ORIGINAL PLAN	DATE
NO.	

DRAWING NAME: T:\PROJECTS\1-ALUKE FILES\013-01 KAIPAPAU BRIDGE\REVISED STRUCT\4 051221\159-5701 DWG PLOT TIME: 05-20-21, 11:32 AM

APPROVED:  MAY 24 2021
 Manager and Chief Engineer, BWS
 (for work affecting BWS facilities
 State R/W & BWS easements only)

GRAPHIC SCALE:

 SCALE: 3/4" = 1'-0"


 THIS WORK WAS PREPARED BY
 ME OR UNDER MY SUPERVISION

 SIGNATURE DATE: 4/30/22
 MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


WING WALL NO. 4 ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021


SHEET No. S7.4 OF 11 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	117	161



WING WALL NO. 1 SECTION 

Scale: 3/4" = 1'-0"





WING WALL NO. 1 SECTION 

Scale: 3/4" = 1'-0"

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY _____	" _____
	TRACED BY _____	" _____
	DESIGNED BY _____	" _____
	QUANTITIES BY _____	" _____
No. _____	CHECKED BY _____	" _____

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S701.DWG PLOT TIME: 06-09-21, 3:29 PM)

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION



WING WALL NO. 1 SECTIONS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)



Scale: As Noted Date: February 2021

SHEET No. *576* OF *11* SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	120	161



GRAPHIC SCALE:



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

WING WALL SECTIONS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S7.9 OF 11 SHEETS


ORIGINAL PLAN	DESIGNED BY	DATE
NOTE BOOK	DESIGNED BY	
No.	QUANTITIES BY	
	CHECKED BY	

DRAWING NAME: I:\PROJECTS\1-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\1-REVISED STRUCT\1-051221\KCB-S701.DWG PLOT TIME: 06-09-21 3:31 PM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	121	161




PLAN SECTION A
Scale: 1" = 1'-0"
S7.3, S7.8, S7.9



TYPICAL POST DETAIL AT RETAINING WALL B
Scale: 1" = 1'-0"
S7.3, S7.8, S7.9




TYPICAL CHAINLINK POST AT END OF WALL - PLAN C
Scale: 1" = 1'-0"
S7.3, S7.8, S7.9




Note:
Typical wall reinf. not shown for clarity.

TYPICAL CHAINLINK POST AT END OF WALL - ELEVATION D
Scale: 1" = 1'-0"
S7.3, S7.8, S7.9



W16 OR W8 AT WING WALLS D
Scale: 1" = 1'-0"
S7.3, S7.3A, S7.4, S7.10

GRAPHIC SCALE:
1 0 1 2
SCALE: 1" = 1'-0"



APPROVED: *[Signature]* MAY 24 2021
DATE
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
TYPICAL DETAILS
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. S7.10 OF 11 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DESIGNED BY	
No.	CHECKED BY	

DRAWING NAME: I:\PROJECTS\ACTIVE FILES\13-01-KAIPAPAU BRIDGE\13-051221\KCB-SS01.DWG PLOT TIME: 06-09-21 3:32 PM

DRILLED SHAFT NOTES:

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	122	161

1. All excavation and drilling operations for foundations shall be monitored by the Engineer.

2. Bottom of drilled shaft cap beam and drilled shaft tip elevations shall be verified by the Engineer prior to placing reinforcement and concrete.

3. Concrete shall be placed in the shaft immediately after placing the reinforcing steel and shall not be placed without approval of the Engineer.

4. Drilled shaft tip elevations shown on this sheet are the minimum depths to be constructed and shall be used to estimate quantities for bidding. The actual tip elevation shall be determined by the Engineer.

5. Construction of drilled shafts shall be done in such a manner and sequence to prevent collapse of drilled shafts due to premature loading of poured drilled shafts before its 28-day concrete strength and other mishaps that may reduce its capacity.

6. Drilling of adjacent shafts shall be staggered in such a manner that the shaft concrete shall have cured a minimum of 24 hours prior to drilling adjacent shafts.

7. Reinforcement:

A. Lap splice length for #10 Cont. shall be 6'-6". No lap splices are allowed in the upper half of the drilled shaft.

B. Lap splice length for #6 Spiral shall be 3'-8".

C. Stagger splice points so that not more than 50% of the bars are spliced at any section normal to axis of the member.

D. Lapped splices shall have a minimum of 2'-0" vertically between ends of splice points.

8. Concrete for drilled shaft shall have a compressive strength of 4500 psi at 28-days of age.

9. Unless noted otherwise, concrete for drilled shafts shall be placed by pumping through a solid tremie pipe. A water reducing and set retarding admixture may be used in all drilled shaft concrete. Proposed admixture shall be tested and certified in the mix design and approved by the Engineer.

10. Concrete placement shall continue after the shaft is full and until good quality concrete is evident at the least 4 feet above top of the shaft and/or drilled shaft extension.

11. Vibration or agitation of drilled shaft concrete during placement is prohibited.

12. Plastic spacers or spacers made with accepted materials shall be used to maintain proper position and clearances to reinforcing bars.

13. The Contractor shall record actual volume of drilled shaft concrete placed and compare with predicted and/or theoretical volumes.

14. The center of the drilled shaft concrete and reinforcing bars shall not vary horizontally by more than 3 inches from the location shown on the plans. The vertical alignment of the drilled shaft shall not vary by more than quarter (1/4) inch per foot of depth.


15. An instrumented load test shall be conducted on the drilled shaft load test shaft. The drilled shaft load test shaft shall be located in the vicinity of Abutment No. 2, as shown on sheet S1.1 and S1.2 and shall be a minimum length of 109 feet below the ground surface. The drilled shaft load test shaft shall be reinforced as shown. A bi-directional axial load test shall be conducted using an expandable base load cell (Osterberg load cell).

The drilled shaft load test should be performed in general accordance with the quick load test method of ASTM Test Designation D 1143 except as modified in specifications. The drilled test shaft shall be loaded to failure to evaluate the ultimate side shear resistance of the shaft.


16. The drilled shaft load test shaft shall be instrumented with a minimum of forty-two (42) embedment strain gages as shown on sheet S8.3. A load cell capable of applying a test load of at least 3,600 kips in each direction shall be used. The instrumented load test shall be completed before construction of any production drilled shafts. The Contractor shall allow seven (7) working days after completion of the load test before any estimated drilled shaft tip elevations will be provided for production drilled shafts.
17. Crosshole Sonic Logging (CSL) nondestructive integrity testing shall be performed on every production shaft, trial shaft, and at the load test shaft shown on S1.1 and S1.2 and on sheets S8.2 and S8.3. Shafts indicating irregular CSL readings may be subject to additional testing, and remedial repairs or drilled shaft replacement.
18. After completion of the CSL tests and final acceptance of the drilled shaft, remove portion of CSL test access tubes within footing and completely fill tubes with non-metallic, non-shrink, non-gaseous cementitious grout of equal strength as the drilled shaft prior to footing reinforcing and concrete placement. See Specifications Section 511.

DRILLED SHAFT TABLE			
Location	Drilled Shaft Type (in Inches)	Length (in Feet)	Estimated Tip Elevation (in Feet MSL)
Abutment No. 1	48	82	(-) 79.6
Abutment No. 2	48	68	(-) 64.5
Trial Shaft	48	100	--

AXIAL LOADS OF DRILLED SHAFT					
Location		Strength Limit State (Kips)		Extreme Limit State (Kips)	
		Demand	Capacity	Demand	Capacity
Abutment No. 1	Axial Compression	883	885	830	1960
Abutment No. 2	Axial Compression	924	925	878	2060




FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	123	161



SECTION AT DRILLED SHAFT
FOR ABUTMENT

Scale: 1" = 1'-0"





NOTES:

1. *The Contractor shall refer to the Special Provisions Section 511 "DRILLED SHAFT".*
2. *Spirals may be discontinuous at drilled shaft cap beam reinforcement to allow for placing drilled shaft cap beam reinforcement. Each end of the spiral shall have 1 1/2 extra turns.*
3. *Provide template or mock-up to ensure no interference between vertical #10 bars and horizontal rebars in shaft cap beams.*

TYPICAL DRILLED SHAFT ELEVATION
Not to scale

GRAPHIC SCALE:



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

DRILLED SHAFT SECTION
AND ELEVATION


KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S8.2 OF 3 SHEETS


DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S801.DWG PLOT TIME: 06-09-21, 3:32 PM)

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	125	161




TYPICAL APPROACH SLAB SECTION

Scale: 3/4" = 1'-0"



SECTION

Scale: $3/4" = 1'-0"$ S9.1 S9.1





SLEEPER SLAB AT CONCRETE BARRIER

Scale: $3/4" = 1'-0"$

S6.1, S6.2, S9.2

GRAPHIC SCALE:



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION



4/30/22

SIGNATURE LIC. EXPIRATION

MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

APPROACH SLAB SECTIONS


KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021


SHEET No. *S9.1* OF *4* SHEETS

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S901.DWG PLOT TIME: 06-09-21, 3:34 PM)


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	126	161



APPROACH SLAB SECTION AT CLOSURE
Scale: 3/4" = 1'-0"
A
S9.1A S9.1A



SLEEPER SLAB SECTION AT CLOSURE
Scale: 3/4" = 1'-0"
B
S9.1A S9.1A



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
[Signature]
SIGNATURE DATE: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SLAB SECTIONS

KAMEHAMEHA HIGHWAY
Kaipapua Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021


SHEET No. S9.1A OF 4 SHEETS

GRAPHIC SCALE:
1 0 1 2 FT
SCALE: 3/4" = 1'-0"

ORIGINAL PLAN	DATE
DESIGNED BY	"
NOTED BY	"
CHECKED BY	"

DRAWING NAME: 15\PROJECTS\15-01\KAIPAPUA BRIDGE\15-01\REVISED STRUCT\15-01\15-01\15-01.DWG PLOT TIME: 06-09-21 3:34 PM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	127	161




CONCRETE BARRIER WALL
Scale: $3/4" = 1'-0"$

- Notes:

1. *At Shaped Concrete at Quadguard Transition, see Civil drawings for layout.*
2. *Provide #5 @9" x  Horiz with minimum 6 #5 x  Vertical*
3. *Top of barrier at Quadguard transition.*



SECTION B
Scale: $3/4" = 1'-0"$ S9.2 | S9.2



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

 4/30/22

SIGNATURE LIC. EXPIRATION
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

CONCRETE BARRIER WALL

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. *S9.2* OF *4* SHEETS

GRAPHIC SCALE:




FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	128	161



Notes:

- * Provide #5  Horiz each end of each layer.
- F Continuous Flashing
Compound Waterproofing



CONCRETE BARRIER WALL

Scale: 3/4" = 1'-0" S3.1 S9.2A

Scale: $3/4" = 1'-0"$

SECTION

Scale: $3/4" = 1'-0"$

Scale: $3/4" = 1'-0"$ S9.2A | S9.2A

Notes:

1. *At Shaped Concrete at Quadguard Transition, see Civil drawings for layout.*
2. *Provide #5 @9" x  Horiz with minimum 6 #5 x  Vertical*
3. *Top of barrier at Quadguard transition.*

GRAPHIC SCALE:



SCALE: 3/4" = 1'-0"

CONCRETE BARRIER WALL

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted

Date: February 2021

SHEET No. *S9.2A* OF 4 SHEETS



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

4/30/22


SIGNATURE LIC. EXPIRATION

MITSUNAGA & ASSOCIATES, INC.

ORIGINAL FILM	SURVEY PLOTTED BY _____ DATE _____
	DRAWN BY _____ TRACED BY _____ DESIGNED BY _____ QUANTITIES BY _____ CHECKED BY _____
No. _____	_____

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$\$_051221\KSB-S902A.DWG PLOT TIME: 06-09-21, 3:36 PM)

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	129	161



Name of Bridge

Date of Year Built


NOTES:

1. Exact details and spacing of letter and figures and location shall be as directed by the Engineer. Gothic letters and figures approximating the dimensions shown will be acceptable if approved by the Engineer.
2. Name & date shall be place on the trailing (exit) end post on each side of bridge.
3. Unless otherwise directed by the Engineer,
The name of the bridge shall be "KA'IPAPAU STREAM BRIDGE".
The year shall be the year at completion.

TYPICAL DETAIL OF LETTERS AND FIGURES

BRIDGE IDENTIFICATION DETAIL


Scale: 3" = 1'-0"




ORIGINAL PLAN	DESIGNED BY	DATE
NOTE BOOK	DRAWN BY	"
No.	CHECKED BY	"

DRAWING NAME: I:\PROJECTS\1-ACTIVE FILES\913-01-KAIPAPAU BRIDGE\1-REVISED_STRUCT\1-051221\KSB-S1001 SW FIXED.DWG PLOT TIME: 08-09-21 3:37 PM

GRAPHIC SCALE:




SCALE: 3"= 1'-0"




THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
**BRIDGE IDENTIFICATION
DETAIL**
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. S101 OF 7 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	130	161




JOINT DETAIL 1
Scale: 1" = 1'-0" S10.2 S10.2



JOINT DETAIL 2
Scale: 1" = 1'-0" S10.2 S10.2

Note:
Align joints in concrete barrier
with 1/2" joints in Aesthetic Railing.

GRAPHIC SCALE:



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: [Signature] LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


TYPICAL JOINT DETAILS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S10.2 OF 7 SHEETS



FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	131	161



TYPICAL AESTHETIC BRIDGE RAILING END PANEL ELEVATION A
Scale: 1" = 1'-0" S10.3 S10.3



TYPICAL AESTHETIC BRIDGE RAILING END PANEL PLAN / SECTION A
Scale: 1" = 1'-0" S10.4 S10.4




STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
**RAILING ELEVATION
AND PLAN AT END PANEL**
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. S10.3 OF 7 SHEETS


ORIGINAL PLAN	DATE
DESIGNED BY	
NOTED BY	
CHECKED BY	

DRAWING NAME: 15\PROJECTS\15-ACTIVE FILES\13-01-KAIPAPAU BRIDGE\15-REVISED STRUCT\15-051221\KCB-S1003 SW FIXED.DWG PLOT TIME: 06-09-21, 3:38 PM



FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	132	161



AESTHETIC BRIDGE RAILING END PANEL ELEVATION AT DRIVEWAY A
Scale: 1" = 1'-0" S10.3 S10.3



AESTHETIC BRIDGE RAILING END PANEL PLAN / SECTION AT DRIVEWAY A
Scale: 1" = 1'-0" S10.4 S10.4



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

**RAILING ELEVATION AND
PLAN AT DRIVEWAY**

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. **S10.4** OF 7 SHEETS


ORIGINAL PLAN	DATE
NOTE BOOK	
QUANTITIES BY	
CHECKED BY	

DRAWING NAME: I:\PROJECTS\1-01-CAIPAPAU BRIDGE\1-01-CAIPAPAU BRIDGE\1-01-CAIPAPAU BRIDGE\1-01-CAIPAPAU BRIDGE.dwg PLOT TIME: 06-09-21, 3:39 PM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	135	161



ELEVATION A
Scale: 3" = 1'-0" S10.7 S10.7




ANCHOR PLATE DETAIL 1
Scale: 3" = 1'-0" S10.6 S10.6



ELEVATION
TYPICAL TUBE SPLICE DETAIL 2
Not to Scale S10.7 S10.7

REFLECTED SOFFIT 3
S10.7 S10.7

METAL RAILING ON AESTHETIC BRIDGE RAILING



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

METAL BIKE RAILING DETAILS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021


SHEET No. S10.7 OF 7 SHEETS

100

DESIGNED BY	DATE
DRAWN BY	
CHECKED BY	
NOTED BY	
QUANTITIES BY	
ORIGINAL PLAN	
NO.	

DRAWING NAME: 15\PROJECTS\15-ACTIVE FILES\13-01-KAIPAPAU BRIDGE\15-REVISED STRUCT\15-051221\KCB-S1003-SW FIXED.DWG PLOT TIME: 06-09-21, 3:41 PM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	136	161



Notes:

- Contractor shall submit locations of W16 Cradles. Contractor shall coordinate W16 Cradle locations with precast girder manufacturer, deck reinforcing abutment reinforcing and wing wall reinforcing.
- Concrete is not Scored within First and Last 2'-0" of Curtain Wall.


CURTAIN WALL ELEVATION
Scale: 3/4" = 1'-0"



SECTION C
Scale: 1" = 1'-0"

SECTION D
Scale: 1" = 1'-0"


SECTION E
Scale: 1" = 1'-0"




Notes:

- All reinforcing steel in W16 cradle shall be ASTM A1035, unless otherwise noted.
- Deck, railing and girder reinforcing are not shown for clarity.
- For cradle at wing wall, see B/S11.1A.
- For cradle at abutment, see B/S11.1A similar.
- Place 1/4" Neoprene Between W16 and S.S. Plate.
- Place 1/4" Neoprene Between W16 and Cradle.

W16 CRADLE SECTION
Scale: 1 1/2" = 1'-0"



APPROVED: *[Signature]* MAY 24 2021
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


W16 CRADLE AND CURTAIN WALL

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021
SHEET No. **S11.1** OF **5** SHEETS


DATE	
DESIGNED BY	
CHECKED BY	
NOTED BY	
ORIGINAL PLAN	
NO.	

DRAWING NAME: KAIPAPAU STREAM BRIDGE REPLACEMENT PROJECT NO. BR-083-1(48) SHEET NO. S11.1 OF 5 SHEETS

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	137	161





W16 CURTAIN WALL SECTION
Scale: 1 1/2" = 1'-0"




W16 CRADLE AT WING WALL
Scale: 1 1/2" = 1'-0"

- Notes:
1. All reinforcing steel in W16 cradle shall be ASTM A1035, unless otherwise noted.
 2. Deck, railing and girder reinforcing are not shown for clarity.
 3. For cradle at wing wall, see B/S11.1A.
 4. For cradle at abutment, see B/S11.1A similar.
 5. Place 1/4" Neoprene Between W16 and S.S. Plate.
 6. Place 1/4" Neoprene Between W16 and Cradle.



APPROVED:  MAY 24 2021
Manager and Chief Engineer, BWS
(for work affecting BWS facilities
State R/W & BWS easements only)

DENNIS K. MITSUNAGA
LICENSED PROFESSIONAL ENGINEER
No. 2422-S
HAWAII, U.S.A.
THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

4/30/22
SIGNATURE MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

**W16 CURTAIN WALL SECTION
AND CRADLE AT WING WALL**

**KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)**


Scale: As Noted Date: February 2021

SHEET No. S11.1A OF 5 SHEETS


SURVEY PLOTTED BY	DATE
DRAWN BY	
DESIGNED BY	
CHECKED BY	
ORIGINAL PLAN	
NOTE BOOK	
No.	

DRAWING NAME: T:\PROJECTS\1-ACTIVE FILES\313-01 KAPAPAU BRIDGE\11 REVISED_STRUCT\11-KSP-S11.1.DWG PLOT TIME: 05-20-21 11:35 AM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	138	161



SECTION A
Scale: 3/4" = 1'-0"




SECTION C
Scale: 3/4" = 1'-0"



SECTION B
Scale: 3/4" = 1'-0"

GRAPHIC SCALE:
1 0 1 2FT
SCALE: 3/4" = 1'-0"

APPROVED: *[Signature]* MAY 2 4 2021
Manager and Chief Engineer, BWS (for work affecting BWS facilities State R/W & BWS easements only)




THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION
4/30/22
SIGNATURE MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
REACTION BLOCK AT WING WALL NO. 3
KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)
Scale: As Noted Date: February 2021


ORIGINAL PLAN	DATE
NOTE BOOK	DESIGNED BY
	CHECKED BY
	QUANTITIES BY
	NO.

PROJECT NAME: KAIPAPAU STREAM BRIDGE REPLACEMENT PROJECT NO. 051221V58-S11.2.DWG. PLOT TIME: 05-13-21 8:52 AM


FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	139	161



SECTION



SECTION
Scale: $3/4" = 1'-0"$



SECTION

Scale: $3/4" = 1'-0"$


GRAPHIC SCALE:

1 0 1 2FT




SCALE: $\frac{3}{4}" = 1'-0"$

APPROVED:  MAY 24 2021
Manager and Chief Engineer, BWS, ^{and} DATE
(for work affecting BWS facilities
State R/W & BWS easements only)



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION

 4/30/22

SIGNATURE LIC. EXPIRATION

MITSUBUNGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION




REACTION BLOCK AT
WING WALL NO. 4
KAMEHAMEHA HIGHWAY
*Kaipapua Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)*

Scale: As Noted Date: February 2021




SHEET No. 511.3 OF 5 SHEETS

DRAWING NAME: E:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\\$\$_REVISED_STRUCT\\$_051221\KSB--S1101.DWG PLOT TIME: 05-13-21, 8:52 AM)

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	140	161




- Notes:
- All angle connections shall be $\frac{3}{16}$ " fillet welds unless noted.
 - Expanded metal mesh shall be welded to inside edges of angles.
 - Stainless steel pin thru pipe hinge shall be inserted and welded to exterior 2" pipes.
 - All pipe hinges, angles and expanded metal mesh shall be stainless steel.
 - Unless otherwise noted all anchor bolts shall be a minimum of 4" from edge of existing concrete.



APPROVED:

 Manager and Chief Engineer, BWS
 (for work affecting BWS facilities
 State R/W & BWS easements only)

MAY 24 2021
 DATE



STATE OF HAWAII
 DEPARTMENT OF TRANSPORTATION
 HIGHWAYS DIVISION

ARV ENCLOSURE DETAILS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. **S11.4** OF 5 SHEETS

SURVEY PLOTTED BY	DATE
DRAWN BY	
TRACED BY	
NOTED BY	
CHECKED BY	
NO.	

DRAWING NAME: F:\PROJECTS\1-ACTIVE FILES\913-01_KAIPAPAU BRIDGE\33-REVISED_STRUCT\3-051221\KSB-S11.4.DWG PLOT TIME: 05-13-21 8:53 AM



FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	141	161



NOTES:

1. See Section 512 for submittals to be stamped and sealed by Hawaii licensed professional geotechnical and structural Engineers.
2. All drawings and details for the prefabricated steel beam bridge and segmental retaining wall shown on sheets S12.1 to S12.5 are schematic only and are shown for bidding purposes only.

DETOUR ROAD TEMPORARY BRIDGE LAYOUT PLAN
Scale: 1/4" = 1'-0"



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

**PREFABRICATED STEEL
BEAM BRIDGE**

**KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)**


Scale: As Noted Date: February 2021

SHEET No. S121 OF 5 SHEETS


ORIGINAL PLAN	DATE
DESIGNED BY	
NOTED BY	
QUANTITIES BY	
CHECKED BY	

DRAWING NAME: 15\PROJECTS\15-01\KAIPAPAU BRIDGE\15-01\REVISED STRUCT\15-01\15-01\KAB-S1201.DWG PLOT TIME: 06-09-21, 3:43 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	142	161





LONGITUDINAL ELEVATION
Scale: 1/4" = 1'-0"
A
S12.1 S12.2



NOTES:

- See Section 512 for submittals to be stamped and sealed by Hawaii licensed professional geotechnical and structural Engineers.
- All drawings and details for the prefabricated steel beam bridge and segmental retaining wall shown on sheets S12.1 to S12.5 are schematic only and are shown for bidding purposes only.

TYPICAL SECTION
Scale: 1/2" = 1'-0"
B
S12.1 S12.2



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

**PREFABRICATED STEEL BEAM BRIDGE
ELEVATION AND TYPICAL SECTION**

**KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)**


Scale: As Noted Date: February 2021

SHEET No. S122 OF 5 SHEETS

ORIGINAL PLAN	DATE
NO.	

DRAWING NAME: 15\PROJECTS\15-01\KAIPAPAU BRIDGE\15-01\REVISED STRUCT\15-01\15-01\KSB-S1202.DWG PLOT TIME: 06-09-21 3:44 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	143	161





* Submit calculations and details to show that the foundation will not be adversely affected by scouring.

PIER NO. 1 ELEVATION A
Scale: 1/2" = 1'-0" S12.4 | S12.3

NOTES:

- See Section 512 for submittals to be stamped and sealed by Hawaii licensed professional geotechnical and structural Engineers.
- All drawings and details for the prefabricated steel beam bridge and segmental retaining wall shown on sheets S12.1 to S12.5 are schematic only and are shown for bidding purposes only.



THIS WORK WAS PREPARED BY
ME OR UNDER MY SUPERVISION
SIGNATURE: *[Signature]* LIC. EXPIRATION: 4/30/22
MITSUNAGA & ASSOCIATES, INC.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

PREFABRICATED STEEL BEAM BRIDGE
FOUNDATION ELEVATION

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)


Scale: As Noted Date: February 2021

SHEET No. S123 OF 5 SHEETS


ORIGINAL PLAN	DATE
DESIGNED BY	DATE
NOTED BY	DATE
CHECKED BY	DATE

DRAWING NAME: I:\PROJECTS\ACTIVE FILES\13-01-KAIPAPAU BRIDGE\13-REVISED-STRUCT\13-051221\KSB-S1202.DWG PLOT TIME: 06-08-21, 3:44 PM

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-083-1(48)	2021	144	161



ABUTMENT SECTION
Scale: 1/2" = 1'-0"





PIER NO. 1 SECTION
Scale: 1/2" = 1'-0"

* Submit calculations and details to show that the foundation will not be adversely affected by scouring.

NOTES:

- See Section 512 for submittals to be stamped and sealed by Hawaii licensed professional geotechnical and structural Engineers.
- All drawings and details for the prefabricated steel beam bridge and segmental retaining wall shown on sheets S12.1 to S12.5 are schematic only and are shown for bidding purposes only.
- Should loose/soft subsoils be encountered at the footing level, the loose/soft materials shall be over excavated a minimum of 24 inches and replaced with stabilization layer consisting of no. 2 coarse rock wrapped with a filter fabric (Mirafi 180N or equal).

ORIGINAL PLAN	DATE
NO.	
DESIGNED BY	
CHECKED BY	
QUANTITIES BY	
REVISIONS	



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION
SIGNATURE DATE: 4/30/22
MITSUNAGA & ASSOCIATES, INC. LIC. EXPIRATION

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

PREFABRICATED STEEL BEAM BRIDGE

SECTIONS

KAMEHAMEHA HIGHWAY
Kaipapau Stream Bridge Replacement
Federal Aid Proj. No. BR-083-1(48)

Scale: As Noted Date: February 2021

SHEET No. S124 OF 5 SHEETS

