

1 **SECTION 301 – HOT MIX ASPHALT BASE COURSE**

2
3 Make the following amendments to said Sections:

4
5 **(I)** Amend **Section 301.03(B)** **Compaction** by revising the second
6 paragraph from lines 84 to 87 to read as follows:

7
8 “Compact mixture immediately upon completion of spreading
9 operations to density of not less than 92.0 percent of maximum theoretical
10 specific gravity in accordance with AASHTO T 209, modified by deletion of
11 Supplemental Procedure for Mixtures Containing Porous Aggregate.”

12
13
14 **(II)** Amend **Section 301.04** **Measurement** from lines 98 to 100 to read as
15 follows:

16
17 **“301.04 Measurement.** The Engineer will measure HMAB course per ton
18 in accordance with contract documents.”

19
20 **(III)** Amend **Section 301.05** **Payment**, from lines 102 to 111 to read as
21 follows:

22
23 **“301.05 Payment.** The Engineer will pay for the accepted pay items
24 listed below at the contract price per pay unit, as shown in the proposal schedule.
25 Payment will be full compensation for the work prescribed in this section and the
26 contract documents.

27
28 The Engineer will pay for one of the following pay items when included in
29 the proposal schedule:

30

31 Pay Item	32 Pay Unit
33 Hot Mix Asphalt Base Course	34 Ton
35 (1) 80% of the contract unit price upon completion of submitting 36 a job-mix formula acceptable to the Engineer; preparing the 37 surface, spreading, and finishing the mixture; and compacting the 38 mixture by rolling;	
39 (2) 20% of the contract unit price upon completion of cutting 40 samples from the compacted pavement for testing; placing and 41 compacting the sampled area with new material conforming to the 42 surrounding area; protecting the pavement; and final analysis.	

43
44

45 The Engineer may, in lieu of requiring removal and replacement, use the
46 sliding scale factor to accept HMAB compacted below 92.0 percent. The

Engineer will make payment for the material in that production day at a reduced price arrived at by multiplying the contract unit price by the pay factor shown in Table 301.05-1.

Table 301.05-1 – Sliding Scale Pay Factor	
Percent Compaction	Percent Payment
92.0 or greater	100
90.0 – 91.9	80
<90.0	Removal

END OF SECTION 301