

1 **SECTION 770 – TRAFFIC SIGNAL MATERIALS**
2

3 Make the following amendments to said Section:
4

5 **(I) Amend Subsection 770.02(A) Standard Traffic Signal Heads** by
6 replacing line 285 through 289 to read:
7

8 **“(4) Back plates.** Back plates shall be furnished and installed on signal
9 heads. Back plates shall be constructed of aluminum alloy 3003-H14
10 sheet having minimum thickness of 0.058 inch, be louvered, and have
11 minimum dimensions equal to signal head size plus five-inch (5”) border.
12 Back plates shall have a dull black finish both sides that minimizes light
13 reflection.
14

15 Back plates shall also include a yellow one-inch (1”) wide, retro-
16 reflective strip placed along the perimeter of the face of back plate. The
17 yellow strip placed along the perimeter of the face shall project a
18 rectangular appearance at night.”
19
20
21
22
23
24

25 **END OF SECTION 770**
26
27
28