

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	83C-01-86M	1986	3	40

UTILITY GENERAL NOTES

GAS COMPANY (GASCO) NOTES

1. The Gasco, Inc. gas pipelines in the project area are plastic coated and cathodically protected. The Contractor shall be extremely careful when working near these gas pipelines.
2. Prior written clearance must be obtained from Gasco, Inc. Maps and Records, 515 Kamae Street at least five working days before starting excavation near these gas pipelines.
3. Since gas line locations on field maps are approximate, the Contractor, after obtaining written clearance, shall call Gasco, Inc. a minimum of 48 hours before starting excavation to arrange for field location of the existing gas pipelines. The telephone number is 547-3575 during business hours, and 526-0066 after hours
4. For relocation of any gas pipeline, the Contractor shall notify Gasco, Inc. five working days before starting work. The Contractor shall provide the necessary excavation and backfill, arrange for traffic permits, and restore pavement, sidewalks, or other facilities. Any relocation of gas facilities shall be performed by Gasco, Inc.
5. The Contractor shall notify Gasco, Inc. immediately after any damage has been caused to existing gas pipelines, coatings, or cathodic protection devices. The Contractor shall be liable for any damages to GASCO facilities. Repair work on such damage shall be done by Gasco, Inc., with payment for this work borne by the Contractor.
6. Minimum vertical and horizontal clearance between the gas pipelines and other pipelines, conduits, ductlines, or other facilities shall be 12 inches. Adequate support and protection for gas pipelines exposed in the trench shall be provided by the Contractor and approved by Gasco, Inc.
7. The Contractor shall work in an expeditious manner in order to keep the uncovered gas pipelines exposed for as short a period of time as possible.
8. The Contractor shall excavate and backfill around the pipeline in the presence of a Gasco representative. All backfill within 6 inches of the pipeline shall be select cushion material approved by Gasco.

WASTEWATER MANAGEMENT (SEWER) NOTES

1. All construction shall be performed in accordance with the City's STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, May 1975 and THE STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION, September, 1984, and THE REVISED ORDINANCES OF HONOLULU, 1978, as amended.
2. The Contractor shall notify the Division of Wastewater Management (7) seven days prior to the commencement of sewer work and submit (4) four sets of approved construction plans.
3. Location of existing sewer appurtenances shown on the plans are approximate only. The exact location shall be verified in the field.

BOARD OF WATER SUPPLY (BWS) NOTES

1. Unless other wise specified, all materials and construction of water system facilities and appurtenances shall be in accordance with the STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, dated 1985, as amended, of the Hawaii Highways Division, Department of Transportation.
2. The BWS Standard Details, Figures 1 to G2 inclusive, bound in the "Water System Standards" of the BWS, dated March 1977, as amended, are applicable to this project.
3. Prior to excavating for new drain, sewer, and other utility lines, the Contractor shall verify in the field the location of existing water mains and appurtenances.

Where the installation of new drain, sewer, and other utility lines are to cross over or under existing water mains, the Contractor shall expose the existing water mains prior to trenching. Excavation around water mains shall be done by hand.
4. The minimum clearance between fire hydrants and utility poles or light standards shall be 3.0 feet.
5. The Contractor shall notify the Board of Water Supply in writing one week prior to commencing work on the water system.
6. All plans approved by the Board of Water Supply are based solely on the adequacy of the water supply. All other features of the water system, such as lines, grades, fittings etc., and drainage and other features of improvements shall not be the responsibility of the Board of Water Supply.
7. The existence and location of underground utilities and structures as shown on the plans are from the latest available data but is not guaranteed as to the accuracy or the encountering of other obstacles during the course of the work. The Contractor shall be responsible and shall pay for all damages to existing utilities.
8. Any adjustments to the existing water system required during construction to meet requirements of BWS Standards, whether shown on the plans or not, shall be done by the Contractor at no cost to the Board.

ZIONS SECURITIES CORP. LAIE FACILITIES

1. The Contractor shall notify, in writing, the Zions Securities Corp. at 55-510 Kam. Hwy., Laie, one week prior to performing work in the Laie vicinity including but not limited to the areas adjacent to the sewer and water facilities.
2. The Contractor shall be responsible for any damage to the existing facilities and no additional payment will be made for repair of damages.

HAWAIIAN ELECTRIC COMPANY (HECO) NOTES

1. The location of HECO's overhead and underground facilities shown on the plans are from existing records with varying degrees of accuracy and are not guaranteed as shown.

The Contractor shall exercise extreme caution whenever construction crosses or is in close proximity of underground lines and shall maintain adequate clearance when operating equipment within or under any overhead lines.
2. The Contractor shall comply with the State of Hawaii's Occupational Safety and Health Law (DOSH).
3. The Contractor shall obtain an excavation permit from HECO's Mapping and Records Division located at 820 Ward Avenue, 4th floor, two weeks prior to starting construction.
4. For verification of underground lines or for assistance in supporting and protecting these lines, the Contractor shall call HECO's Underground Division at 548-7395 a minimum of 72 hours in advance.
5. When trench excavation is adjacent to or beneath our existing structures or facilities, the Contractor is responsible for:
a) Sheeting and bracing the excavation to prevent slides, cave-ins and settlements.
b) Protecting existing structures or facilities with beams, struts, or under-pinning.
6. Any work required to relocate HECO facilities shall be done by HECO and the Contractor shall be responsible for all coordination, and for costs if applicable.
7. The Contractor shall be liable for any damages to HECO facilities and shall immediately report such damages to HECO's Trouble Dispatcher at 548-7961.

HAWAIIAN TELEPHONE COMPANY (HTCO) NOTES

1. The location of existing Hawaiian Telephone Company underground facilities are approximate only. The Contractor shall verify their location and depth of the facilities. Any damages to the underground facilities as a result of his operations shall be repaired and paid by the Contractor.
2. The Contractor shall notify Hawaiian Telephone Company Telephone Cable Locator Service at 834-6214, 72 hours prior to the start of excavation for field location of Hawaiian Telephone Company underground facilities including the U.S. Army Signal Corps cable located approximately along the existing edge of pavement of the highway.

STATE OF HAWAII	
DEPARTMENT OF TRANSPORTATION	
HIGHWAYS DIVISION	
UTILITY GENERAL NOTES	
KAMEHAMEHA HIGHWAY RESURFACING	
Laiemaloa Bridge to Puuluanā Street	
PROJECT NO. 83C-01-86M	

SHEET No. OF SHEETS

DATE	_____
DESIGNED BY	_____
TRACED BY	_____
NOTED BY	_____
CHECKED BY	_____
ORIGINAL PLAN	_____
NOTE BOOK	_____
No.	_____