

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	83D-01-97M	1997	3	5

GENERAL NOTES

- The scope of work for this project consists of repairing spalled and cracked concrete on Kaaawa Stream Bridge.
- The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
- The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property And Services; and Section 645 -Traffic Control.
- At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
- The exact locations and limits of areas to be repaired shall be determined in the field by the Engineer.
- The Contractor shall notify in writing, the Oahu Transit Services, Inc. Roads Supervision Office, 811 Middle St., Hon., HI 96819 (ph. #848-4571) seven (7) days prior to any repairing operations.
- The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting repairing operations.
- The Contractor shall erect construction warning signs approximately 500 feet before the beginning of project and 500 feet after the end of project or as directed by the Engineer.
- The Engineer will determine if additional sandblasting is required when a patching area is exposed to the environment for too long. Additional sandblasting shall be considered incidental to the various contract items.
- The Contractor shall be required to provide to the Engineer and his personnel a means of conducting the inspection. The Contractor shall also provide to the Engineer and his personnel the necessary safety measures and safety equipment required to conduct the inspection. This work shall be considered incidental to the various contract items.

ORIGINAL PLAN	SURVEY PLANNED BY	DATE
NOTE BOOK	DRAWN BY	1/23/97
1/10/01	DESIGNED BY	
1/10/01	QUANTITIES BY	
1/10/01	CHECKED BY	

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION  
**GENERAL NOTES**  
KAMEHAMEHA HIGHWAY  
Repair Spalls at Soffit, Piles and  
Pier Caps on Kaaawa Stream Bridge  
Project No. 83D-01-97M  
Date: December, 1996  
SHEET No. 1 OF 1 SHEETS