

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20
- 21
- 22
- 23
- 24
- 25
- 26
- 27
- 28
- 29
- 30
- 31
- 32
- 33
- 34
- 35
- 36
- 37
- 38
- 39
- 40
- 41
- 42
- 43
- 44
- 45
- 46

**(I)** Amend **Subsection 301.02 Materials** by revising line 11 to read as follows:

**(II) Amend Subsection 301.03(B) Compaction** by revising the second paragraph from lines 84 to 87 to read as follows:

(III) Amend **Subsection 301.04 Measurement** from lines 98 to 100 to read as follows:

**(IV) Amend Subsection 301.05 Payment**, from lines 102 to 111 to read as follows:

The Engineer will pay for one of the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
Hot Mix Asphalt Base Course (with Polymer Modified Asphalt)	Ton
<p>(1) 80% of the contract unit price upon completion of submitting a job-mix formula acceptable to the Engineer; preparing the surface, spreading, and finishing the mixture; and compacting the mixture by rolling;</p> <p>(2) 20% of the contract unit price upon completion of cutting samples from the compacted pavement for testing; placing and compacting the sampled area with new material conforming to the surrounding area; protecting the pavement; and final analysis.</p>	

The Engineer may, in lieu of requiring removal and replacement, use the sliding scale factor to accept HMAB compacted below 92.0 percent. The Engineer will make payment for the material in that production day at a reduced price arrived at by multiplying the contract unit price by the pay factor shown in Table 301.05-1.

Table 301.05-1 – Sliding Scale Pay Factor	
Percent Compaction	Percent Payment
92.0 or greater	100
90.0 – 91.9	80
<90.0	Removal

**END OF SECTION 301**