

1 **SECTION 631 – TRAFFIC CONTROL, REGULATORY, WARNING, AND**
2 **MISCELLANEOUS SIGNS**

3
4 Make the following amendment to said Section:

5
6 **(I) Amend Section 631.03(C) Labeling of Signs** by revising lines 42 to 51 to
7 read as follows:

8
9 **“(C) Labeling of Signs.** Label back of each sign with sign stickers as
10 directed by the State. Sign stickers will be provided by the State.”

11
12 **(II) Amend Section 631.04 – Measurement** by revising lines 67 to 69 to read:

13
14 **“631.04 Measurement.** The Engineer will measure regulatory, warning,
15 and miscellaneous signs as complete units of the type and design specified in
16 the proposal.

17
18 The Engineer will not measure removal and disposal and storing of existing and
19 temporary signs that the Contractor will not incorporate in the completed highway
20 for payment.”

21
22 **(III) Amend Section 631.05 – Payment** by revising lines 71 to 99 to read as
23 follows:

24
25 **“631.05 Payment.** The Engineer will pay for the accepted quantities of
26 regulatory, warning, and miscellaneous signs at the contract price per each for
27 the type and design specified complete in place. Payment will be full
28 compensation for excavating and backfilling, furnishing and installing materials,
29 furnishing equipment, tools, labors and incidentals necessary to complete the
30 work.

31
32 The Engineer will not pay for removing and disposing or storing of existing
33 and temporary signs that the Contractor will not incorporate in the completed
34 highway separately. The Engineer will consider them incidental to the various
35 contract items.

36
37 The Engineer will pay for the following pay items when included in the
38 proposal schedule:

39

40 Pay Item	41 Pay Unit
42 Regulatory Sign (10 Square Feet or Less)	43 Each
44 Regulatory Sign (10 Square Feet or Less) with Post(s)	45 Each
46 Warning Sign (10 Square Feet or Less)	47 Each

48	Warning Sign (10 Square Feet or Less) with Post(s)	Each
49		
50	Removal of Existing Sign	Each
51		
52	Removal of Existing Sign and Post(s)	Each
53		
54	Anchor Base for Portable Contra-Flow Sign	Each"

55

56

57

58

59

END OF SECTION 631