

1                   **SECTION 755 – PAVEMENT MARKING MATERIALS**

2  
3       Make the following amendments to said Section:

4  
5       **(I) Amend Subsection 755.02 (C) Retroreflective Pavement Markers** by  
6       revising lines 223 to 236 to read:

7  
8               “Exterior surface of shell shall be smooth and contain one or two  
9       retroreflective faces of specified color.”

10  
11       **(II) Amend Subsection 755.05 (C)(1) Glass Beads** by adding the following  
12       after line 869:

13  
14               **“(f)** The glass beads shall not contain more than 200 ppm (total)  
15       arsenic, 200 ppm (total) antimony nor more than 200 ppm (total)  
16       lead, when tested according to EPA Methods 3052 and 6010C.  
17       Other suitable x-ray fluorescence spectrometry analysis methods  
18       may be used to screen samples of glass spheres for arsenic and  
19       lead content.”

20  
21  
22  
23  
24  
25  
26  
27                   **END OF SECTION 755**  
28