



TREE PROTECTION ZONE

- All trees identified on the plans should be protected. All trees 6" caliper or greater (as measured at 4½ feet height) shall be protected. If trees other than those designated for removal are damaged beyond survival condition as determined by the Engineer, the Contractor shall remove such trees and replace with a tree of the same specie and size and maintain for the duration of the construction or 12 months whichever is greater at no cost to the state.
- The recommended Tree Protection Zone should be located at the outer drip line of the canopy of the tree. However, the minimum protection zone around a tree should be at least 20 feet from the external surface of the tree's trunk.
- All trees shall remain unless shown for removal. All protected trees shall be listed on the roadway plans. If there is a discrepancy, contractor shall contact the Engineer immediately.
- Protective fences shall be erected around trees identified on the plans or trees with a trunk diameter greater than 6 inches (as measured at a height of 4½ feet.) Protective fence shall be 4 feet high orange plastic mesh or approved equivalent supported on steel T-post a minimum of 6 feet long. Protective fence shall surround the tree at a minimum of 5 feet from the tree trunk with steel T-post at a minimum of 5 feet on center. Fence shall be installed and approved by Landscape Architect or Engineer prior to any demolition work and shall remain in place until site work is completed. Signs shall be posted on all four sides to read "Tree Protection Zone (TPZ) - No Grade Changed, Stored or Equipment Permitted Within TPZ."
- For the duration of construction within the drip line of the trees to remain, there must be :
 - No changed, alternation or disturbance to the grade by adding fill, excavating or scraping except as noted on plans;
 - No storage on construction materials or equipment;
 - No stockpiling of any construction materials or excavated materials;
 - No disposal of any liquids example concrete sleuth, gas, oil or paint;
 - No vehicular traffic, equipment or excessive pedestrian traffic;
 - No attachment of any wires, ropes, lights or any other such attachment other than those of a protective nature to any tree to be preserved, and
 - No cleaning of equipment or material under the canopy of any tree or group of trees to be preserved.




TREE PROTECTION ZONE (TPZ) DETAIL

Not to Scale



PLAN VIEW




Note :

Nodules to face tree. Place top edge of root control barrier at finish grade and secure with manufacturer provided pins. Seams shall have minimum 3 inches overlap. Refer to manufacturer instructions for bonding the seam. Do not allow gaps in fabric during installation or backfilling. Root control barrier should not be left exposed to surface water or sunlight for more than 12 hours since high temperatures and sunlight reduce effective life of product label and MSDS sheet for safety information.

MEDIAN DETAIL WITH ROOT CONTROL BARRIER INSTALLATION DETAIL

Not to Scale

Tree roots shall not be cut unless cutting is unavoidable. When root cutting is unavoidable, a clean, sharp cut shall be made to avoid shredding or smashing. Root cuts shall be made back to a lateral root whenever possible. Exposed roots shall be covered immediately with soil or burlap and keep moist. Fertilize and water to minimize shock as directed by a certified Arborist or Engineer. Root Cutting shall be considered Incidental to Biochemical Root Control Barrier.




TREE PRUNING DETAIL

Not to Scale

Note :

- Positions of first and second cuts may be reversed in some cases, particularly when cutting a large branch with a chainsaw.
- Do not make flush cuts or leave stubs.
- Do not paint cuts.
- Remove dead, broken or malformed branches.
- Remove all vines entwined in the tree or around its trunk.
- All pruning shall be completed using clean sharp tools. All cuts shall be clean and smooth, with the bark intact with no rough edges or tears.
- Dispose of all cuttings outside of right of way.
- Retain the normal shape of the plant.



FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	92AB-01-06M	2006	74	74

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


LANDSCAPING DETAILS

NIMITZ HIGHWAY AND
ALA MOANA BOULEVARD RESURFACING
Fort Street to Piikoi Street
Project No. 92AB-01-06M

Scale: Not to Scale Date: April 2006

SHEET No. 1 OF 1 SHEETS

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	92AB-01-06M	2006	74S1	74



Note :
Maintain 2 ft. minimum width between utilities and palms
except where otherwise noted.

ALA MOANA BLVD.

TRAFFIC COUNTING STATION LANDSCAPING PLAN


03/01/07 This sheet added to contract plans

DATE	REVISION
------	----------

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
LANDSCAPING PLAN
NIMITZ HIGHWAY AND
ALA MOANA BOULEVARD RESURFACING
Fort Street to Piikoi Street
Project No. 92AB-01-06M
Scale: Not to Scale Date: February 2007
SHEET No. 1 OF 2 SHEETS

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	92AB-01-06M	2006	74S2	74

- | PLANT LIST | | | |
|------------|---------------------|-----------------------------------|-------------------------------|
| | COMMON NAME | BOTANICAL NAME | COMMENTS |
| 21 | Areca Palm | <i>Chrysalidocarpus Lutescens</i> | 15 gal. can, 6' ht., 24" O.C. |
| | St. Augustine Grass | <i>Stenotaphrum Secundatum</i> | 6" Sprigs, 4" O.C. |



1. *Trunks must be protected from rope sling burns and abrasions during moving.*
2. *Prune off all dead fronds.*
3. *Water heavily to insure soil settles around roots.*
4. *Tree shall be plumb, if there is leaning at the end of the plant establishment period, the tree shall be rejected.*

Not to Scale

03/01/07	<i>This sheet added to contract plans</i>
DATE	REVISION

STATE OF HAWAII
 DEPARTMENT OF TRANSPORTATION
 HIGHWAYS DIVISION

LANDSCAPING DETAILS

NIMITZ HIGHWAY AND
ALA MOANA BOULEVARD RESURFACING


Fort Street to Pili'oi Street
Project No. 92AB-01-06M

Scale: Not to Scale *Date: February 2007*

SHEET No. 2 OF 2 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY _____ DATE _____
NOTE BOOK	DRAWN BY _____ *
Hand-drawing	TRACED BY _____ *
co/452.dgn	DESIGNED BY _____ *
	QUANTITIES BY _____ *
	CHECKED BY _____

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	92AB-01-06M	2006	7453	74




MULTI-TRUNK PALM PLANTING DETAIL ON LEVEL GROUND

Not to Scale

NOTES:

1. Trunks must be protected from rope sling burns and abrasions during moving.
2. Prune off all dead fronds.
3. Water heavily to insure soil settles around roots.
4. Tree shall be plumb, if there is leaning at the end of the plant establishment period, the tree shall be rejected.



GRASS PLUG SPACING DETAIL

Not to Scale

03/15/07	This sheet added to contract plans
DATE	REVISION
STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION LANDSCAPING DETAILS NIMITZ HIGHWAY AND ALA MOANA BOULEVARD RESURFACING Fort Street to Pilihoi Street Project No. 92AB-01-06M Scale: Not to Scale Date: March 2007 SHEET No. 3 OF 3 SHEETS	