

1. The Contractor shall resurface the prepared pavement with A.C. Mix V in accordance with the following schedule:

2. The roadway width for resurfacing shall be 21'±.
3. There will be no resurfacing on bridge decks except on Bridge No. 5A from Sta. 1172 + 28.17 to Sta. 1172 + 50.00, which will receive a maximum of 3/4" A.C. Mix V.
4. Resurfacing shall also be done alongside the main roadway at the following locations:

5. Refer to Article 4.1 of the Specifications for additional requirements.

DISTRICT OF WAIANAE
ISLAND OF OAHU

LOCATION OF PROJECT
PROJECT NO. 900C-02-68

ALL CHANGES MADE DURING CONSTRUCTION HAVE
BEEN NOTED IN RED ON THESE TRACINGS AND
CHECKED BY

FARRINGTON HIGHWAY
PROJECT NO. 900C-02-68

PROJECT NO. 900C-02-68

NOTE

BEG. OF PROJECT **END OF PROJECT**

Makaha Beach Park

Keauu Beach Park

Makaha Bridge No. 125

Makaha Bridge No. 124

Makaha Bridge No. 126

Makaha Bridge No. 127

Makaha Bridge No. 128

Makaha Bridge No. 129

Makua Protestant Church Cemetery

Makua Bridge No. 130

Bridge No. 5A

Cave

EQ = Sta. 1180 + 99.90 BK.
Sta. 1181 + 00.90 AHD.

Proj. No. WPSO 23-B
Sta. 1018 + 33.42

Proj. No. WPSO 23-B
Sta. 1207 + 02.38

Proj. No. R-AD 2(I)
Sta. 288 + 00

0 0.5
SCALE IN MILES

LAYOUT PLAN
GROSS LENGTH = 3.573 Miles
BRIDGES = 0.048 Mile
NET RDWY LENGTH = 3.525 Miles