## <u>DEPT. OF DESIGN AND CONSTRUCTION (DDC) NOTES:</u> (For work within areas under DDC jurisdiction)

- 1. The Contractor shall obtain a Right-of-Entry to Parks Permit prior to construction
- 2. Locations of all existing utilities shown are approximate only. The Contractor shall exercise extreme caution in excavating near utilities. Any and all damage shall be immediately repaired and/or restored to its original condition by the contractor at his cost. Utilities shall include but not limited to electrical, telephone, sewer, water, and irrigation systems, etc.
- 3. Except for portions of the area affected by this contract, the park will be in continuous use by the public. The Contractor shall provide full cooperation with the Department of Design and Construction to effectively maintain such use of the park facilities. Contact Parks Maintenance and Recreation Services District III Superintendent, phone no. 671-0561, two weeks prior to start of work.
- 4. For all depressions, low spots, uprooted areas and problem spots as determined by the Officer-in-Charge, the Contractor shall fill with approved compacted fill and grassed in accordance with the Department of Design and Construction Standard Specifications for Parks.
- 5. All tree relocation and tree pruning (top and root) shall be done in the presence of an arborist certified by the International Society of Aboriculture. Extensive root pruning may require top pruning to properly balance and compensate for water loss. All work shall be done under the observation of the Beautification Division, Department of Design and Construction. Contractor shall notify the BeautificationAdministrator, phone 971-7151, seven days prior to start of work.
- 6. Maintenance of relocated trees and grassing shall be for a minimum of 60 calendar days after establishment of landscaping.
- 7. All relocated trees shall be guaranteed for one year. Contractor shall replace with the same size and species if any tree fails to survive by the end of one year.
- 8. Parking and driving of vehicles and storage of materials within the driplines of trees shall be prohibited.
- 9. The existing irrigation system shall be repaired and/or relocated as shown and as noted on the plans and in accordance with the standard specifications for Irrigation and Water Systems of the Department of Design and Construction, City and County of Honolulu.
- 10. Existing sprinkler heads and quick connect valves may be buried. The locations of existing water and sprinkler lines, heads and valves as shown are approximate only. The Contractor shall locate, expose, and verify these existing facilities prior to commencing with work.

	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
	HAWAII	HAW.	NH-093-1(19)	1999	4	49

- 11. The Contractor shall perform the relocation work in such a manner so shutting down of the existing water and sprinkler lines are kept to a minimum and adjust sprinklers to assure proper coverage and operation.
- 12. Coordinate all sprinkler relocation work with the Parks,
  Maintenance and Recreation Services Superintendent. The
  Contractor shall maintain all areas affected by his operations,
  including those areas outside his construction area that may be
  affected.
- 13. No tracked vehicles or equipment are allowed. No overnight storage of materials, equipment, or vehicles are allowed.
- 14. The Contractor shall restore all damage caused by his operations to original condition or better at his own expense. All restoration work to be done in accordance with Department of Design and Construction Recreation Standards.

DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TRACKS BEACH PARK

DRIVEWAY NOTES

FARRINGTON HIGHWAY IMPROVEMENTS

SHEET No. 1

Vicinity of Tracks Beach Park
Federal Aid Project No. NH-093-1(19)

Date: May, 1999

OF 1 SHEETS

