

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HSIP-093-1(23)	2011	3	19

GENERAL NOTES

1.

The scope of work for this project consists of installation of centerline rumble strips, signage, and installation of traffic signal assemblies and back plates.
2.

The Contractor is reminded of the requirements of Subsection 105.16 - Subcontracts which requires him to perform work to not less than 30 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3.

The Contractor's attention is directed to the following Sections: Subsection 104.11 - Utilities and Services; Subsection 107.06 - Contractor Duty Regarding Public Convenience; and Section 645 - Work Zone Traffic Control.
4.

At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5.

The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data, but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall tone for the exact locations and depths of all underground facilities, either shown on or omitted from the plans, in areas where work, such as the placement of sign posts, traffic signal conduits, etc. may affect these properties. Toning shall be considered incidental to the various contract items and will not be paid for separately. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6.

The Contractor shall notify, the Oahu Transit Services, Lowell Tom (848-4578) or Ed Sniffen (848-4571), two (2) weeks prior to construction, informing them of location, scope of work, and closure of Farrington Highway and/or traffic lanes and dates of closure.
7.

The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting construction operations.
8.

The Contractor shall indemnify and be solely responsible for the protection of adjacent properties, utilities and existing structures from damages due to construction. Repairing any damage shall be at the Contractor's own expense, to the satisfaction of the Engineer.
9.

The Contractor shall be responsible for ensuring that the existing drainage system will be functional at all times during construction. The Contractor shall furnish materials, equipment, labor, tools and incidentals necessary to maintain flow at no cost to the State.
10.

The Contractor shall clean and remove any accumulation of aggregates along the roadside within 10 feet of the edge of pavement. This work shall be considered incidental to the various contract items and will not be paid for separately.
11.

The Contractor shall provide and maintain for access to and from all existing driveways , sidewalks and ADA access routes complying with ADAAG section 4.3, and side streets and cross streets at all times during construction. This work shall be considered incidental to Item No. 645.0100 - Traffic Control.
12.

No material and/or equipment shall be stockpiled or otherwise stored within the highway right-of-way except at locations designed in writing and approved by the Engineer.

LEGEND

- sign

Existing Traffic Sign
- post

Existing Traffic Signal Pole
- pullb

Existing Traffic Signal Pullbox

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

FARRINGTON HIGHWAY SAFETY IMPROVEMENTS

Leihoku Street to Kili Drive

Federal Aid Project No. HSIP-093-1(23)

Date: 08, 2011

SHEET No. 1 OF 1 SHEETS