

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ADDENDUM NO. 4

FOR

**FARRINGTON HIGHWAY RESURFACING
VICINITY OF KILI DRIVE TO SATELLITE TRACKING STATION ROAD
FEDERAL AID PROJECT NO. STP-093-1(026)
DISTRICT OF WAIANAE
ISLAND OF OAHU
FY 2016**

The following amendments shall be made to the Bid Documents:


A. PLANS

1. Revise Plan Sheet No. 40 by amending note "BL Sta. 1214+83.00± Lt. to BL Sta. 1255+33.30± Lt." to read as follows:

"Remove 3,935.00± L.F. of existing guardrail and posts. Install 3,800.00± L.F. of Strong Post W-Beam Guardrail, and 37.50± L.F. of Guardrail Type 3 Thrie Beam with Transitions (See Details on Plan Sheet No. 79) over existing Twin Cell Culverts at BL Sta. 1216+00 and BL Sta. 1243+00. At existing Triple Cell Culvert, connect New Guardrail to existing guardrail (See Details on Plan Sheet No. 78). Install FLEAT 350 (See Details on Plan Sheet No. 24) or Equivalent at Approach and Trailing End."
2. Revise Plan Sheet No. 40 by amending note "BL Sta. 1223+27.80± Rt. to BL Sta. 1228+75.10± Rt." to read as follows:

"Remove 278.00± L.F. of existing guardrail and posts. Install 387.50± L.F. of Strong Post W-Beam Guardrail. At existing Triple Cell Culvert, connect New Guardrail to existing guardrail (See Details on Plan Sheet No. 78). Install FLEAT 350 (See Details on Plan Sheet No. 24) or Equivalent at Approach and Trailing End."

Please acknowledge receipt of this Addendum No. 4 by recording the date of its receipt in the space provided on page P-4 of the Proposal.


FORD N. FUCHIGAMI
Director of Transportation

STP-093-1(026)

Addendum No. 4