

GENERAL NOTES

1. The scope of work for this project consists of constructing a 4 foot bituminous sidewalk, a 4 foot concrete sidewalk, curbing, and wheelchair ramps, installing new guardrails, removing and relocating existing guardrails, demolishing and removing a concrete drop inlet and a concrete ditch, plug existing RCP, constructing a catch basin and concrete spillway, and installing a 6 foot chain link fence, pavement striping and markings.
2. The existence and location of underground utilities, appurtenances and structures as shown on the plans are from the latest available data but is not guaranteed as to the accuracy or the encountering of other obstacles during the course of the work. The Contractor shall be responsible and shall pay for all damages to existing utilities resulting from his operations. All damaged portions shall be replaced in accordance with the Standards and Specifications of the State and/or the affected utility company.
3. The Contractor shall exercise extreme caution whenever construction is in close proximity of the underground signal corps line.
4. The exact limits of constructing the specified items are approximate. The exact locations shall be determined in the field by the Engineer.
5. Saw cutting of the existing asphalt concrete pavement shall be considered incidental to roadway excavation.
6. Removal and disposal of existing pipe post at the location of O.B. @ Sta. 78+60± will not be measured and paid for separately but shall be considered incidental to the various contract items in the proposal.
7. The Contractor's attention is directed to Subsection 107.13- "Public Convenience and Safety"; Section 645- "Traffic Control" of the Special Provisions and Subsection 107.21- "Contractor's Responsibility for Utility Property and Service" for Hawaiian Electric Co., Hawaiian Telephone Co., Board of Water Supply and Wastewater Management (Sewer) Utility Notes.

LEGEND

- ts- Existing Traffic Signal Line
- sc- Existing Signal Corps Line
- t- Existing Telephone Line
- w-4- Existing Water Line
- s-6- Existing Sewer Line
- pb Existing Telephone Pullbox
- tp Existing Telephone Pole
- pp Existing Power Pole
- wmh Existing Water Manhole
- smh Existing Sewer Manhole
- fh Existing Fire Hydrant
- wm Existing Water Meter
- gp Existing Guy Pole with Anchor
- wr Existing Water Valve
- sls Existing Street Light Standard
- ==CD24== Existing Drainage Line
- dmh Existing Drainage Manhole
- jp Joint Pole
- N.I.C. Not In Contract

FED. ROAD DIST. NO.	STATE	FED-AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	99C-01-87	1987	3	8

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
No.	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
GENERAL NOTES AND LEGEND
KAMEHAMEHA HIGHWAY IMPROVEMENTS
Mililani Town to Waikalani Drive
Project No. 99C-01-87
Date: June, 1987
SHEET NO. 1 OF 8 SHEETS