

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	99D-01-92M	1992	3	10

GENERAL NOTES

LEGEND

1. The scope of work for this project consists of constructing an additional left turn lane on Kamehameha Highway at Waimano Home Road, constructing a median, traffic island and wheelchair ramps, adjusting a utility manhole and installing traffic signal standards, loop detectors, signs & pavement markings.
2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, to perform with its own organization, work amounting to not less than 50 percent of the total contract cost less deductible amounts allowed. Non compliance with this Subsection may be grounds for rejection of bid.
3. The Contractor's attention is directed to Subsection 107.13 - Public Convenience and Safety; Section 645 - Traffic Control and Subsection 107.21 - Contractor's Responsibility for Utility Property and Service.
4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6. Smooth riding connections shall be constructed at all limits of construction as shown on the plans and/or as directed by the Engineer.
7. Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to accomplish maintenance of flow, the cost of which shall be considered incidental to the various contract items.
8. Contractor shall provide for access to and from all existing driveways and streets at all times.
9. All saw cutting work shall be considered incidental to Roadway Excavation.
10. The Contractor shall notify the State in writing two (2) weeks prior to starting paving operations.
11. The Contractor shall notify the Mass Transit Line, Inc. Customer and Public Relations Office at 848-4576, seven (7) days prior to starting construction.



Roadway Construction Area

at&t

Existing American Telephone & Telegraph Manhole

scmh

Existing Signal Corp Manhole

tmh

Existing Telephone Manhole

sdmh

Existing Storm Drain Manhole

smh

Existing Sewer Manhole

cb

Existing Catch Basin

d1

Existing Drain Inlet

wmh

Existing Water Manhole

wm

Existing Water Meter

wv

Existing Water Valve

gv

Existing Gas Valve

fh

Existing Fire Hydrant

jp

Existing Joint Pole

sl

Existing Street Light

tsp

Existing Traffic Signal Pole

tspb

Existing Traffic Signal Pullbox

tscb

Existing Traffic Signal Control Box

mon.

Existing Monument

tree

Existing Tree

s-8"

Existing Sewer Line

fm-6"

Existing Force Main Line

d-24"

Existing Drain Line

w-8"

Existing Water Line

oil-10"

Existing Oil Line

g-16"

Existing Gas Line

t

Existing Telephone Cable

at&t

Existing American Telephone & Telegraph Cable

inertial barriers

Existing Inertial Barriers

road loop detectors

Existing Road Loop Detectors

guardrail

Existing Guardrail

right of way

Existing Right of Way

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION  
**GENERAL NOTES AND LEGEND**  
KAMEHAMEHA HIGHWAY  
Left-Turn Lane at Waimano Home Road  
PROJECT NO. 99D-01-92M  
Date: Dec., 1991  
SHEET No. 1 OF 1 SHEETS