

GENERAL NOTES

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	99C-02-98M	1999	3	6

- The scope of work for this project consists of cleaning and painting (overcoating) the steel girders, girder stiffeners, end diaphragms, and intermediate diaphragms of the bridge structures; and cleaning, painting, and greasing the fixed and expansion bearings.*
- If the removal of old paint by hand or power-operated equipment do not remove the material satisfactorily, the Engineer will allow the Contractor to use limited water blasting. Limited water blasting will be allowed only in areas where the above mentioned cleaning methods are ineffective. In limited water blasting operations, the Contractor shall not exceed nozzle pressures that will cause the removal of the existing paint coat.*
- Project does not consist of any designated paint stripping. Only removal of old paint, flaking paint, loose rust, and loose dust as directed in Subsection 695.02 are allowed.*
- The Contractor shall inspect all steel members of the bridge overpass and conduct minor repairs as described in Subsection 695.03. The extent and method of the minor repair shall be reviewed and agreed upon by the Engineer.*
- Plan Sheet Nos. 4 to 6 are for information purposes only. All dimensions of existing metal members to be cleaned and painted shall be verified in the field by the Contractor.*
- The Contractor shall gain access to the jobsite via the City and County of Honolulu's Park and Ride Access Road as directed in Subsection 699.01.*
- The cleaning and painting of metal surfaces shall not be measured separately, but shall be paid for on a lump sum basis under various pay items in the proposal.*
- The Contractor shall not permit the discharge of any kind resulting from the construction activities. The Contractor's attention is directed to Subsection 695.04.*
- The Contractor's attention is directed to Section 107, "Legal Relations and Responsibility to Public" of the Specifications. The Contractor shall be responsible for getting the necessary permits and licenses required to do the job.*
- The Contractor shall paint the steel portions of the bridge structures with a prime coat, intermediate and stripe coat, and a top coat as directed in Subsection 695.03(E).*

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY G. Athurcia	6-30-98
066 George	TRACED BY J. Fullinwider, H. Alejandro	
N. Ramdgn	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

**GENERAL NOTES AND LEGEND**  
KAMEHAMEHA HIGHWAY  
Repaint Steel Girders and Lubricate  
Bearings on Waipahu Overpass  
Project No. 99C-02-98M

Scale: None      Date: June, 1998

SHEET No. 1 OF 1 SHEETS