

Revised Dec. 4, 1935

NOTES ON PAVEMENT AND BASE COURSE

CRUSHER RUN BASE COURSE: 8" (compacted thickness) of crusher run material (20% wear) constructed in two layers

ASPHALTIC MACADAM SURFACE COURSE: 3" (compacted thickness) No 1 Crushed rock (3 1/2" to 1 1/4") keyed with No 3 crushed rock (1" to 3/8"); 16 lbs per sq. yd. Asphalt (85-100); and sufficient No 5 crushed rock (3/8" to #10) to complete keying; 5 lbs per sq. yd. of Asphalt (120-150) and sufficient No 6 crushed rock (1/4" to #20) to fill surface voids

GENERAL NOTES: Particular reference is made to the specifications covering these items of work.

FOR TYPICAL ROAD SECTION BETWEEN STA. 52+70 & STA. 65+39 SEE SHEET 4304.17A

