

STANDARD PLANS SUMMARY

FED. ROAD DIST. NO.	STATE	FED-AID- PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7500A-01-00M	1988	2	12

Standard Plan No.	Title	Date
B-01	Notes and Miscellaneous Details	07/01/86
B-02		
B-03	Typical Structure Excavation and Backfill Pay Limits	07/01/86
B-04		
B-05		
B-06	Concrete Box Girder	07/01/86
B-07	Concrete Box Girder	07/01/86
B-08	Concrete Box Girder	07/01/86
B-09		
B-10		
B-11		
B-12	Prestressed Concrete Piles	07/01/86
B-13	Prestressed Concrete Piles	07/01/86

D-01	Chain Link Fence With Toprail	r 03/06/87
D-02	Chain Link Fence Without Toprail	07/01/86
D-03	Wire Fence With Metal Posts	07/01/86
D-04	Typical Details of Curbs and/or Gutters	07/01/86
D-05	Typical Details of Reinforced Concrete Drop Driveway	07/01/86
D-06 ●	Centerline and Reference Survey Monument	07/01/86
D-07 ●	Street Survey Monument	07/01/86
D-08	Landscaping Shrub and Tree Planting	07/01/86
D-09	Field Office	07/01/86
D-10	Field Office	07/01/86
D-11	Project Site Laboratory	07/01/86
D-12	Project Site Laboratory	07/01/86
D-13	Field Office & Project Site Laboratory	07/01/86

H-01	Type A, B, C and D Catch Basin	07/01/86
H-02	Type A1, B1, C1 and D1 Catch Basin	07/01/86
H-03	Type A2, B2, C2 and D2 Catch Basin	07/01/86
H-04	Typical Reinforcing Details for Catch Basins	07/01/86
H-05	Type A, B and C Storm Drain Manhole	07/01/86
H-06	Type D and E Storm Drain Manhole	07/01/86
H-07	Type F Storm Drain Manhole	07/01/86
H-08	Catch Basin and Manhole Casting	07/01/86
H-09	Type A-9 and A-9P Frames and Grates	07/01/86
H-10	Type A-9B Frames and Grates	07/01/86
H-11	Type 61614 and 61214 Grated Drop Inlet	07/01/86
H-12	Type 61616 Grated Drop Inlet	07/01/86
H-13	61214, 61614 & 61616 Steel Frames and Grates	07/01/86
H-14	61214B Steel Frame and Grates	07/01/86
H-15	61614B Steel Frame and Grates	07/01/86
H-16	Concrete and Cement Rubble Masonry Structures	07/01/86
H-17	Inlet Structures	07/01/86
H-18	Flared End Section for Culverts	07/01/86
H-19	Outlet Structures	07/01/86
H-20	Concrete Spillway Inlet	07/01/86
H-21	18" Slotted C. M. P. Drain	07/01/86
H-22	C. M. P. Coupling Details Standard Joint	07/01/86
H-23	Hat Shaped Coupling Band	07/01/86

Standard Plan No.	Title	Date
TE-01 ●	Miscellaneous Sign Details	07/01/86
TE-02 ●	Galvanized Flanged Channel Sign Post Mounting	07/01/86
TE-03 ●	Galvanized Square Tube Sign Post Mounting	07/01/86
TE-04 ●	Regulatory Signs	r 09/01/87
TE-05 ●	Warning Signs	07/01/86
TE-06 ●	Miscellaneous Signs	r 09/01/87
TE-07	Reserved	07/01/86
TE-08 ●	Construction Signs	r 09/01/87
TE-09	Miscellaneous Intersection Signs	r 03/06/87
TE-10	Reserved	07/01/86
TE-11	Bike Route Sign and Supplementary Plates	07/01/86
TE-12	State Route Marker and Auxiliary Markers	07/01/86
TE-13	Interstate Route Marker	07/01/86
TE-14	State Route Marker and Border Detail for Guide Signs	07/01/86
TE-15	Route Marker Assemblies	07/01/86
TE-16 ●	Miscellaneous Reflector Markers	07/01/86
TE-17	Type II Object Markers	07/01/86
TE-18	Mileposts	07/01/86
TE-19	Reserved	07/01/86
TE-20	Overhead Sign Supports	07/01/86
TE-21	Overhead Sign Support, Box Truss Type, Aluminum	07/01/86
TE-22	Foundation Details and Schedules	07/01/86
TE-23	Destination & Ground Mounted Expressway Signs	07/01/86
TE-24	Breakaway Sign Supports for Ground Mounted Guide Signs	07/01/86
TE-25	Laminated Aluminum Sign Panels (Overhead)	07/01/86
TE-26	Laminated Aluminum Sign Panels (Ground Mounted)	07/01/86
TE-27	Solid Aluminum Extruded Sign Panel and Accessory Details	07/01/86
TE-28	Guide Signs Luminaire Mountings	07/01/86
TE-29	Reserved	07/01/86
TE-30 ●	Raised Pavement Markers and Striping	07/01/86
TE-31 ●	Miscellaneous Pavement Markings	07/01/86
TE-32 ●	Miscellaneous Pavement Markings	r 09/01/87
TE-33 ●	Miscellaneous Pavement Markings	07/01/86
TE-34	Reserved	07/01/86
TE-35	Pavement Alphabets, Numbers & Symbols	07/01/86
TE-36	Pavement Alphabets, Numbers & Symbols	07/01/86
TE-37	Reserved	07/01/86
TE-38	Traffic Signal System, Miscellaneous Details	07/01/86
TE-39	Traffic Signal System, Miscellaneous Details	07/01/86
TE-40	Loop Detectors	r 03/06/87
TE-41	Pullboxes	07/01/86
TE-42	Type III Traffic Signal Standard	07/01/86
TE-43	Concrete Pullbox (2' x 3')	07/01/86
TE-44	Reserved	07/01/86

Standard Plan No.	Title	Date
TE-45	Reserved	07/01/86
TE-46	Reserved	07/01/86
TE-47	Reserved	07/01/86
TE-48	Reserved	07/01/86
TE-49	Reserved	07/01/86
TE-50	Metal Guardrail	r 03/06/87
TE-51	Metal Guardrail	r 09/01/87
TE-52	Metal Guardrail with Rubrail	07/01/86
TE-53	Metal Guardrail with Rubrail at Obstruction	r 09/01/87
TE-54	Beam Type Guardrail with Rubrail at Obstruction (Shoulder Installation)	r 09/01/87
TE-55	Metal Guardrail Connection to Concrete Barrier	r 09/01/87
TE-56	Concrete Barrier Transition	07/01/86
TE-57	Guardrail Type 3, Thrie Beam	r 09/01/87
TE-58	Approach End Flare, One & Two Way Roadway	07/01/86
TE-59	Trailing End Flare, One & Two Way Roadway	r 09/01/87
TE-60	Anchor Block Details	07/01/86
TE-61	Breakaway Cable Terminal (BCT)	r 03/06/87
TE-62	Breakaway Cable Terminal (BCT)	r 09/01/87
TE-63	Guardrail Type 4 (Rigid Barrier)	r 09/01/87
TE-64	Portable Concrete Guardrail	r 03/06/87
TE-65	Guardrail Type 4, Miscellaneous	r 09/01/87
TE-66	Barricades	07/01/86
TE-67	Delineation & Pavement Markings at Bridges	07/01/86
TE-68	Wheelchair Ramps	07/01/86
TE-69	Wheelchair Ramps	r 09/01/87

NOTE:
STANDARD PLANS APPLICABLE TO THIS PROJECT ARE INDICATED BY A "●" NEXT TO THE STANDARD PLAN NO. (D-07●)

09/01/87	REVISED STANDARD PLANS TE-04, TE-06, TE-08, TE-32, TE-51, TE-53, TE-54, TE-55, TE-57, TE-59, TE-62, TE-63, TE-65 & TE-69.
03/06/87	REVISED STANDARD PLANS D-01, TE-09, TE-40, TE-50, TE-51, TE-57, TE-59, TE-61, TE-63 AND TE-64.
DATE	REVISION

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

STANDARD PLANS SUMMARY
KUNIA ROAD RESURFACING
URBAN BOUNDARY TO WILIKINA DR.
PROJECT NO. 7500A-01-00M
Date: Mar., 1988

SHEET NO. 1 OF 1 SHEETS

GENERAL NOTES

FED. ROAD DIST. NO.	STATE	FED. RD. PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7500A-01-88M	1988	3	12

1. The Scope of Work consists of resurfacing with asphalt concrete pavement, cold planing, adjusting manhole and valve box frame & covers, installing pavement reinforcing fabric, traffic signs and pavement markers and striping.
2. All potholes, depressions, cracks and wheel ruts shall be cleaned, then filled and compacted with Asphalt Concrete Pavement Mix No. V preceeding laying of reinforcing fabric. This work shall be measured and paid for as provided under Item No. 401.0500 Asphalt Concrete Pavement Mix No. V.
3. The Contractor's attention is directed to Subsection 107.13- Public Convenience and Safety; Section 645- Traffic Control of the Special Provisions and Subsection 107.21- Contractor's Responsibility for Utility Property and Service for Hawaiian Electric Co., Hawaiian Telephone Co. and the U.S. Army.
4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6. The exact locations and limits or areas to be reconstructed and/or cold planed shall be determined in the field by the Engineer.
7. The Contractor shall remove and dispose of all existing raised pavement markers prior to the overlaying of Asphalt Concrete. This work shall be considered incidental to Asphalt Concrete Pavement Mix No. V and will not be paid for separately.
8. Smooth riding connections shall be constructed at all limits of resurfacing including the beginning and end of project, connecting approaches, side streets and driveways as shown on the plans and/or as directed by the Engineer.
9. The exact limits of resurfacing shall be determined in the field by the Engineer.
10. The Contractor shall notify Mr. Alan Goo of the U.S. Army Engineer District at 655-0762 seven (7) days prior to start of construction for coordinating paving operations in the vicinity of Schofield's Foote and Lyman Gates.
11. The Contractor shall notify Colonel Michael E. Heenan of the U.S. Air Force at 655-1414 seven (7) days prior to start of construction for coordinating operations in the vicinity of Wheeler Field's Kunia Gate.
12. Placement of Reinforcing Fabric will not be required on the transitions at the beginning and end of project.

DATE	_____
SURVEY PLOTTED BY	_____
DRAWN BY	_____
DESIGNED BY	_____
QUANTITIES BY	_____
CHECKED BY	_____
ORIGINAL PLAN	_____
NOTE BOOK	_____
No.	_____

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
GENERAL NOTES
KUNIA RD. RESURFACING Urban Boundary to Wilikina Dr. Proj. No. 7500A-01-88M Date: Mar, 1988
SHEET No. 1 OF 1 SHEETS