


FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7101A-01-04M	2006	18	74

CURB RAMP AND SIDEWALK NOTES:


1. These typical details are intended as curb ramp guidelines for design and construction.
2. A 2% maximum cross slope shall be maintained in the direction of pedestrian traffic.
3. Subject to field conditions, the Engineer shall determine the final location of curb ramps.
4. All pullboxes shall be installed away from the curb ramp and within the sidewalk/unpaved area to the maximum extent feasible.
5. Where necessary, existing pullboxes, handholes, manholes, etc. shall be adjusted to match curb ramp grade. Adjustments shall not be paid for separately but shall be considered incidental to the various curb ramp items unless indicated otherwise.
6. Transitions from ramps to gutters and roadways shall be flush.
7. Curb ramps and sidewalks shall be constructed to eliminate ponding to the maximum extent feasible.
8. The pedestrian push button shall meet operational and reach requirements of the American with Disabilities Act Accessibility Guidelines (ADAAG):
 - a) Forward Reach. The maximum height for forward reach shall be 48".
 - b) Side Reach. The maximum height for side reach shall be 54".
 - c) Operation. Controls and operating mechanisms shall be operable with one hand and shall not require tight grasping, pinching, or twisting of the wrist. The force required to activate controls shall be no greater than 5 lbf.
9. The maximum slopes of adjoining gutters or road surface immediately fronting the curb ramp shall not exceed 5% for Type A and D ramps and 8.33% for Type B, C, and E ramps. The counterslope may be exceeded when the change of grade does not exceed 13% (11% preferred) over a distance of 2 ft. Exceeding the 13% (11% preferred) change in grade will cause a person in a wheelchair to tip forward and/or fall backward.
10. There shall be a 30"x48" level ground surface (2% max. cross slope, both directions) for a forward or side approach, as appropriate, to a pedestrian push button.
11. Construction joints are required to join curb ramps with sidewalks.
12. Unless otherwise noted, new gutters are required as shown.
13. All curb ramps shall be reinforced with 6x6 W1.4/W1.4 welded wire fabric.
14. Surface of sidewalks and curb ramps shall be firm, stable, and slip-resistant. This includes the surfaces of pullboxes, valve covers, manhole covers, etc.
15. Bed course material is required for curb ramps, sidewalks, and gutters.
16. All sidewalks shall provide a minimum clear width of 3'-0" (excluding curb) for pedestrian circulation. If this cannot be met, a minimum 32-inch clear width is allowed for a distance of 24-inches.
17. Passing spaces along new sidewalks with 5' clear width or less shall be provided at maximum 200' intervals as required by ADA guidelines. The passing area shall be a minimum 5' wide by 5' long as feasible.
18. If possible, install utility poles, fire hydrants, light poles, sign posts, pullboxes, etc. off of sidewalk but within the right-of-way.
19. Objects protruding from utility poles and walls adjacent to the sidewalks (i.e. wall mounted fire hydrants, telephones, meters on poles, etc.) shall be mounted to meet the current American with Disabilities Act Accessibility Guidelines (ADAAG) and will be subject to Engineer's approval.
20. If a curb ramp is not constructed according to the plans, the Contractor shall reconstruct the curb ramp at no cost to the State. Construction tolerance for Portland Cement Concrete shall be based on 1/4 inch per 10 ft. (±0.2%). Remedial measures will not be accepted.
21. Additional information is available from:
 - a) American with Disabilities Act Accessibility Guidelines (ADAAG), Jan. 1998, The Access Board.
 - b) Accessible Rights-of-Way: A Design Guide, Nov. 1999, The Access Board.
 - c) Designing Sidewalks and Trails for Access, Part 1, July 1999, FHWA.
 - d) Designing Sidewalks and Trails for Access, Part 2, Sept. 2001, FHWA.

STATE OF HAWAII	
DEPARTMENT OF TRANSPORTATION	
HIGHWAYS DIVISION	
CURB RAMP AND SIDEWALK NOTES	
FARRINGTON HIGHWAY REHABILITATION,	
VICINITY OF OLD FORT WEAVER ROAD	
TO KAMEHAMEHA HIGHWAY	
PROJECT NO.: 7101A-01-04M	
No Scale	Date: July, 2005
SHEET No. 1 OF 6 SHEETS	


FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7101A-01-04M	2006	19	74



TYPICAL CURB RAMPS




PLAN



SECTION "A-A"

CURB RAMP - TYPE "A"
SIDEWALK WIDTH 12'-0" OR GREATER



DETAIL "A"

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

CURB RAMP DETAILS

FARRINGTON HIGHWAY REHABILITATION,
VICINITY OF OLD FORT WEAVER ROAD
TO KAMEHAMEHA HIGHWAY

PROJECT NO.: 7101A-01-04M







Not to Scale Date: July, 2005

SHEET No. 2 OF 6 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
tdl/usr2/traffic/std/curbampa.dgn	CHECKED BY	
tdl/usr2/traffic/std/curbampa.dgn	QUANTITY BY	
tdl/usr2/traffic/std/curbampa.dgn	CHECKED BY	

tdl/usr2/traffic/std/curbampa.dgn R 10-16-00 TE-68

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7101A-01-04M	2006	20	74



CURB RAMP - TYPE "B"
SIDEWALK WIDTH 4'-0" OR GREATER
BUT LESS THAN 6'-0" WIDTH

CURB RAMP - TYPE "B" MODIFIED
SIDEWALK WIDTH 6'-0" OR GREATER
BUT LESS THAN 12'-0" WIDTH

* See Curb Ramp and Sidewalk Note No. 9
** The slope of the ramp shall take precedence over the length of the ramp. If the maximum slope of a ramp cannot be met within a length of 12 feet, then the slope of the ramp shall be set when the length of the ramp is set at the maximum of 12 feet.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION


CURB RAMP DETAILS

FARRINGTON HIGHWAY REHABILITATION,
VICINITY OF OLD FORT WEAVER ROAD
TO KAMEHAMEHA HIGHWAY
PROJECT NO.: 7101A-01-04M


Not to Scale Date: July, 2005

SHEET No. 3 OF 6 SHEETS

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7101A-01-04M	2006	21	74




PLAN




ELEVATION

CURB RAMP - TYPE "C"
USE AT MEDIAN CROSSINGS, ISLANDS




SECTION "A-A"




DETAIL "A"


DETAIL "B"



CURB RAMP - TYPE "C" MODIFIED



CURB RAMP - TYPE "D"



CURB RAMP - TYPE "D" MODIFIED

- * See Curb Ramp and Sidewalk Note No. 9
- ** The slope of the ramp shall take precedence over the length of the ramp. If the maximum slope of a ramp cannot be met within a length of 12 feet, then the slope of the ramp shall be set when the length of the ramp is set at the maximum of 12 feet.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

CURB RAMP DETAILS


FARRINGTON HIGHWAY REHABILITATION,
VICINITY OF OLD FORT WEAVER ROAD
TO KAMEHAMEHA HIGHWAY

PROJECT NO.: 7101A-01-04M

Not to Scale Date: July, 2005

SHEET No. 4 OF 6 SHEETS




FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7101A-01-04M	2006	22	74





CURB RAMP - TYPE "E"
SIDEWALK WIDTH 7'-0" OR GREATER

(TO BE USED ONLY WITH TRAFFIC SIGNAL STANDARD OR PEDESTRIAN PUSH BUTTON PEDESTAL ON TRIANGULAR "ISLAND")


- * See Curb Ramp and Sidewalk Note No. 9
- ** The slope of the ramp shall take precedence over the length of the ramp. If the maximum slope of a ramp cannot be met within a length of 12 feet, then the slope of the ramp shall be set when the length of the ramp is set at the maximum of 12 feet.
- *** The Clearance shall be increased to 6'-0" or wider at areas with high pedestrian traffic or as directed by the Engineer or as shown on the plans.



- * Match width of existing sidewalk whenever possible.
- ** Breakover and departure angles should not exceed 10 degrees or 17%.



DETAIL "A"
NOT TO SCALE
(NEW CONSTRUCTION)



ALTERNATE DETAIL
NOT TO SCALE

DRIVEWAY APRON

- NOTES:**
- For extension to existing driveway, scoring and finish shall match existing scoring and finish. For driveway constructed in built up areas, scoring conforming to scoring at adjacent driveways may be authorized.
 - This detail is only one method for providing ADA access. Other methods can be used. These methods are shown in references listed in Curb Ramp and Sidewalk Note No. 21.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

CURB RAMP DETAILS

FARRINGTON HIGHWAY REHABILITATION,
VICINITY OF OLD FORT WEAVER ROAD
TO KAMEHAMEHA HIGHWAY


PROJECT NO.: 7101A-01-04M

Not to Scale Date: July, 2005


SHEET No. 5 OF 6 SHEETS

R 02-05-02 TE-69 stt. 5 of 6 tdl/usr2/traffic/std/curbampedgn


FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	7101A-01-04M	2006	23	74



Left



Right




Left & Right


PEDESTRIAN PUSH BUTTON WITH SIGN

Man, Arrow & Push Button - White
Background - Black

NOTE:
Arrowhead to be installed
in proper direction.




TYPICAL CROSSWALK STRIPING AT CURB RAMP




NOTE:
All curb ramps shall
be reinforced.


TYPICAL CONSTRUCTION JOINT AT EXISTING SIDEWALK



TYPICAL CROSSWALK STRIPING AT DIAGONAL CURB RAMP



PLAN



ELEVATION

DETAIL - BACK CURB

NOTE:
This detail can be used in situations where the edge of
sidewalk cannot be flush with the face of (back) curb due
to right of way restrictions.

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
MISCELLANEOUS DETAILS
FARRINGTON HIGHWAY REHABILITATION, VICINITY OF OLD FORT WEAVER ROAD TO KAMEHAMEHA HIGHWAY
PROJECT NO.: 7101A-01-04M
Not to Scale Date: July, 2005
SHEET No. 6 OF 6 SHEETS