

ORIGINAL
PLAN

DATE
09/23

SURVEY PLATTED BY
DESIGNED BY
CHECKED BY

NOTED BY
DESIGNED BY
CHECKED BY

NOTED BY
DESIGNED BY
CHECKED BY

NOTED BY
DESIGNED BY
CHECKED BY

NOTED BY
DESIGNED BY
CHECKED BY

TRAFFIC SIGN SUMMARY					
SIGN NO.	MESSAGE	QUANTITY			
		10 SQ. FT. OR LESS		GREATER THAN 10 SQ. FT.	
		W/POST	W/O POST	W/POST	W/O POST
R1-1	STOP	7			
R1-2	YIELD	3			
R2-1(25)	SPEED LIMIT 25		2		
R3-1			1		
R3-2			1		
R3-4			1		
R3-26		1	1		
R3-47		3			
R5-1	DO NOT ENTER SYMBOL	2			
R5-1a	WRONG WAY	1			
R6-1(L)		2	2		
R6-1(R)		1	3		
R7-4	NO STOPPING OR STANDING	3			
R7-12a	LOADING ZONE COMMERCIAL VEHICLES WITH PERMIT ONLY MON-SAT 7AM-4PM EXCEPT HOLIDAYS		2		
R7-107c	NO PARKING HERE TO CORNER	1			
R7-107d	NO PARKING 6AM TO 6PM EXCEPT SUNDAY	1			
R7-107e	NO PARKING 6:30AM TO 8:30AM EXCEPT SAT,SUN,HOL		1		
R7-108e	1 HR PARKING MON THRU SAT 7AM TO 6PM EXCEPT TOW AWAY HRS		1		
R7-108(L)	1 HR PARKING 7AM TO 6 PM	1	2		
R7-108(R)	1 HR PARKING 7AM TO 6 PM		1		
R7-201a			4		
R8-3a		3			
R8-3a(L & R)		2	2		
R8-3a(L)		2	2		
R8-3a(R)		2	1		
R10-5a	LEFT ON LEFT ARROW ONLY		1		
R10-9	RIGHT TURN ON RED AFTER STOP		2		
R10-11a	NO TURN ON RED		1		
R10-12	LEFT TURN YIELD ON GREEN ●		2		
W4-2(R)		1			
W14-1	DEAD END		1		
TOTAL		36	34		

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-7413(1)	1994	18	18

PAVEMENT MARKING SUMMARY	
DESCRIPTION	QUANTITY
PAVEMENT MARKERS	
TYPE A _____	300 EACH
TYPE C _____	230 EACH
TYPE D _____	70 EACH
TYPE H _____	60 EACH
TAPE - TYPE I OR THERMOPLASTIC EXTRUSION	
8-INCH PAVEMENT STRIPE (WHITE) _____	1,300 LIN. FT.
DOUBLE 4-INCH PAVEMENT STRIPE (YELLOW) _____	1,200 LIN. FT.
TAPE - TYPE II OR THERMOPLASTIC EXTRUSION	
4-INCH PAVEMENT STRIPE (WHITE) _____	1,200 LIN. FT.
4-INCH PAVEMENT STRIPE (YELLOW) _____	1,000 LIN. FT.
8-INCH PAVEMENT STRIPE (WHITE) _____	920 LIN. FT.
12-INCH PAVEMENT STRIPE (WHITE) _____	70 LIN. FT.
12-INCH PAVEMENT STRIPE (YELLOW) _____	150 LIN. FT.
DOUBLE 4-INCH PAVEMENT STRIPE (YELLOW) _____	650 LIN. FT.
TAPE - TYPE III OR THERMOPLASTIC EXTRUSION	
4-INCH PAVEMENT STRIPE (WHITE) _____	960 LIN. FT.
4-INCH PAVEMENT STRIPE (YELLOW) _____	80 LIN. FT.
12-INCH PAVEMENT STRIPE (WHITE) _____	460 LIN. FT.
CROSSWALK MARKINGS _____	44 LANE
PAVEMENT ARROW _____	49 EACH
PAVEMENT WORD _____	9 EACH
PAINT	
PAINT CURB (RED) _____	1,380 LIN. FT.
PAINT CURB (YELLOW) _____	40 LIN. FT.

CONSTRUCTION SIGN SUMMARY				
SIGN NO.	LOCATION	MESSAGE	W/POST	W/O POST
CW20-1d	DILLINGHAM BLVD.	ROAD CONSTRUCTION AHEAD	1	
CG20-2	DILLINGHAM BLVD.	END CONSTRUCTION	1	
CW20-1d	SCHOOL ST.	ROAD CONSTRUCTION AHEAD	1	
CW20-1d	LILIHA ST.	ROAD CONSTRUCTION AHEAD	1	
CG20-2	LILIHA ST.	END CONSTRUCTION	1	
TOTAL			5	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TRAFFIC SIGN SUMMARIES

LILIHA STREET RESURFACING
North King Street to H-1 Overpass
Fed. Aid Project No. STP-7413(1)

Not to ScaleDate: Sept. 1993

SHEET No. 79 OF 9 SHEETS