

SECTION 01533 – BARRICADES

PART 1 – GENERAL

1.01 RELATED DOCUMENTS

The General Provisions of the contract, including the General Provisions for Construction Projects (2016), Special Provisions, and General Requirements of the Specifications, apply to the work specified in this section.

1.02 BARRICADES

- A. The contractor shall take precaution to protect people and property from injury and damage. He shall erect barricades to delineate his work areas and provide the appropriate signing, hazard lights, and temporary paint striping as directed by the Engineer, to aid public and airport pedestrian and vehicular traffic around his work areas. Barricades shall be traffic cones, delineators, blinker barricades, caution tape, sawhorses, plywood barricades or other barriers as approved by the Engineer to effectively provide proper protection.
- B. The contractor shall be responsible for his own security and protection of his property, including mobilization yard barricades.
- C. Barricades, in general, shall be neat and in good condition, as required for protection. In areas frequented by the general public, the barricades shall be visually presentable and plywood partitions shall be painted. Where dust is a problem, the Contractor shall erect floor to ceiling dust proof partitions
- D. The Contractor shall coordinate and sequence this work with the Engineer to permit the continuing operation of the existing Airport facility. Barricades shall be removed upon the completion and acceptance of work and the premises left clean and operational.

PART 2 – PRODUCTS (Not Applicable)

PART 3 – EXECUTION (Not Applicable)

PART 4 – MEASUREMENT AND PAYMENT

4.01 BASIS OF MEASUREMENT AND PAYMENT

Work under this section will not be measured nor paid for separately, but shall be considered incidental to and included in the prices bid for the various items of work in this project.

END OF SECTION