

SECTION 01560 - ENVIRONMENTAL CONTROLS

PART I – GENERAL

1.1 RELATED DOCUMENTS

- A. The General Provisions, Special Provisions, and Technical Provisions, apply to the work specified in this section. Special attention is directed to the following Articles:
1. State of Hawaii, Air and Water Transportation Facilities Division, General Provisions for Construction Projects, Article VI, Control of Materials, Paragraph 6.8 Non-Conforming Materials.
 2. State of Hawaii, Air and Water Transportation Facilities Division, General Provisions for Construction Projects, Article VII, Legal Relations and Responsibility to Public, Paragraph 7.14 Pollution Control and Protection of Archeological Historical, and Burial Sites.
 3. State of Hawaii, Air and Water Transportation Facilities Division, General Provisions for Construction Projects, Article VII, Legal Relations and Responsibility to Public, Paragraph 7.17 Contaminated or Hazardous Items and Material; Regulated Items and Material; Waste.
 4. Section 01561 Construction Site Runoff Control Program.
 5. Section 01562 Management of Contaminated Media.
- B. The latest version of the State of Hawaii, Department of Transportation, Airports Division (DOTA) Construction Activities BMP Field Manual.

1.2 ENVIRONMENTAL PROTECTION

With the exception of those measures set forth elsewhere in these specifications, environmental protection shall consist of the prevention of environmental pollution as the result of construction operations under this contract. For the purpose of this specification, environmental pollution is defined as the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare, unfavorably alter ecological balances of importance to human life, affect other species of importance to man, or degrade the utilization of the environment for aesthetic and recreational purposes.

1.3 APPLICABLE REGULATIONS

In order to provide abatement and control of environmental pollution arising from the construction activities of the Contractor and their Subcontractors in the performance of this contract, the work performed shall comply with the intent of all applicable Federal, State, and Local laws and regulations concerning environmental pollution control and abatement, including, but not limited to, the following regulations:

- A. State of Hawaii, Department of Health, Administrative Rules, Chapter 55, WATER POLLUTION CONTROL; Chapter 54, WATER QUALITY STANDARDS.
- B. United States, Environmental Protection Agency, CLEAN WATER ACT; 33 United States Code §1251 et seq.
- C. State of Hawaii, Department of Health, Administrative Rules, Chapter 59, AMBIENT AIR QUALITY, Chapter 60.1, AIR POLLUTION CONTROL.
- D. United States, Environmental Protection Agency, CLEAN AIR ACT; 42 United States Code §7401 et seq.
- E. State of Hawaii, Department of Health, Administrative Rules, Chapter 42, VEHICULAR NOISE CONTROL.
- F. State of Hawaii, Department of Health, Administrative Rules, Chapter 46, COMMUNITY NOISE CONTROL.
- G. State of Hawaii, Occupational Safety and Health Standards, Title 12, Department of Labor and Industrial Relations, Subtitle 8, Division of Occupational Safety and Health, Part 3 Construction Standards, Chapter 145 Asbestos.
- H. Environmental Protection Agency, Code of Federal Regulations Title 40, Part 61, Subpart M (Revised Subpart B), NATIONAL EMISSION STANDARDS FOR AIR POLLUTANTS and Subpart B, NATIONAL EMISSION STANDARDS FOR ASBESTOS; Final Rule dated November 20, 1990.
- I. State of Hawaii, Department of Health, Title 11, Chapter 501, Asbestos Requirements.
- J. U.S. Department of Labor - Occupational Safety and Health Administration (OSHA) Asbestos Regulations, Code of Federal Regulations Title 29, Parts 1910, 1915 and 1926, Occupational Exposure to Asbestos, Final Rule dated August 10, 1994.

1.4 SUBMITTALS

The Contractor shall submit the following items within 30 calendar days after the Notice to Proceed Date:

- A. Submit proposed means, methods, techniques and procedures to be used for environmental control.
- B. Submit a State of Hawaii Department of Health Asbestos Notification of Demolition and Renovation Form for all demolition projects (including facilities which no asbestos is present) and renovation projects per HAR 11-501.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 AIR POLLUTION CONTROL

- A. Emission: The Contractor shall not be allowed to operate equipment and vehicles that show excessive emissions of exhaust gases until corrective repairs or adjustments are made, as determined by the Engineer.
- B. Dust: The Contractor, for the duration of the contract, shall maintain all excavations, embankments, haul roads, permanent access roads, plant sites, waste disposal areas, borrow areas, and all other work areas within or without the project limits free from dust which would cause a hazard to the work or operations of other Contractors, or to persons or property. Industry-accepted methods of stabilization suitable for the area involved, such as sprinkling or similar methods, will be permitted. Chemical or oil treating shall not be used.
- C. Burning on Airport property shall not be permitted.

3.2 WATER POLLUTION CONTROL

- A. Wastes: The Contractor shall not deposit, at the airport site or in its vicinity, solid waste or discharge liquid waste, such as fuels, lubricants, bituminous waste, untreated sewage, and other pollutants which may contaminate the body of ground water.
- B. Spillages: No petroleum products, bituminous materials, or other deleterious substances, including debris, are allowed to fall, flow, leach, or otherwise enter the sewage systems or storm drains. All spills shall be immediately reported by following the instructions found on the Spill Reporting Fact Sheet for the appropriate airport and completing the Spill Reporting Form. The Spill Reporting Fact Sheet and Form can be found at:

<http://hidot.hawaii.gov/airports/doing-business/engineering/environmental/construction-site-runoff-control-program>

Any fines assessed to DOTA, as a result of Contractor's spillages or the Contractor's failure to report spillages, shall be paid by the Contractor.

Reference Specification Section 01562, Paragraph 3.3(C) Release Reporting for additional information and requirements.

- C. Erosion: The Contractor shall provide any necessary temporary drainage, dikes, and similar facilities to prevent erosion damage to the site. Run-off shall be controlled to prevent damage to the surrounding area.

3.3 NOISE CONTROL

- A. At all times keep objectionable noise generation to a minimum by:
1. Equipping air compressors with silencing packages.
 2. Equipping jackhammers with silencers on the air outlet.
 3. Equipment that can be electrically driven instead of gas or diesel is preferred. If noise levels on equipment cannot reasonably be brought down to criteria, listed as follows, either the equipment will not be allowed on the job or use time will have to be scheduled subject to approval of the Engineer.
 4. All construction vehicles and equipment on the project operating between 10:00 p.m. and 7:00 a.m. shall be equipped with an ambient noise sensing variable volume backup alarm system. The system shall be in compliance with Title 29 of the Code of Federal Regulations, Part 1926.601(b)(4)(i).
- B. Objectionable noise received on neighboring properties is defined as any noise exceeding the noise limits of State Regulations (Title 11, Hawaii Administrative Regulations, Department of Health, Chapter 46 – Community Noise Control) or City and County of Honolulu ordinance, as stated below, or as any noise causing a public nuisance in a residential area, as determined by the State and community representatives, or by the nuisance provisions of local ordinances.
1. The noise limitations established are as set forth in the following table after any applicable adjustments provided for herein are applied:

RECEIVING PROPERTY

<u>Noise Source</u>	<u>Residential</u>	<u>Commercial</u>	<u>Industrial</u>
Airport	50 dBA	65 dBA	70 dBA

2. Between the hours of 6:00 pm to 5:00 am on weekdays and weekends, the noise limitations above may be exceeded for any receiving property by no more than:
 - a. Five dBA for a total of 15 minutes in any one hour period; or
 - b. Ten dBA for a total of 5 minutes in any one hour period; or
 - c. 15 dBA for a total of 1.5 minutes in any one hour period.
- C. In addition to the noise controls specified, demolition and construction activities conducted within 1,000 feet of residential areas may have additional noise controls

required.

- D. The Contractor and its subcontractor operations shall, at all times, comply with all State of Hawaii and City and County of Honolulu requirements.
- E. For work conducted within Airport buildings, noise levels from work activities shall not exceed 85 dBA on the slow scale at the project boundary.

3.4 DISPOSAL

Construction waste, such as crates, boxes, building materials, pipes, and other rubbish shall be properly disposed of at a licensed landfill. Please consult with the local landfill to ensure that objects meet the specific landfill's requirements for size, type, etc. Other areas or methods proposed by the Contractor will be approved only if the Engineer determines that their effect on the environment is equal to or less than those described herein.

3.5 HAZARDOUS MATERIALS CONTROL

- A. The use of hazardous materials, i.e., asbestos and PCB, in the construction of this project shall be strictly prohibited. Any corrective action to remove and replace the hazardous material and contaminated work shall be at the sole expense of the Contractor.

B. DEFINITIONS

1. HAZARDOUS SUBSTANCE – Any substance designated pursuant to Section 311(b)(2)(A) of the Clean Water Act; any element, compound, mixture, solution, or substance designated pursuant to Section 102 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA); any hazardous waste having the characteristics identified under or listed pursuant to Section 3001 of the Solid Waste Disposal Act; any toxic pollutant listed under Section 307(a) of the Clean Water Act; any hazardous air pollutant listed under Section 112 of the Clean Air Act, as amended (42 U.S.C. §§7401-7626); any imminently hazardous chemical substance or mixture regulated under Section 7 of the Toxic Substances Control Act, as amended (15 U.S.C. §§2601-2671), oil, trichloro propane, and any other substance or pollutant or contaminant designated by rules adopted pursuant to this chapter (Chapter 128D, Hawaii Revised Statutes)
2. OIL – Oil Waste of any kind or in any form, including, but not limited to, petroleum, fuel oil, sludge, oil refuse, oil mixed with waste, crude oil or any faction or residue.
3. POLLUTANT OR CONTAMINANT – Any element, substance, compound, or mixture, which after release into the environment and upon exposure, ingestion, inhalation, or assimilation into any organism either directly from

the environment or indirectly by ingestion through food chains, will or may reasonably be anticipated to cause death, disease, behavioral abnormalities, cancer, genetic mutation, physiological malfunctions (including malfunctions in reproduction) or physical deformation, in such organism or their offspring.

PART 4 – MEASUREMENT AND PAYMENT

4.1 BASIS OF MEASUREMENT AND PAYMENT

All work specified in this Section shall not be measured nor paid for separately but shall be considered incidental to item 01561, Construction Site Runoff Control Program.

END OF SECTION