



Cat's Claw Vine

Gold Trees

Claw Vine

- 1 1/2" Angle Control Valve
- 1" Angle Control Valve

Shrubbery Type Sprinkler

Finished Ground—

Feeder-7

Shoulder

Finished Ground—

Sprinkle

Feeder

SECTION THRU FEEDER
SHOWING SPRINKLER
Scale: $1\frac{1}{2}" = 1'-0"$

278	+80	Lin. Ft.	¾"	Galvanized Wrought Iron Pipe
600	-610	"	1 "	"
510	-530	"	1½"	"
9	-10	"	2 "	"
64	-72	"	2½"	"
130	+34	"	3 "	"
65	-63	— 	Underground Half-Circle Lawn Type Sprinkler Heads, Buckner No. 400 AH	
	12	— 	Part-Circle Rotary Pop-Up Sprinklers ⅛" Nozzle , Buckner No. 1290 ½	
	3	— 	Full - Circle " , Buckner No. 1290	
	1		1" Angle Control Valve ,	Buckner No. 51
	1	— 	1½"	, Buckner No. 53
	2		2 "	, Buckner No. 54
281	-875		Cat's Claw Vine ,	Bignonia Ungus - Cati , cover over fill slopes , plants spaced 4' o.c.
	G		Gold Tree ,	Tabebuia Donnell - Smithii , spaced as shown
3400	-3200	Sq. ft.	Bermuda Grass ,	Cynodon Dactylon , cover over shoulder areas

DETAIL OF SHRUBBERY TYPE SPRINKLER
Scale: $1\frac{1}{2}" = 1'-0"$

Scale: $1\frac{1}{2}" = 1'-0"$

Cover _____

Lock Cap —

Finished Ground

Angle

DETAIL OF ANGLE CONTROL
VALVE HOUSING AND CAP

TERRITORIAL HIGHWAY DEPARTMENT
TERRITORY OF HAWAII
SPRINKLER SYSTEM &
LANDSCAPING PLAN
RAMP U-1
MAUKA ARTERIAL
PROJECT NO. U-59(3) Unit 2

Scale: 1" = 20' Nov., 1953

SHEET NO OF SHEETS

5681.06

EX-11-1