

GENERAL NOTES

1. The scope of work for this project consists of installing cable restraining units, reinforced concrete blocking at abutments and footings, and fiber wrapping columns for Lunalilo-Vineyard Off-Ramp, Makiki Viaduct and Palama Separation.
2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3. The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 104.04 - Maintenance of Traffic; Subsection 104.11 - Night Work; Subsection 104.12 - Noise Control; Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property and Services; and Section 645 -Traffic Control.
4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic and to avoid any conflict with the daily activities of the various businessess beneath Makiki Viaduct and Palama Separation.
5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6. The Contractor shall notify in writing, the Oahu Transit Services, Inc. Roads Supervision Office, 811 Middle St., Hon., HI 96819 (ph. #848-4571) seven (7) days prior to any retrofitting operations.
7. The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting retrofitting operations.
8. The Contractor shall erect construction warning signs in accordance with the latest version of the MUTCD or as directed by the Engineer.
9. The Contractor is reminded to perform all work for Lunalilo-Vineyard Off-Ramp and Makiki Viaduct at night as described in the Special Provisions: Subsection 104.11 - Night Work.
10. Removal and disposal of existing concrete curb and gutter, curb, sidewalk, asphalt concrete pavement, chain link fence, concrete median barrier, and any debris shall be considered incidental to various contract items.
11. Provide smooth transition where new sidewalk construction meets the existing grade or sidewalk.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	BR-HI-1(225)	2000	3	37

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	12-3-99
delgrace	CC/B. Yeh	
mihlogn	QUANTITIES BY	
N.	CHECKED BY	

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
GENERAL NOTES
INTERSTATE ROUTE H-1
<i>Seismic Retrofit for Lunalilo-Vineyard Off-Ramp, Makiki Viaduct and Palama Separation</i>
<i>Federal Aid Project No. BR-HI-1(225)</i>
Date: Aug., 1999
SHEET No. 1 OF 1 SHEETS