

1 **SECTION 602 – Reinforcing Steel**
2

3 Make the following amendments to said Section:
4

5 **(I)** Amend **602.03(D) – Placing and Fastening** by adding the following after
6 line 114:
7

8 ‘When placing welded-wire fabric (WWF), comply with the
9 recommendations of ACI 302.1R, “Guide for Concrete Floor and Slab
10 Construction”. WWF must not be laid on the ground and “pulled up” after the
11 concrete is placed or “walked in” after placing the concrete or using small piles of
12 fresh concrete. Use supports tied to the WWF, e.g., precast concrete spacer
13 blocks to maintain the proper elevation of the WWF. Plastic spacers must not be
14 used. The number of precast concrete spacer blocks must be used in a quantity
15 that will prevent sagging, bending and will maintain the required clearances.”
16

17 **(II)** Amend **602.04 – Measurement** and **602.05 – Payment** to read as follows:
18

19 **“602.04 Measurement.** The Engineer will not measure reinforcing steel.
20

21 **602.05 Payment.** The Engineer will not pay for the accepted reinforcing
22 steel separately. The Engineer shall consider the cost for the accepted
23 reinforcing steel as included in the contract price of the various contract items.
24 The cost is for the work prescribed in this section and the contract documents.”
25
26
27
28
29
30

END OF SECTION 602