

1 **SECTION 641 – HYDRO-MULCH SEEDING**
2

3 Make the following amendments to said Section:
4

5 **(I)** Amend **Subsection 641.02(A) – Seed** by adding sentence to read after
6 line 31:

7
8 “Hydro-mulch seeding shall be Common Bermuda.”
9

10 **(II)** Amend **Subsection 641.02(B) – Fertilizer** by revising the section from
11 line 33 to 36 to read:

12
13 **“(B) Fertilizer.** Proper fertilizer shall be used in hydro-mulch mix,
14 depending on condition of soil. Apply at rates and in amounts consistent
15 with manufacturer’s specifications. Contractor shall provide a Soil Analysis
16 Report, if requested by Engineer, and shall use report to determine
17 quantity and ratio of fertilizer for sustained growth of grass. Submit
18 recommendations from a licensed Landscape Architect when deviating
19 from the application rates and amounts above.”
20

21
22 **(III)** Amend **Subsection 641.03(A) – Seeding** by revising the first paragraph
23 from line 100 to 103 to read:

24
25 **“(A) Seeding.** Apply seeded mulch within the timeframe in Subsection
26 209.03(B) Construction Requirements, if temporary stabilization will not be
27 utilized, after completion of slopes or portion of slope when exposed face
28 attains height of 15 feet. Notify Engineer not less than 24 hours ahead of
29 hydro-mulch seeding operation. Do not hydro-mulch until the Engineer
30 inspects and accepts areas for planting.”
31

32 **END OF SECTION 641**
33