

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20
- 21
- 22
- 23
- 24
- 25
- 26
- 27
- 28
- 29
- 30
- 31
- 32
- 33
- 34
- 35
- 36
- 37
- 38
- 39
- 40
- 41
- 42
- 43

(I) Amend **712.07(A)** **Frame and Cover** from line 98 to line 112 to read as follows:

(II) Amend **712.07(B) Frame and Grate** from line 114 to line 132 to read as follows:

Reinforcing steel for grate shall conform to Subsection 709.01 - Reinforcing Steel. Frame and grate shall be cleaned thoroughly and painted on all sides that will not be imbedded in concrete with one coat of high-grade asphalt conforming to ASTM A 849, Class M, Fully Coated, at shop. Second coat of paint shall be applied on all sides not imbedded in concrete just before the pre-final inspection. Any damage to the zinc-coating of a frame or grate shall be repaired in accordance with ASTM A780 using a Zinc-based solder coating.

Fabricated frame and grate shall be true to line and free of twists, bends, and open joints. Splices will not be allowed. Cut surfaces and edges shall be made smooth by machining or grinding before fabrication of frame and grate.

Size and length of weld shall be as specified in contract documents. Welds shall be free of defects, discontinuities and shall have full penetration.”

NH-H1-1(271)
712-1a

3/30/06