

1 **SECTION 645 - WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to the said Section:

4
5 **(I) Amend Subsection 645.03 - Construction** by revising the sentence
6 on lines 60 and 61 to read:

7
8 "Furnish, install, and maintain barricades, signs, cones, delineators,
9 lights, flashing signals, six (6) advisory signs, two electronic message boards
10 (126 inches wide and 76 inches high), advertisements, and other traffic
11 control devices as required by the Engineer."

12
13 **(III) Amend Subsection 645.03(F) - Lane Closures** by revising lines 248
14 to 251 to read:

15
16 **(F) Lane Closures.**

17
18 "Lane closures will be allowed only in one direction on the
19 Interstate Freeway H-1 (Eastbound and Westbound) and the same
20 number of lanes can be closed on the Highway under the area of
21 work during the following hours:

22
23 **(1) Eastbound (Excluding Ramps).**

24
25 **a) Three Lanes Open:**

26		
27	Sunday	Midnight to Midnight
28		
29	Monday	Midnight to 4:30 A.M.
30		
31	Friday	9:00 P.M. to Midnight
32		
33	Saturday	Midnight to Midnight
34		

35 **b) Two Lanes Open:**

36		
37	Sunday	Midnight to Midnight
38		
39	Monday	Midnight to 4:30 A.M.
40		
41	Friday	10:00 P.M. to Midnight
42		
43	Saturday	Midnight to 9:00 A.M.
44		
45	Saturday	6:00 P.M. to Midnight
46		

(2) Westbound (Excluding Ramps).

a) Three Lanes Open:

Sunday Midnight to Midnight

Friday 9:00 P.M. to Midnight

Saturday Midnight to Midnight

b) Two Lanes Open:

Sunday Midnight to Midnight

Friday 10:00 P.M. to Midnight

Saturday Midnight to 9:00 A.M.

Saturday 6:00 P.M. to Midnight

(3) Ramps.

a) One Lane Open:

Sunday Midnight to Midnight

Monday Midnight to 4:30 A.M.

Friday 9:00 P.M. to Midnight

Saturday Midnight to Midnight

The Contractor shall maintain a 10-foot minimum lane open for all the ramps at all times.

The Contractor shall temporarily close off area to vehicular and pedestrian traffic directly below the viaduct structure while deck demolition is in progress. The cost to install all necessary traffic control and pedestrian safety measures shall not be paid for separately and shall be considered incidental to the various contract items.

The Contractor shall coordinate with the Highways Division, Kaneohe Field Office No. 2 at telephone number 233-5430, 20 working days prior to any work affecting the Zipper Lane. The Zipper Lane deployment is approximately from 1:00 A.M. to 12:00 P.M.

93 The Zipper Lane Deployment Area (ZLDA) shall be free of debris
94 during the project duration.

95
96 The Contractor shall be responsible for any costs associated with the
97 Zipper Lane deployment beyond its normal operations.

98
99
100 A Night Work Noise Variance application for this project had been
101 submitted to the Department of Health.

102
103 The Contractor shall coordinate lane closures with adjacent projects at
104 no increase to the contract price or contract time. One project in the
105 vicinity is the Interstate Route H-1 Freeway Rehabilitation, Middle Street to
106 Vicinity of Ward Avenue, Project No. IM-H1-1(269).

107
108 Exceptions to the lane closure hours specified shall require a written
109 request 10 working days for the Engineer's approval prior to any adjustments
110 specified.

111
112 No time extension will be given for the above restrictions. The
113 contract time for the project has accounted for any loss of time due to the
114 above restrictions."

115
116
117
118
119 **END OF SECTION 645**