

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
202.0420	Removal of Existing Concrete Swale	147	SY	\$ _____	\$ _____
202.0430	Removal of PCC Shoulder	340	SY	\$ _____	\$ _____
205.0100	Structure Excavation for Barrier/Retaining Walls	50	CY	\$ _____	\$ _____
205.0200	Structure Backfill for Barrier/Retaining Walls	25	CY	\$ _____	\$ _____
209.0100	Installation, Maintenance, Monitoring, and Removal of BMP	LS	LS	LS	\$ _____
209.0200	Additional Water Pollution, Dust, and Erosion Control	FA	FA	FA	\$ 25,000.00
301.1000	Hot Mix Asphalt Base Course	246	Ton	\$ _____	\$ _____
304.0100	Aggregate Base	395	CY	\$ _____	\$ _____
401.1000	HMA Pavement, Mix No. IV	7,250	Ton	\$ _____	\$ _____
415.0150	Cold Planing	81,300	SY	\$ _____	\$ _____
421.0000	High Friction Surface Treatment (with Modified Epoxy or Polymer Binder or Equivalent)	2,072	SY	\$ _____	\$ _____
503.0100	Concrete for End Post at Site 1B	20	CY	\$ _____	\$ _____
503.0200	Concrete for End Post at Site 8A	3	CY	\$ _____	\$ _____
503.0300	Concrete for Drainage system	57	CY	\$ _____	\$ _____
507.7001	Concrete End Post for Type I End Post Retrofit	20	EA	\$ _____	\$ _____
507.7002	Concrete End Post for Site 8B	1	EA	\$ _____	\$ _____

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
602.0100	Reinforcing Steel for End Post at Site 1B	1,300	LB	\$ _____	\$ _____
602.0200	Reinforcing Steel for End Post at Site 8A	300	LB	\$ _____	\$ _____
603.0010	Bed Course Material for Culvert	68	CY	\$ _____	\$ _____
603.0400	Clean Existing Culverts	FA	FA	FA	\$ 25,000.00
603.0500	Field Adjustment for Culverts	FA	FA	FA	\$ 66,400.00
603.1010	24-Inch Reinforced Concrete Pipe, Class III or 24-Inch High-Density Polyethylene Pipe, Type S	615	LF	\$ _____	\$ _____
604.0370	Type A Storm Drain Manhole, 8.00 feet to 8.99 feet	1	EA	\$ _____	\$ _____
604.2340	Type 61616 Grated Inlet, 6.0 feet to 6.99 feet	1	EA	\$ _____	\$ _____
604.2350	Type 61214P Grated Inlet, 6.00 feet to 6.99 feet	3	EA	\$ _____	\$ _____
604.2351	Type 61214P Grated Inlet, 7.00 feet to 7.99 feet	1	EA	\$ _____	\$ _____
606.0100	Transition Section Type End Post Connection Upgrade	24	EA	\$ _____	\$ _____
606.0200	Transition Section Type MASH Strong Post Thrie-Beam Transition (Westbound Sta. 375+93+- to Sta. 375+87+-)	1	EA	\$ _____	\$ _____
606.0300	Guardrail Type 31" W-Beam Guardrail with Standard 8" Offset Block (Westbound Sta. 375+87+- to Sta. 374+23.50)	164	LF	\$ _____	\$ _____
606.0400	End Anchorage Type Trailing-End Anchorage System (Westbound Sta. 374+23.50 to Sta. 374+00+-)	1	EA	\$ _____	\$ _____
612.0100	Grouted Rubble Paving	11	CY	\$ _____	\$ _____
615.1000	12-Inch Milled Rumble Strip, Shoulder	96,910	LF	\$ _____	\$ _____
629.1000	4-Inch Pavement Striping (Profile Thermoplastic)	228,800	LF	\$ _____	\$ _____

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
629.1001	4-Inch Pavement Striping (Type I Tape or Thermoplastic)	18,710	LF	\$ _____	\$ _____
629.1002	White 4-Inch Pavement Striping (Type II Tape or Thermoplastic)	130,370	LF	\$ _____	\$ _____
629.1003	Yellow 4-Inch Pavement Striping (Type II Tape or Thermoplastic)	105,990	LF	\$ _____	\$ _____
629.1004	4-Inch Pavement Striping (Type III Tape or Thermoplastic)	7,310	LF	\$ _____	\$ _____
629.1005	8-Inch Pavement Striping (Type I Tape or Thermoplastic)	6,830	LF	\$ _____	\$ _____
629.1006	8-Inch Pavement Striping (Type II Tape or Thermoplastic)	27,200	LF	\$ _____	\$ _____
629.1007	12-Inch Pavement Striping (Type II Tape or Thermoplastic)	10,950	LF	\$ _____	\$ _____
629.1008	Double 4-Inch Pavement Striping (Type I Tape or Thermoplastic)	370	LF	\$ _____	\$ _____
629.1009	Pavement Arrow (Paint, Type I Tape, or Thermoplastic)	37	EA	\$ _____	\$ _____
629.1010	Pavement Word (Paint, Tape, Type I Tape or Thermoplastic)	49	EA	\$ _____	\$ _____
629.1011	Pavement Symbol (Paint, Tape, Type I Tape or Thermoplastic)	7	EA	\$ _____	\$ _____
629.1012	Type A Pavement Marker	1,390	EA	\$ _____	\$ _____
629.1013	Type C Pavement Marker	11,190	EA	\$ _____	\$ _____
629.1014	Type H Pavement Marker	2,680	EA	\$ _____	\$ _____
632.1000	Milepost Marker with Post	31	EA	\$ _____	\$ _____
645.1000	Traffic Control	LS	LS	\$ _____	\$ _____

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
645.2000	Additional Police Officers, Additional Traffic Control Devices, and Advertisement	FA	FA	FA	\$ 100,000.00
648.1000	Field-Posted Drawings	LS	LS	LS	\$ _____
656.0100	Drilling Holes and Installing Dowel Reinforcing Bars for Barriers and Retaining Walls	500	EA	\$ _____	\$ _____
695.1000	Furnish, Transport, Install, Maintain, Relocate, and Remove Portable Concrete Barrier	150	EA	\$ _____	\$ _____
695.2000	Portable Concrete Barrier End Treatment (NCHRP 350 Compliant)	15	EA	\$ _____	\$ _____
699.1000	Mobilization (Not to Exceed 6 Percent of the Sum of All Items Excluding Bid Price of this Item)	LS	LS	LS	\$ _____
a. SUM OF ALL ITEMS					\$ _____
NOTE: Bidders must complete all unit prices and amounts. Failure to do so may be grounds for rejection of bid.					

1 **PROPOSAL SCHEDULE**

2
3 The bidder is directed to Subsection 105.16 – Subcontracts.

4
5 The bidder's attention is directed to Section 699 - Mobilization for the
6 limitation of the amount bidders are allowed to bid.

7
8 If the bid price for any proposal item having a maximum allowable bid
9 indicated therefore in any of the contract documents is in excess of such a
10 maximum amount, the bid price for such proposal item shall be adjusted to reflect
11 the limitation thereon. The comparison of bids to determine the successful
12 bidder and the amount of contract to be awarded shall be determined after such
13 adjustments are made, and such adjustments shall be binding upon the bidder.