

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	I-HI-1(176)	1982	3	20

	M-35	M-36	N-79	HL-1
Δ	19°46'05"	0°41'57.5"	20°03'127"	72°30'00"
R	1909.86'	8500.00'	1800.00'	75.00'
T	658.94'	103.74'	630.00'	54.99'
L	332.78'	51.87'	318.26'	94.90'

TRUE NORTH
Scale: 1"=20'

MF @ Sta. 208+61.35 (BK) Lt.
Install 6" Underdrain and Cleanout
For Details, See Sheet No. _____

MF @ Sta. 207+50± Lt. to MF @ Sta. 209+75± (BK) Lt.
Install 162.5 Lin. Ft. of Guard Rail, Type 3-
Single and 62.5 Lin. Ft. of Guard Rail,
Type 3-Single with Rub Rail on Steel Post.
For Details, See Standard Details.

MF @ Sta. 209+75± (BK) Lt.
End Guard Rail with
Type A Flare

MF @ Sta. 207+50± Lt.
Type G Flare

Begin Transition
Ramp N Sta. 10+10

End Transition
Ramp N Sta. 12+00

Guard Rail
with Rub Rail

Exist. 6" Underdrain Cleanout

OUTBOUND LANES MOANALUA FREEWAY

INBOUND LANES

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

PLAN
IMPROVEMENTS TO RAMP N
INTERSTATE ROUTE H-1
HALAWA INTERCHANGE
F.A.I. PROJ. NO. I-HI-1(176)

Scale: As Shown Date: _____

SHEET NO. 3 OF 3 SHEETS

ORIGINAL PLAN	SURVEY PLATTED BY	DATE
NOTED BY	DRAWN BY	
DESIGNED BY	TRACED BY	
QUANTITIES BY		
CHECKED BY		

