FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR		TOTAL SHEETS
HAWAII	HAW.	H1E-01-92M	1992	3	6

GENERAL NOTES

- 1. This project consists of repairing spalls, restriping and installing pavement markers.
- 2. The Contractor is reminded of the requirements of Subsection 108.01 Subletting of Contract, to perform with his organization, work amounting to not less than 50 percent of the total contract cost less deductible amounts allowed.

 Non-compliance with this Subsection may be grounds for rejection of bids.
- 3. The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 Public Convenience and Safety, Subsection 107.21 Contractor's Responsibility for Utility Property and Services, and Section 645 Traffic Control.
- 4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
- 5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
- 6. The exact locations and limits of areas for spall repairs shall be determined in the field by the Engineer.
- 7. The Contractor shall notify the Mass Transit Line, Inc. Operations Office at 527-6397 seven (7) days prior to any repairing operations.
- 8. The Contractor shall notify the State in writing, two (2) weeks prior to starting repairing operations.

LEGEND

Spall location

Existing Light Standard

Existing Deck Storm Drain
Frame and Grate

O Existing 48" Ø Column

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

INTERSTATE ROUTE H-1
PEARL CITY VIADUCT REPAIRS
PROJECT NO. H1E-01-92M

Date: Dec., 1991

SHEET No. 1 OF 1 SHEETS