

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HIE-01-94M	1994	3	27

GENERAL NOTES

1.

The scope of work for this project consists of reconstructing weakened pavement areas, cold planing, striping, and signing and installing pavement markers.
2.

The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3.

The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property And Services; and Section 645 -Traffic Control.
4.

At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5.

The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6.

The exact locations and limits or areas to be reconstructed and cold planed shall be determined in the field by the Engineer.
7.

The Contractor shall notify in writing, the Oahu Transit Services, Inc. Roads Supervision Office, 811 Middle St., Hon., HI 96819 (ph. #848-4571) seven (7) days prior to any paving operations.
8.

The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting paving operations.
9.

The Contractor shall remove and dispose of all existing raised pavement markers prior to the overlaying of Asphalt Concrete. This work shall be considered incidental to Asphalt Concrete Pavement, Mix No. IV and will not be paid for separately.
10.

All holes, depressions and wheel ruts shall be filled and compacted with Asphalt Concrete Pavement, Mix No. V prior to resurfacing. This work will be paid for under Asphalt Concrete Pavement, Mix No. IV.
11.

Smooth riding connections shall be constructed at all limits of resurfacing, including the beginning and end of project, connecting approaches as shown on the plans and/or as directed by the Engineer.
12.

Dressing of shoulder shall consist of clearing, grubbing, grading, reshaping and compacting the unpaved shoulders with suitable material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.
13.

Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.
14.

All saw cutting work shall be considered incidental to Excavation for Reconstruction of Weakened Pavement Areas.

15.

Striping, installing pavement markers and signing work includes exception areas. See Pavement Marking and Striping Plans.

LEGEND

- Reconstruction Areas
- Cold Planing Areas
- Resurfacing Limits
- dd

Existing Deck Drain
- gdi

Existing Grated Drain Inlet
- cb

Existing Catch Basin
- p

Existing Traffic Sign
- slpb

Existing Highway Lighting Standard Pull Box
- sls

Existing Highway Lighting Standard

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	12-17-94
NOTE BOOK	TRACED BY	
	QUANTITIES BY	
N	CHECKED BY	

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

RTE. H-1 INBOUND SHLDR. LANE RESURF.  
Waiawa Interchange On-Ramp to  
Moanalua Off-Ramp  
Project No. HIE-01-94M

Date: Nov., 1993