## GENERAL NOTES

- 1. The scope of work for this project consists of repairing expansion joints, cold planing and resurfacing with asphalt concrete pavement.
- 2. The Contractor is reminded of the requirements of Subsection 108.01 Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
- 3. The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 Public Convenience and Safety; Subsection 107.21 Contractor's Responsibility For Utility Property And Services; and Section 645 -Traffic Control.
- 4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
- 6. The exact locations and limits or areas to be filled with leveling course, and/or cold planed shall be determined in the field by the Engineer.
- 7. The Contractor shall notify in writing, the Oahu Transit Services, Inc. Roads Supervision Office, 811 Middle St., Hon., HI 96819 (ph. #848-4571) seven (7) days prior to any paving operations.
- 8. The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting paving operations.
- 9. The Contractor shall remove and dispose of all existing raised pavement markers prior to the overlaying of Asphalt Concrete. This work shall be considered incidental to Asphalt Concrete Pavement, Mix No. IV and will not be paid for separately.
- 10 All holes, depressions and wheel ruts shall be filled and compacted with Asphalt Concrete Pavement, Mix No. IV prior to resurfacing. This work will be paid for under Asphalt Concrete Pavement, Mix No. IV.
- 11. Smooth riding connections shall be constructed at all limits of resurfacing, including the beginning and end of project, as shown on the plans and/or as directed by the Engineer.
- 12. Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.
- 13. The Contractor shall provide for access to and from all existing side streets at all times.
- 14. All pavement striping and pavement markers including adhesives shall be replaced. The Engineer will not pay for these items separately. The Engineer will consider the prices for them included in the contract unit price for Asphalt Concrete Pavement, Mix No. IV.
- 15. All saw cutting work shall be considered incidental to Cold Planing.

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR			
HAWAII	HAW.	H1I-01-97M	1997	3	6	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

## GENERAL NOTES

INTERSTATE ROUTE H-1
KEEAUMOKU STREET SEPARATION
Repair Expansion Joints and Resurface Deck

Project No. H11-01-97M

Date: Nov., 1996

SHEET No. 1 OF 1 SHEETS